



320100038P

Open field

AMENDED PLANS RECEIVED

DATE 22/2/10

New 3.0m high galvanised steel palisade fencing to be provided to the extent of the service yard to latest SSL specification

New 2.5m high galvanised steel personnel/security gates

Proposed Rear Extension

SERVICE YARD

External transformer with fence surround

New scissor lift with canopy over

New 2.5m high galvanised steel personnel and vehicular access gates

SUPERMARKET

Flat roofed side extension

Shopfront extension/infill below existing overhanging roof

Shopfront extension/infill below existing overhanging roof

ATMs

Customer Entrance Lobby

Shopfront canopy

CUSTOMER CAR PARK

Proposed covered trolley corral

12No Disabled parking bays

Proposed covered trolley corral

7No Parent & Child parking bays

External steel hoops for trolley storage

Bus/Taxi Pick-up Point

Bus turning circle

RECYCLING CENTRE

Garage (Ireland's Ltd)

Existing low wall with signage

Existing store totem sign

INGLEWHITE ROAD

ISABELLA STREET

NOTES
Drawing data derived/reproduced from survey and Ordnance Survey data as indicated below

DO NOT SCALE FROM THIS DRAWING.
VERIFY ALL DIMENSIONS AND SETTING OUT ON SITE
NOTIFY ANY DISCREPANCIES TO THE ARCHITECT
FOR STRUCTURAL INFORMATION, REFER TO
STRUCTURAL ENGINEER'S DRAWINGS.
FOR M&E INFORMATION, REFER TO M&E ENGINEER'S
AND SUB-CONTRACTOR'S DRAWINGS.
FOR HEALTH & SAFETY INFORMATION, REFER TO
HEALTH & SAFETY RISK ASSESSMENTS

THIS DRAWING CONSISTS OF THE
FOLLOWING SURVEY DATA & PROPOSALS:

ORDNANCE SURVEY CROWN COPYRIGHT,
LICENCE NUMBER 100020449

Additional site information added by HCD from
photographs & aerials.

1:250
0 5 10 15 20 25
m

PARKING NUMBERS

Standard Parking Spaces	133
Disabled Parking Spaces	12
Parent & Child Parking Spaces	7
Total Customer Car Parking	152
Staff Parking (adjacent Recycling)	4
New covered trolley bays	4

PROVIDE NEW TARMAC SURFACE TO
PROPOSED WORKS IN CAR PARK; REPAIR
EXISTING KERB AS NECESSARY. PROVIDE
NEW CAR PARK LAYOUT AND SPECIALIST
BAYS AND WALKWAYS AS SHOWN. ALL
NEW ROAD MARKINGS TO BE APPLIED AS
WHITE THERMOPLASTIC PAINT, UNLESS
OTHERWISE STATED, IN ACCORDANCE
WITH BS EN 1463-1:1998.

TOTAL NET SALES - 1143m²

NET FLOOR AREA OF REAR EXTENSION - 174m²

TOTAL GROSS EXTERNAL FLOOR AREA - 2302m²

REVISION C BY: MJ/S DATED: 19/02/2010
Two additional mobility spaces added as per Highway Authority request.
Re-issued for planning.
REVISION B BY: S.C. DATED: 15/02/2010
Updated to incorporate proposed customer toilet extension to east face of shopfront/age.
REVISION A BY: S.C. DATED: 20/01/2010
Updated to topographical survey, rec'd 14 Jan 2010 and added personnel and vehicular access gates to service yard.
REVISION 1 BY: MJ/S DATED: 12/01/2010
INITIAL ISSUE

PLANNING

PLAN DATE:



for
Sainsbury's

CLIENT:

STORE ACQUISITION 2234
INGLEWHITE ROAD, LONGRIDGE

PROJECT:

PROPOSED SITE PLAN

DESIGN:
DRAWN BY: MJ/S/OSurvey SCALE: 1:250 @ A1 DATE: JAN 2010

Hodfield Cawkwell Davidson

17 Brookgrove Rd, Sheffield, S10 2LZ. T 0114 266 8181 F 0114 266 6246 www.hcd.co.uk
Architecture | Engineering | Interior Design | Masterplanning | Urban Design
ARCH / 2009-073 / 6410
S:\Arch\2009\2009-073\Drawing\Plan\Store\2234_2234_Plan.dwg (12/01/2010)