


320100038P



AMENDED PLANE RECEIVED

DATE 17/02/10

Open field

New 3.0m high galvanised steel palisade fencing to be provided to the extent of the service yard to latest SSL specification

New 2.5m high galvanised steel personnel/security gates

Proposed Rear Extension

SUPERMARKET

SERVICE YARD

External transformer with fence surround

New scissor lift with canopy over

New 2.0m high galvanised steel personnel and vehicular access gates

Shopfront extension/infill below existing overhanging roof

Shopfront extension/infill below existing overhanging roof

Customer Entrance Lobby

ATMs

Bus / Taxi Pick-up Point

RECYCLING CENTRE

Garage (Ireland's Ltd)

Existing low wall with signage

INGLEWHITE ROAD

CUSTOMER CAR PARK

10 No Disabled parking bays

7 No Parent & Child parking bays

External steel hoops for trolley storage

Existing store totem sign

Proposed covered trolley corral

Proposed covered trolley corral

Proposed covered trolley corral

Proposed covered trolley corral

NOTE:
Drawing data derived/reproduced from survey and Ordnance Survey data as indicated below.

DO NOT SCALE FROM THIS DRAWING.
VERIFY ALL DIMENSIONS AND SETTING OUT ON SITE.
NOTIFY ANY DISCREPANCIES TO THE ARCHITECT.
FOR STRUCTURAL INFORMATION, REFER TO STRUCTURAL ENGINEER'S DRAWINGS.
FOR M&E INFORMATION, REFER TO M&E ENGINEERS AND SUB-CONTRACTOR'S DRAWINGS.
FOR HEALTH & SAFETY INFORMATION, REFER TO HEALTH & SAFETY RISK ASSESSMENTS.

THIS DRAWING CONSISTS OF THE FOLLOWING SURVEY DATA & PROPOSALS:

ORDNANCE SURVEY CROWN COPYRIGHT,
LICENCE NUMBER 100020449.

Additional site information added by HCD from photographs & aerials.

1:250
0 5 10 15 20 25
m

PARKING NUMBERS

Standard Parking Spaces	137
Disabled Parking Spaces	10
Parent & Child Parking Spaces	7
Total Customer Car Parking	154
Staff Parking (adjacent Recycling)	4
New covered trolley bays	4

PROVIDE NEW TARMAC SURFACE TO PROPOSED WORKS IN CAR PARK; REPAIR EXISTING KERB AS NECESSARY. PROVIDE NEW CAR PARK LAYOUT AND SPECIALIST BAYS AND WALKWAYS AS SHOWN. ALL NEW ROAD MARKINGS TO BE APPLIED AS WHITE THERMOPLASTIC PAINT, UNLESS OTHERWISE STATED, IN ACCORDANCE WITH BS EN 1463-1:1998.

TOTAL NET SALES - 1143m²

NET FLOOR AREA OF REAR EXTENSION - 174m²

TOTAL GROSS EXTERNAL FLOOR AREA - 2302m²

PROPOSED BY: J.C. CHECKED: DATE: 15/02/2010
Updated to incorporate proposed customer toilet extension to east face of shopfront stage.
PROPOSED BY: J.C. CHECKED: DATE: 20/01/2010
Updated to topographical survey, rect'd 14 Jan 2010 and added personnel and vehicular access gates to service yard.
REVIEWED BY: MJS. CHECKED: DATE: 12/01/2010
MINOR ISSUE

PLANNING

PLANNING DATE:



LONGCROSS
Construction Ltd

for
Sainsbury's

STORE ACQUISITION 223A
INGLEWHITE ROAD, LONGRIDGE

PROJECT:

PROPOSED SITE PLAN

DRAWING BY: MJS/O/Survey SCALE: 1:250 @ A1 DATE: JAN 2010

Hadfield Cawkwell Davidson

17 Broadmore Rd, Sheffield, S10 2LZ. T 0114 266 8181 F 0114 236 6246 www.hcd.co.uk

Architecture | Engineering | Interior Design | Masterplanning | Urban Design
ARCH / 2009-073 / 6410 / B