



- 12 Existing opening extended.
- 13 New sections of walls / partitions.
- 14 New door opening formed.
- 15 Existing door opening infilled.
- 16 Section of wall cut back.
- 17 New section of partition to Bathroom increasing Landing area.
- 18 New Bathroom formed with new dormer.
- 19 Existing door opening to Bedroom repositioned.
- 20 Part window opening infilled and new opening formed into new Bedroom area.
- 21 Window opening to Kitchen extended.

- 22 Window to Bedroom 2 repositioned.
- 23 Shower removed, new sections of walls constructed forming cupboard.
- 24 Wood burning stove.
- 25 Stainless steel flue to wood burning stove.
- 26 New loft access hatch.
- 27 Timber frame side wall with Cedar cladding as extension forming garden / bin store. Boarded door access front and rear.
- 28 Roof extended down over side path to form storage area. NOTE:- Gutter not to project over boundary line.

Materials

- 1 Cedar clad walls to rear extension.
- 2 Powder coated aluminium cladding to steel framework / balcony edge.
- 3 Timber fascia, barge and soffit boards.
- 4 Stainless steel and glass balustrade to balcony.
- 5 Stainless steel and obscure glass (to local authority approval) to both sides of balcony - min height 2000mm.
- 6 Powder coated aluminium framed windows and sliding doors.
- 7 Tile roof finish to match existing.
- 8 Powder coated aluminium gutters and rain water pipes.
- 9 Cedar clad walls to existing and extended dormer.
- 10 New pitched roof to existing / extended dormer with steel lead finish or lead effect liquid plastic weathering system.
- 11 Tarmac drive area widened to 7.6M to form 3no car parking bays (drained to garden area).

Window to garden room repositioned.
REV C Balcony added with obscure glass balustrade / screen to both sides 12-12-11
REV B Balcony omitted glazing configuration amended 2-11-11
REV A Design amendments 24 NOV 2011

Client
Mr and Mrs Walton
Job Title
Proposed Alterations
20 The Hazels
Salesbury
320111057P

Drawing Title
Proposals

Scale
1:100 at A1
Date
NOV 2011
Drawn
DL

spa ARCHITECTS
SUNDERLAND PEACOCK & ASSOCIATES LTD.
HAZELWIRE, PEACOCK ROAD, CLITHEROE,
LANCASHIRE, BT7 2AG
T 01206 820774 F 01206 827238
E info@sunderlandpeacock.com
www.sunderlandpeacock.com

4199 = 02C

