

Langho Football Club

Proposed FencingScale 1:250

3m high 'Twinbar' fencing to all sides of pitch with 2 single leaf gates and 1 double leaf gate finished galvanised and green powder coated

4 No 1Heras fencing to be installed at the base of the proposed base of slope. Slope to be no greater than 1:5

Maintenance gate to be used as main access o facility. Left hand gate to be locked at all times and only unlocked for maintenance purposes. Right hand gate to be locked when facility is not being used.


Maintenance access to be constructed with 6f2 and covered with excavated topsoil to a depth of 100mm. Temporary maintenance gates to be locked at all times during construction.

Pedestrian access to be fenced using heras fencing for construction period only.

Key:




2m high security fencing to be installed to perimeter to contractors site. To be removed on completion.



3m high ball stop fencing,twin bar with 1.2m high super rebound panel; painted in Ral 6005 (Moss Green)

320120225P



ThorntonContracts

THIS DRAWING & THE INFORMATION CONTAINED THEREIN IS CONFIDENTIAL. COPYRIGHT & THE EXCLUSIVE PROPERTY OF THORNTON CONTRACTS LTD, WHO OWN & MAINTAIN ALL MASTERS. IT MAY NOT BE REPRODUCED WITHOUT THE WRITTEN PERMISSION OF THORNTON CONTRACTS LTD OR ITS AGENT. REFER TO THORNTON CONTRACTS LTD FOR CONDITIONS & PROVISION OF DRAWINGS, INCLUDING DISC COPIES.

ALTHAM INDUSTRIAL ESTATE
ALTHAM
LANCASHIRE BB5 5TU
Tel: 01282 777345
Fax: 01282 777654

PROJECT
LANGHO FOOTBALL CLUB
DEWHURST ROAD, LANGHO, BB6 8AF

DRAWING TITLE
LAYOUT PLAN
PROPOSED FLOODLIT SYNTHETIC TURF PITCH

DRAWN	MLS	DATE	16.01.12	SCALE	AS SHOWN
APPROVED	-	DATE	-	FILE NAME	-
DRAWING No: 11336-03-004				REV	0

REVISION	B	-	REVISION	C	-	REVISION	D	-	REVISION	E	-	REVISION	F	-	REVISION	G	-	REVISION	H	-	REVISION	J	-	REVISION	K	-	DRAWING STATUS
PRELIMINARY																											