

SD 63 NW

LONGRIDGE

DIXON ROAD

7/124

6.11.49

Sharley Fold

II

House, '1619 I A S' on lintel. Sandstone rubble with stone slate roof. 2 storeys. To the right of the modern porch is a 3-light double-chamfered mullioned window with hood. At the far left of the facade, beyond a modern window, is a similar window. On the 1st floor are 2 3-light rebated and chamfered mullioned windows, with a 2-light chamfered window to the right of the porch. The studded plank door, with chamfered surround and triangular head, is now within the porch. Gable stacks, the right-hand one being of stone. Wing at rear, with an outshut against its south-west wall.

SD 63 NW

LONGRIDGE

HIGHER ROAD

7/125

27.10.71

Nos. 6 to 44

[Formerly listed as Nos 4 to 44
(even)]

II

Row of houses, begun in 1793. Squared coursed sandstone with slate roof and brick stacks, except that on the gable (left-hand) wall of No. 44. 2 storeys with cellars entered at lower ground level to the rear. Windows have plain reveals and projecting stone sills, with modern windows. Each house is of one bay, with the doors of adjacent houses paired, with a third door, leading through a tunnel to the yard, between them. The doorways have plain stone surrounds. Some of the houses now have an extra window on the 1st floor over the door. Nos. 6, 8 and 44 have stone gutter brackets. A keyed joint between No. 24 and 26 indicates a break in construction. Built by the Longridge Building Society, one of the earliest terminating building societies in the country, and used as an example by Price, Seymour J., Building Societies, their Origin and History, Cambridge, 1958, pp 32-44.
