© Site Engineering Personnel Limited 2012
Reproduction in whole or in part by any means is prohibited without the prior permission of Site Engineering Personnel Limited.

PLAN GRID NORTH

LEGEND

AV	AIR VALVE	MH	MANHOLE
BOL	BOLLARD	MKR	MARKER
BH	BORE HOLE	MS	MILE STONE
BH	BH	MP	MONITORING POINT
	BUSH	MP	MAIN PLATE
		PO	POST
BS	BUS STOP	PO	POST OFFICE BOX
CT	CABLE TV CONST	RW	RAINWATER PIPE
CB	CONTROL BOX	RL	RIDGE LEVEL
DR	DRAIN	RS	ROAD SIGN
	DRIP LINE	RE	ROODING EYE
EB	EARTH BOD	SP	SIGN POST
EL	EAVES LEVEL	ST	STATION
EC	ELEC INSPECTION COVER	TC	TELECOM COVER
EP	ELECTRICITY POLE	TP	TELEGRAPH POLE
FH	FIRE HYDRANT	TCB	TELEPHONE CALL BOX
FP	FLAG POLE		TIE WIRE
GV	GAS VALVE/TAP	BO	TRAFFIC BOLLARD
	GATE	TL	TRAFFIC LIGHT
GP	GATE POST	LB	TRAFFIC LIGHT BOX
	GULLY		TREE
IC	INSPECTION COVER		
	INVERT LEVEL		
KO	KERB OUTLET		
LP	LAMP POST	WLB	TRC1 EARTH
LH	LITTERBOY	WM	WATER METER
MH	MANHOLE	WO	WATER OUTLET
SH	MANHOLE	WV	WATER STOP VALVE/TAP

	HEDGE		PALISADE
			BARB WIRE
			BARBED WIRE
			SONIC PANEL
			POST AND WIRE
			POST AND RAIL
			IRON RAIL
			CLOSE BOARDED
			CHAIN LINK
			WATER COURSE
			KERB
			FENCE
			SURFACE CHANGE
			DRAINAGE CHANNEL
			WALL
			TOP BANK
			BOTTOM BANK
			BUILDING
			BUILDING CANOPY
			OVER HEAD ELECTRICAL
			OVER HEAD TELECOM
			HEDGE

32013011 3P

SUPPLY CH NODES			
Name	Easting	Northing	Height
SEP1	375847.972	434915.134	76.701
SEP2	375843.767	434917.184	76.703
SEP3	375842.567	434917.587	76.713
SEP4	375841.367	434917.990	76.723
SEP5	375838.966	434918.793	75.886
SEP6	375836.565	434919.595	75.792
SEP7	375834.165	434920.398	75.699
SEP8	375817.161	434926.091	69.171
SEP9	375814.761	434926.893	69.077
SEP10	375809.960	434928.495	68.889
SEP11	375807.560	434929.297	68.795
SEP12	375805.159	434930.100	68.701
SEP13	375802.759	434930.902	68.607
SEP14	375800.358	434931.705	68.513
SEP15	375797.958	434932.507	68.419
SEP16	375795.557	434933.310	68.325
SEP17	375793.157	434934.112	68.231
SEP18	375790.756	434934.915	68.137
SEP19	375788.356	434935.717	68.043
SEP20	375785.955	434936.520	67.949
SEP21	375783.555	434937.322	67.855
SEP22	375781.154	434938.125	67.761
SEP23	375778.754	434938.927	67.667
SEP24	375776.353	434939.730	67.573

All levels relate to O.S Datum. Established using the Leica Smartnet GPS Network.
Orientation to a OS Grid.

SITE ENGINEERING PERSONNEL LTD
SURVEY & ENGINEERING PROJECTS
AND SPECIALISTS IN SITE INVESTIGATION, TOPOGRAPHICAL SURVEY, BUILDING SURVEYING, NEW ENGINEERS, UTILITY CONTRACTS

Client
HARGREAVES CONTRACTING LIMITED
234-236 St. GEORGES ROAD
BOLTON
BL1 2PH

Project Title
TOPOGRAPHICAL SURVEY:
PETRE WOOD
LANGHO

Scale	Date	Job No
1:200@A0	JUNE 2012	07203-T-01
Surveyed: AN	Drawn: RW	Checked: CS

Survey & Engineering Projects, 19 Derby Lane, Hulme Manor, Lancashire, M40 8LJ
T: (0161) 709620 F: (0161) 7251941 W: www.sepro.com E: info@sepro.com