





SIGN ELEVATIONS

SIGN 1

2795 OVERALL LENGTH

LLOYDS BANK

300

SIGN 2

900

600

700

600

700

SIGN 3

EXISTING ILLUMINATED MERCHANDISING UNIT IN WINDOW TO REMAIN IN SITU WITH DARK GREEN ACRYLIC FRAME TO BE REPLACED WITH NEW 'BRIGHT GREEN' ACRYLIC. NEW COMMUNICATION MATERIAL WILL BE INSTALLED AND POSTER AREA WILL REMAIN ILLUMINATED AS EXISTING.

SIGN 4

297

594

Digitally printed self adhesive vinyl opening hours/statutory signage reverse applied to inside of glazing

SIGN 5

200

300

Folded aluminium name plate with pushed through stainless steel letters and vinyl graphic to face.

GENERAL SPECIFICATION

INDIVIDUAL LETTERS - GREEN FACES

K

300 CAP HEIGHT

Internally illuminated lettering, returns fabricated from aluminium powdercoated 'Darker Core Green' with 'Core Green' acrylic faces, which will illuminate.

Letters will be fixed directly to building.

Darker Core Green

PMS ref: 7483c

Core Green

Acrylic ref: 692

INTERNALLY ILLUMINATED 'HERITAGE' PROJECTING SIGN

Horse logo

Internally illuminated projecting sign. Logo section manufactured from folded aluminium powdercoated White with 'Bright Green' returns. 'Horse' logo is shoulder cut opal acrylic with digitally printed self adhesive vinyl applied to face. Logo section will sit in an aluminium frame powdercoated silver. Sign will illuminate via LED's.

Bright Green

PMS ref: 375c

© Copyright 2013 Merson Signs Ltd.

PLEASE REFER TO SIGN MANUAL FOR INDIVIDUAL SIGN SPECIFICATION

50450795-CLITHEROE, 7 CHURCH STREET, CLITHEROE, LANCASHIRE, BB7 2DD

SCALE @ A3: NTS

REV C

ALL SIZES ARE IN MILLIMETRES