

Initial Arboricultural Impact Assessment

in Relation to Proposed Construction of Agricultural Access Track



Chadswell Hall, Chaigley, Lancashire BB7 3LT

Prepared by:

Bowland C Tree Consultancy Ltd December 2015

CONTENTS

- 1. TREE SURVEY SCHEDULE FOR ARBORICULTURAL IMPACT APPRAISAL & BS5837:2012 TABLE 1
- 2. TEMPORARY PROTECTIVE FENCING SPECIFICATION
- 3. TREE IMPACT PLAN

Contact Details

Bowland Tree Consultancy Ltd 7 Lakeland Close Billington Lancashire BB7 9LN

T: 01254 825098 E: info@bowlandtreeconsultancy.co.uk



TREE SURVEY SCHEDULE FOR ARBORICULTURAL IMPACT APPRAISAL Site: Chadswell Hall, Chipping Road, Chaigley, Lancashire, BB7 3LT Agent for Client: Gary Hoerty Associates

Surveyor:	Jennie Keighley MSc		
Survey Date:	17 July 2015		Page
Job Ref:	BTC909		

Page: 1 of 2

No.	Species	Height	Stem Diam.		Branch Spread	Branch & Canopy Clearances	Life Stage	PC	General Observations and Comments	Management Recommendations	ERC	Cat. Grade	RPA (m²)	RPA Radius (m)
T1	Sycamore	17	920	E S	8 8 8 8	2-N 2	М	G	Bifurcates at a height of 3m.Basal epicormics.	Protect RPA throughout development.	40+	A1/2	383	11.04
T2	Sycamore	23	900	E S	5 8 9.5 6	4-S 2	М	G	 Seven well established suckerlings around base up to 120mm stem diameter. Crown heavily biased south. 2m long split/wound on significant eastern branch. Several 100mm diameter branch failures and removals. Ivy has been removed and stacked around base. 	 Retain in context of proposed development. Ensure protection of Root Protection Area (RPA) throughout construction using temporary protective fencing to produce a Construction Exclusion Zone (CEZ) (see appendices). 	40+	A1	366	10.8
тз	Hybrid Black Poplar	29	950	Е	9 12 9 11	2-W 1	Μ	М	 Significant leader on western side at a height of 2m. Showing signs of a moderate reduction in vitality. Limb lost from top of crown. 	 Retain in context of proposed development. Ensure protection of RPA throughout construction using temporary protective fencing to produce a CEZ. 	40+	B1	408	11.4
T4	Sycamore	28	1200		12 9 6 7	2 3	М	М	 Numerous pruning wounds on southern side where cut away from power line. Some partially occluded, some not. Basal epicormics. Aerial roots on northern side. Trifurcates at a height of 2m. Locally notable status. 	 Retain in context of proposed development. Ensure protection of RPA throughout construction using temporary protective fencing to produce a CEZ. 	40+	A1	651	14.4
Т5	Beech		1200#	E S	12 13 8 5	1.5-E 1	Μ	G	 Located on neighbouring land and, therefore, not inspected in detail. Western crown reaches 6m into field. On boundary verge above ditch to the east. Veteran status. 	 Retain in context of proposed development. Ensure protection of RPA throughout construction using temporary protective fencing to produce a CEZ. 	40+	A1/3	651	14.4

Headings and Abbreviations:

Headings and Abbreviations:		
No.	Allocated sequential reference number - Tree ('T'), Group ('G'), Woodland (W') or Hedge ('H') reference number - refer to plan and to numbered tags where applicable	
Species:	Common name	
Height:	In metres, to nearest half metre – where possible approximately 80% are measured using an electronic clinometer and the remainder estimated against the measured trees. In the case of Groups and Woodlands the measurement listed is that of the highest tree	
Stem Diam .:	Stem diameter in millimetres, to nearest 10mm - measured and calculated as per Annex C of BS5837:2012. MS = multi-stemmed, TS = twin-stemmed	
Branch Spread:	Crown radius measured (or estimated where considered appropriate) from the four cardinal points (north, east, south and west) to give an accurate visual representation of the crown	
Branch & Canopy Clearances:	Existing height above ground level, in metres, of first significant branch and direction of growth (e.g. 2.5-N) and of canopy at lowest point – to inform on crown to height ratio, potential for shading, etc.	
Life Stage:	Estimated age class - Y = young, SM = semi-mature, EM = early-mature, PM = post-mature	
PC:	Physiological Condition - a measure of the tree'(s)' overall vitality, i.e. D = Dead, MD = Moribund, P = Poor, M = Moderate, G = Good	
General Observations and Comments:	Comments relating to the tree'(s)' overall condition and any other pertinent factors including structural defects, current and potential direct structural damage, physiological decline, poor form, etc.	
Management Recommendations:	Either Preliminary or In Consideration of the Proposal - In the case of Arbonicultural Constraints Surveys the recommended management works only take exiting site and tree circumstances and conditions into account and not proposed developments. Arbonicultural Impact Assessment and I	Method Statement related
-	Surveys take the proposed development into consideration with recommendations made accordingly. More than one option may be given if considered appropriate	
ERC:	Estimated Remaining Contribution - in years as per BS5837:2012 (i.e. <10, 10+, 20+, 40+)	
Cat. Grade:	Category Grading - tree retention value listed as U, A, B or C - in accordance with BS5837:2012 Table 1	
RPA m ² :	Root Protection Årea in m ² - calculated area around the tree that must be appropriately protected throughout the development process in order avoid root damage	Bowland C
RPA Radius (m):	Root Protection Area Radius - in metres measured from the centre of the stem to the line of tree protection	
# (Estimated Dimensions):	Where trees are located off-site, or are inaccessible for any other reason, and accurate measurements or other information cannot be taken then the information provided is estimated and is duly suffixed with a "#" symbol	Tree Consultancy Ltd
. ,		

TREE SURVEY SCHEDULE FOR ARBORICULTURAL CONSTRAINTS APPRAISAL Site: Chadswell Hall, Chipping Road, Chaigley, Lancashire, BB7 3LT Gary Hoerty Associates Agent for Client:

Surveyor:	Jennie Keighley MSc	
Survey Date:	17 July 2015	Page: 2 of 2
Job Ref:	BTC909	

No.	Species	Height	Stem Diam.	Brar Spre	hear	Branch & Canopy Clearances	Life Stage	PC	General Observations and Comments	Management Recommendations	ERC	Cat. Grade	RPA (m²)	RPA Radius (m)
Т6	Sycamore	24	600#	N 5 E 7 S 7 W 6		1-E 1	EM	G	 Dense basal epicormics render stem inaccessible. Located in hedge H2. 	 Retain in context of proposed development. Ensure protection of RPA throughout construction using temporary protective fencing to produce a CEZ. 	40+	A1	163	7.2
Τ7	Holly	11	1x430 1x400 (ts)	N 2 E 2 S 5 W 3		0.5-E 0	PM		 Moderate dieback in northern crown. Stem and branches heavily galled throughout. On verge, with raised buttresses. 	 Protect RPA throughout development. 	10+	C1	156	7.05
G1	2no. Ash, 1no. Blackthorn, 1no. Hawthorn	≤ 10	≤ 1x170 1x130 2x110 (ms)	N ≤ ≤ S ≤ ≤ W ≤	2	0.5-E ≥1	Y-SM	М	 Very closely spaced group. One of sub-stems on eastern Ash bifurcates at a height of 1m with included bark union. Another bifurcating sub-stem has decay spreading from union up stems. 	 Retain in context of proposed development. Ensure protection of RPA throughout construction using temporary protective fencing to produce a CEZ. 	10+	C1	≤ 32	≤ 3.17
G2	21no. Sycamore, 11no. Scots Pine, 3no. Ash, 3no. Green Alder, 3no. Swamp Cypress, 2no. Elder, 2no. Hawthorn, 2no. Damson	≤ 4	≤ 200	N ≤ ≤ ≤ S W ≤	2	0.5 ≥ 0	Y-SM	M-G	 Widely spaced group. One Scots Pine to the west has failed at base. 	 Remove one/two trees as necessary from south-east corner of group in order to construct access track as proposed. Ensure protection of RPA of remainder of group throughout construction using temporary protective fencing to produce a CEZ. 	40+	C1	≤ 18	≤ 2.4
H1	Holly, Hawthorn, Blackthorn, Hazel, Elder, Ash	≤ 2	≤ 6x50 (ms)	≤ 1 wi		N/A ≥ 0	SM	G	 Managed roadside hedge. 	 Remove approximately 15m length of hedge to form access at road frontage as proposed. Relocate a further approximately 60m length of hedge into a set-back position to allow for required visibility splay. Protect RPA of remainder of hedge throughout development. 	20+	C1	N/A	1.47
H2	Hawthorn, Elder	≤ 3	≤ 6x50 (ms)	≤ 2 w		N/A ≥ 0	EM	М	 Outgrown, previously laid boundary hedge 	 Remove one section, approximately 5m in length, to form access to existing track as proposed. Protect RPA of remaining hedge throughout development. 	20+	C1/2	N/A	1.47



Category and definition	Criteria (including subcategories where app	ropriate)		Identification on plan						
Trees unsuitable for retention (see Note)										
Category U Those in such a condition that they cannot realistically be retained as living trees in the context of the current land use for longer than 10 years	 Trees that have a serious, irremediable, st that will become unviable after removal of cannot be mitigated by pruning) Trees that are dead or are showing signs of Trees infected with pathogens of significar suppressing adjacent trees of better qualit Note: Category U trees can have existing or poparagraph 4.5.7. 	Red								
	1. Mainly arboricultural qualities	2. Mainly landscape qualities	3. Mainly cultural values, including conservation							
Trees to be considered for retention	on									
Category A Trees of high quality with an estimated remaining life expectancy of at least 40 years	Trees that are particularly good examples of their species, especially if rare or unusual; or those that are essential components of groups or formal or semi-formal arboricultural features (e.g. the dominant and/or principal trees within an avenue)	Trees, groups or woodlands of particular visual importance as arboricultural and/or landscape features	Trees, groups or woodlands of significant conservation, historical, commemorative or other value (e.g. veteran trees or wood-pasture)	Green						
Category B Those of moderate quality and value: those in such a condition as to make a significant contribution. A minimum of 20 years is suggested.	Trees that might be included in the high category, but are downgraded because of impaired condition. Examples include the presence of remediable defects including unsympathetic past management and minor storm damage	Trees present in numbers, usually as groups or woodlands, so they form distinct landscape features which attract a higher collective rating than they might as individuals. But which are not, individually, essential components of formal or semi-formal arboricultural features. For example, trees of moderate quality within an avenue that includes better, A category specimens. Or trees which are internal to the site, therefore individually having little visual impact on the wider locality	Trees with clearly identifiable conservation or other cultural benefits	Blue						
Category C Those trees of low quality and value: currently in adequate condition to remain until new planting could be established - a minimum of 10 years is suggested - or young trees with a stem diameter below 150 mm	Trees not qualifying in higher categories Note – Whilst C category trees will usually not to trees with a stem diameter of less than 150mm	Trees present in groups or woodlands, but without this conferring on them significantly greater landscape value, and/or trees offering low or only temporary screening benefit be retained where they would impose a significant of	Trees with very limited conservation or other cultural benefits constraint on development, young	Grey						

BS5837:2012 Table 1 – Cascade Chart for Tree Quality Assessment



DISCLAIMER

Survey Limitations: Unless otherwise stated all trees are surveyed from ground level using non-invasive techniques. The disclosure of hidden crown and stem defects, in particular where they may be above a reachable height or where trees are ivy clad or in areas of ground vegetation, cannot therefore be expected. All obvious defects, however, are reported. Detailed tree safety appraisals are only carried out under specific written instructions. Comments upon evident tree safety relate to the condition of said tree at the time of the survey only.

Unless otherwise stated all trees should be re-inspected annually in order to appraise their on-going mechanical integrity and physiological condition. It should, however, be recognised that tree condition is subject to change, for example due to the effects of disease, decay, high winds, development works, etc. Changes in land use or site conditions (e.g. development that increases access frequency) and the occurrence of severe weather incidents are also significant considerations with regards tree structural integrity and trees should therefore be re-assessed in the context of such changes and/or incidents and inspected at intervals relative to identified and varying site conditions and associated risks.

Where trees are located wholly or partially on neighbouring private third-party land then said land is not accessed and our inspection is therefore restricted to what can reasonably be seen from within the site. Stem diameters of trees located on such land are estimated. Any subsequent comments and judgments made in respect of such trees are based on these restrictions and are our preliminary opinion only. Recommendations for works to neighbouring third-party trees are only made where a potentially unacceptable risk to persons and/or property has been identified during our survey. Where significant structural defects of third-party trees are identified and associated management works are considered essential to negate any risk of harm and/or damage then we will first attempt to inform the site occupier of the issues and, if not possible, then inform the relevant Council. Where a more detailed assessment is considered necessary then appropriate recommendations are set out in the Tree Survey Schedule.

Where tree stem locations are not included on the plan(s) provided then they are plotted at the time of the survey using, where appropriate and/or practicable, a combination of measurement triangulation and GPS co-ordination. Where this is not possible then locations are estimated. Restrictions in these respects are detailed in the report.

The tree survey and any report information provided is intended as a guide to identify key tree related constraints to site development only. As such, the potential influence of trees upon existing or proposed buildings or other structures resulting from the effects of their roots abstracting water from shrinkable load-bearing soils is not considered herein. The tree survey information in its current form should not therefore be considered sufficient to determine appropriate foundation depths for new buildings. Accordingly, an updated survey, with reference to the current NHBC Standards Chapter 4.2 - Building Near Trees, must therefore be prepared for the specific purpose of informing suitable foundation depths subsequent to planning approval being granted. The advice of a structural engineer must also be sought with regard to appropriate foundation depths for new buildings.

Copyright & Non-Disclosure Notice: The content and layout of this report are subject to copyright owned by Bowland Tree Consultancy Ltd, save to the extent that copyright has been legally assigned to us by another party or is used by Bowland Tree Consultancy Ltd under license. This report may not be copied or used without our prior written agreement for any purpose other than those indicated.

Third Parties: Any disclosure of this document to a third party is subject to this disclaimer. The report was prepared by Bowland Tree Consultancy Ltd at the instruction of and for use by our client, as named. This report does not in any way constitute advice to any third party who is able to access it by any means. Bowland Tree Consultancy Ltd excludes to the fullest extent lawfully permitted all liability whatsoever for any loss or damage arising from reliance on the contents of this report.

- TEMPORARY PROTECTIVE FENCING SPECIFICATION -

Construction Exclusion Zones (CEZs), enclosed by **Temporary Protective Fencing**, as detailed below and to be agreed with the Local Planning Authority (LPA), shall:

- be retained in place throughout the development process, as specified in the 'Temporary Protective Fencing Construction' section below and detailed in BS5837:2012 Figure 2 (overleaf);
- 2. be sited in the area(s) defined by the Root Protection Areas on the associated Tree Plan;
- 3. be erected prior to any construction, demolition or excavation works and remain in place for the duration of the project;
- 4. preclude any delivery of site accommodation and/or materials and/or plant machinery;
- preclude all construction related activity, with the sole exception of specified arboricultural works and any other works to be carried out under supervision that have been agreed by all parties; and
- 6. preclude the storage of all development related materials and substances including fuels, oils, additives, cement and/or any other deleterious substance.

Any incursion into CEZs must be by prior arrangement, following consultation with the LPA.

Temporary Protective Fencing Construction

- 1. Temporary protective fencing panels shall be weldmesh "Heras" panels of at least 2.0 metres in height.
- 2. The panels shall butt together and be securely fixed to a scaffold framework, as per 3 to 5 below.
- 3. The scaffold framework shall comprise of upright poles of at least 3.0 metres in length driven no less than 0.6 metres into the ground at maximum 3.0 metre centres with horizontal and diagonal poles fixed to the uprights, as per 4 to 5 below.
- 4. The two horizontal rail poles shall be attached to the uprights at heights of 0.6 and 1.8 metres with 3 no. clamps to each joint.
- 5. The diagonal scaffold pole struts be clamped to the top rail of the scaffold framework at a 45° angle and extend back into the CEZ and clamped to a 0.7 metre length of scaffold tube that shall be driven no less than 0.5m into the ground.
- 6. No fixing shall be made to any tree and all possible precautions shall be taken to prevent damage to tree roots when locating posts.
- 7. A 600mm x 300mm warning sign reading "TREE PROTECTION AREA KEEP OUT" (see Figure 1, below) shall be fixed to every 10.0 metre length of protective fencing.
- 8. On completion and prior to any demolition or construction works, site preparation, excavation or delivery of plant and materials, the Consulting Arboriculturist shall inspect the Temporary Protective Fencing.

Figure 1: CEZ Warning Sign

– TREE PROTECTION AREA –
KEEP OUT!
(TOWN & COUNTRY PLANNING ACT 1990)
THE TREES ENCLOSED BY THIS FENCE ARE PROTECTED BY PLANNING
CONDITIONS AND/OR SUBJECTS OF A 'TREE PRESERVATION ORDER', THE
CONTRAVENTION OF WHICH MAY LEAD TO CRIMINAL PROSECUTION
THE FOLLOWING <u>MUST</u> BE OBSERVED BY <u>ALL</u> PERSONNEL:
 THE PROTECTIVE FENCING MUST <u>NOT</u> BE MOVED
 NO PERSON SHALL ENTER THE CONSTRUCTION EXCLUSION ZONE
NO MACHINE, PLANT OR VEHICLES SHALL ENTER THE EXCLUSION ZONE
• NO MATERIALS SHALL BE STORED IN THE EXCLUSION ZONE
NO SPOIL SHALL BE DEPOSITED IN THE EXCLUSION ZONE
 NO EXCAVATION SHALL OCCUR IN THE EXCLUSION ZONE
 NO FIRES SHALL BE LIT IN THE EXCLUSION ZONE
ANY INCURSION INTO THE EXCLUSION ZONE MUST BE WITH THE
WRITTEN PERMISSION OF THE LOCAL PLANNING AUTHORITY






Figure 2: BS5837:2012 Default specification for protective barrier


6. Standard scaffold clamps

Figure 3: BS5837:2012 Examples of above-ground stabilising systems









	KEY
	T = Individual Tree
	G = Group of Trees
	H = Hedge
	Please refer to associated Tree Survey Schedule for specific details in respect of items below:
	Tree Categorisations:
	Those to be Considered for Retention:
	Category 'A' Tree/Group/Hedge Those of a High Quality with an Estimated
	Remaining Life Expectancy of at Least 40 Years
	Category 'B' Tree/Group/Hedge Those of a Moderate Quality with an
	Estimated Remaining Life Expectancy of at Least 20 Years
	Category 'C' Tree/Group/Hedge
	Category C Theerorouph heage Those of Low Quality with an Estimated Remaining Life Expectancy of at Least 10
	Years, or Young Trees
	Those Considered Unsuitable for Retention:
	Category 'U' Tree/Group/Hedge Those in Such a Condition that they Cannot
	Realistically be Retained as Living Trees in the Context of the Current Land Use for
	Longer Than 10 Years
	Note: The locations of individual trees, groups, hedges were not included on the topographical site survey plan provided, and
	their locations were subsequently plotted by the arboricultural surveyor at the time of the survey using GPS siting and
	measurement from site features where possible. As such, the plotted locations of these trees, groups and hedges cannot therefore be considered to be wholly accurate
	Root Protection Areas (RPAs):
	RPAs Area(s) of Ground Around Trees that Should
	be Protected Throughout Development Works with Protective Fencing to form a
	Construction Exclusion Zone
	Note: Trees or hedges with their identification numbers labelled in grey are recommended for removal in the context of the
	development
	Broinett
Remove one/two trees from south-eastern	Project: CHADSWELL HALL
edge of group G2 as necessary in order to	CHIPPING ROAD CHAIGLEY
construct access track	LANCASHIRE
	BB7 3LT
	Agent for Client:
	GARY HOERTY ASSOCIATES
	Title:
Remove and relocate section of hedge H1	IN TREE IMPACT PLAN
to form access and visibility splay	Access Track
	Scale: 1:500@A2
	Date: December 2015 Drawn by: JK
	Checked by: PH
	Bowland Ć
Road	
H1	Tree Consultancy Ltd
	t: 01254 825098
	Ref: BTC909-TIP Rev: