

KEY

Proposed Broad-Leaf Tree Planting:



Tb = *Tilia tomentosa* 'Brabant' (Silver Lime) - to be Select Standard or Heavy Standard bare-root or root-ball stock at 10-12 or 12-14cm girth respectively or container grown stock at 40L+
Qp = *Quercus robur* (Pin Oak) - to be Select Standard or Heavy Standard bare-root or root-ball stock at 10-12 or 12-14cm girth respectively or container grown stock at 40L+
Pst = *Prunus serotina* 'Tibetica' (Tibetan Cherry) - to be Select Standard or Heavy Standard bare-root or root-ball stock at 10-12 or 12-14cm girth respectively or container grown stock at 40L+
Bp = *Betula pendula* (Silver Birch) - to be Select Standard or Heavy Standard bare-root or root-ball stock at 10-12 or 12-14cm girth respectively or container grown stock at 40L+

Tree Planting & Maintenance Recommendations:

Important: In addition to the details below, all tree planting, management and maintenance is to be carried out in accordance with the guidance detailed in the associated Tree Planting Specification and Tree Management & Maintenance Schedule

Plant Supply, Storage, Planting and Establishment:

To be in accordance with current guidance included in BS4043:1989 - Transplanting Root-Balled Trees and the Joint Council for Landscape Industries / Committee on Plant Supply and Establishment: Trees and Shrubs for Landscape Planting (1997) or, if applicable, any such guidance that should supersede these documents prior to development commencing

Tree Planting:

To be in accordance with current guidance included in BS4043:1989 - Transplanting Root-Balled Trees and BS4428:1989 - Recommendations for General Landscape Operations, or, if applicable, any such guidance that should supersede these documents prior to development commencing

Staking:

To be short stake method, to no more than one third height of tree, with two stakes and cross bar

Mulching:

To be with a minimum 75mm depth of well composted wood mulch

Watering:

To be carried out immediately before and straight after planting

General Maintenance:

To be in accordance with current guidance included in BS4043:1989 - Transplanting Root-Balled Trees and BS7370:1993, or, if applicable, any such guidance that should supersede these documents prior to development commencing

Project:

THE BOWLING GREEN
BROCKHALL VILLAGE
OLD LANGHO
LANCASHIRE

Client:

MR & MRS LOFTHOUSE

Title:

TREE PLANTING PLAN
in Support of Discharge of Condition 8 of Detailed
Planning Approval for Application no.
3/2013/0323

Scale:

1:200@A2

Date:

September 2013

Drawn by:

PH

Unapproved for use: Copying or reproduction is prohibited

Ref: BTC454

Rev:

