



FIRST FLOOR PLAN

Tiled roof on felt & battens
on 102 x 50 roof spars
400 & 8 ceiling joists of oak
200 mm fibre glass insulation

new 114 approved facing
brick to external leaf
50 mm cavity with drithern insulation
100 mm thermalite blocks to inner
leaf

9.2m

100 x 56 mm studded
partitions plasterboard
& skim both sides

39 mm waste to bath
32 mm waste to basin
75 mm re-sealing traps
to fittings
100 mm soil & vent pipe

AMENDED PLANS RECEIVED
DATE 22/4/16