

Tree No.	Species	Height M	Dia @ 1.5 m	Table D RPA	Crown Spread	Crown Clearance	Age Class	Physiological Condition	Structural Condition	Management Recommendations	Remaining Contribution	Retention Category
T1	Goat Willow	8	Off site		5	1	Mature	Good	Good	Too close to the wall and building this tree will cause damage	-10	U
T2	Conifer	7	400MM	4.8M	1	3	Mature	Fair	Good	Too close to the wall	-10	C
T3	Sycamore	9	Off site		5	3	Mature	Fair	Fair	Off site	20 +	B
T4	Sycamore	9	Off site		5	3	Mature	Fair	Fair	Off site	20 +	B
T5	Beech	9	720MM	8.4M	8	2	Mature	Poor	Poor	Signs of Phytophthora Bleeding Canker	-10	U
T6	Goat Willow	6	340MM	3.9M	3	3	Mature	Poor	Poor	significantly suppressed, Fell.	-10	C
T7	Horse Chestnut	9	830MM	10.2M	8	1	Mature	Good	Good	None	20+	B
T8	Sycamore	9	710MM	8.4M	6	3	Mature	Fair	Poor	Stem burificates at 3M poor union	10-20	C
T9	Beech	6	340MM	3.9M	4	2	Early Mature	Fair	Fair	Suppressed, Fell	10-20	C
T10	Lime	8	EST 700MM Epicormic	8.4M	5	0	Mature	Good	Good	None	20 +	B

