



- BFRC "A" Rated for thermal efficiency.
- Fully drained and incorporating three thermally breaks and two weather seals.
- Grade 304 "18/82 Stainless steel construction.
- Takes a 28mm unit.
- Our Stainless Steel profile frames are manufactured with corner joints fully butted, welded, dressed square, flat and finished smooth.
- Warm powder coated to 60 microns to any RAL colour.
- Metal cills are available in a choice of profiles as are drip moulds and other ancillaries.
- All of our windows are factory-glazed.
- The design nature of our Steelyte opening casements mean that our glazing units can be removed for repair on site using hand tools.
- Warm edge spacer technology.
- Can easily accommodate specialised glass for Security, UV filtration, Energy conservation and Sound inhibition.
- Overall 40mm sight line.

Our Steelyte opening casements are designed to take a full 28mm unit and are manufactured using grade 304 "18/8" Stainless steel, which is all but immune to corrosion, is particularly good for use in coastal properties, those which are situated in exposed areas and which generally exceeds British Standard 6510.

Incorporating three thermally breaks and two weather seals it has achieved an "A" Rating for thermal efficiency. Our frames are polyester powder coat paint finish to EN ISO BS: 6497, or BS EN 13438, or can be supplied polished for modern building applications.

We offer a wide choice and range including top hung, bottom hung and side hung opening casements. Inward and outward opening Hopper lights and shapes can also be accommodated. Our windows are normally supplied to open outwards. All of our opening casements incorporate a PVC edging in order to protect historic stonework.

We also offer a stainless steel fixed frame window with the narrowest of sight lines.

Our opening casements can be double or triple glazed using high performance 28mm insulating glass units. This specification combines the latest glazing technology with warm edged spacer bar and Argon gas filling; this achieves a superior performance double-glazed unit. All of our windows are factory-glazed. However the design nature of our Steelyte opening casements means that our glazing units could be removed for repair on site using basic hand tools.

