



Notes

Floodlighting Equipment
 8 x 15m Masts (M1-M8)
 Each carrying the following Floodlights :-
 M1-M8.....2 x WB03/2KW/A3MAXI

Lamps (OSRAM)
 2000W/HQI-TSW/N/L
 (230 000 INITIAL Lm)

Illuminance Levels
Initial -
 (100hrs) E.i.ave = 318Lux
Maintained -
 (4000hrs) E.i.ave = 254Lux

Uniformity
 Emin/Eave = 0.61
 Grid values in Lux(initial).
 Grid interval = 5m.
 Contour values in Lux (initial).
 Contours: 2, 5, 10, 50 Lux.

Maintenance Factor = 0.80

320170492P



Project
 Blackburn Rugby Club

www.halliday-lighting.co.uk

Drawing Title
 Proposed floodlighting

Drawn By (print) JS	Date 03/04/2017
------------------------	--------------------

Project No 02735	Scale 1:750 @ A3
---------------------	---------------------

Drawing No HLS02735	Status Proposal
------------------------	--------------------