

Conservation Box Sash WindowSpecification Rev A 21st December, 2017Shireburn Quad - Window W14

Description:	Pair of timber-framed single glazed sash windows. Each window has a total of 36 glass panes separated by slim glazing bars (18 panes to each half of the window). The windows are set in a stone surround, with a central mullion.
Timber:	Engineered European Oak, or other suitable hardwood, such as Accoya or similar
Mullion section:	225mm
Sill section (h x d)	89mm x 184mm
Sill horns:	Not required
Staff beads:	Timber glued and pinned
Sash horns:	Not required
Frame profile:	60mm Fine Lambs Tongue moulding
Glazing bar:	18mm through glazing bar
Internal glazing bar detail:	18mm Fine Lambs Tongue
External Glazing Bar detail:	18 mm chamfered linseed oil putty
Glass Units:	6 mm single sheets of glass
Draught-proofing:	Non visible brush strip, fixed into routed grooves to meeting rail and frames
Ironmongery:	Brass sash catch, sash lifts, sash lock, sash pulleys and weights
Finish:	Primed and decorate with two coats of linseed oil paint such as Oricalcum. Colour to match adjacent windows unless entire elevation is being renewed / redecorated in which case a muted Farrow and Ball type colour could be selected.
Child restrictor:	Required