

Conservation Casement WindowSpecification Rev A 21st December 2017Shireburn Quad - Window W20 & W25

Description:	3-light casement window set in stone surround with two stone mullions. The central opening light is side-hung, with fixed lights to either side. Each light has eight glass panes separated by slim glazing bars.
Timber:	Engineered European Oak or other suitable hardwood from a sustainable source such as Accoya or similar.
Mullion section:	175mm
Sill section (h x d)	Not Required
Sill horns:	Not required
Staff beads:	Timber glued and pinned
Frame profile:	68mm Sq main frame, 44mm Sq opening/fixed light frame.
Glazing bar:	18mm through blazing bar
Internal Glazing Bars	18mm Fine Lambs Tongue
External Glazing Bars	18 mm chamfered linseed oil putty
Glass Units:	6 mm single sheets of glass
Ironmongery:	Brass hinges, stays, handles.
Draught-proofing:	Non-visible brush strip fixed into routed grooves on frames
Finish:	Primed and decorate with two coats of good quality gloss paint or linseed oil paint such as Oricalcum. Colour to match adjacent windows unless entire elevation is being renewed / redecorated in which case a muted Farrow and Ball type colour could be selected.
Child restrictor:	Required