



Conservation Casement Window

Specification

Shireburn Quad - Window W23a & 25

Description:	Six light timber framed single glazed window with casement or fixed lights. Each window has eight glass panes within them separated by slim glazing bars. Externally the window has stone surround, and mullions, splitting the window into three
Timber:	Engineered European Oak
Mullion section:	175mm
Sill section (h x d)	Not Required
Sill horns:	Not required
Staff beads:	Timber glued and pinned
Sash horns:	Not required
Frame profile:	68mm Sq main frame, 44mm Sq opening/fixed light frame.
Internal Glazing Bars	18mm Fine Lambs Tongue
External Glazing Bars	18 mm chamfered putty
Glass Units:	6 mm single sheets of glass
Ironmongery:	Brass hinges, stays, handles,
Finish:	Primed and decorate with two coats of good quality gloss paint. Colour to match adjacent windows unless entire elevation is being renewed / redecorated in which case a muted Farrow and Ball type colour could be selected.
Child restrictor:	Required

320171148

Cassidy+
Ashton



STONYHURST

Conservation Box Sash Window

Specification

Shireburn Quad - Window W18

Description:	Two light timber framed single glazed window with sash. Each window has thirty six glass panes within them separated by slim glazing bars. Externally the window has stone surround, and central mullion.
Timber:	Engineered European Oak
Mullion section:	225mm
Sill section (h x d)	89mm x 184mm
Sill horns:	Not required
Staff beads:	Timber glued and pinned
Sash horns:	Not required
Frame profile:	60mm Fine Lambs Tongue moulding
Internal Glazing Bars	18mm Fine Lambs Tongue
External Glazing Bars	18 mm chamfered putty
Glass Units:	6 mm single sheets of glass
Ironmongery:	Brass sash catch, sash lifts, sash lock, sash pulley
Finish:	Primed and decorate with two coats of good quality gloss paint. Colour to match adjacent windows unless entire elevation is being renewed / redecorated in which case a muted Farrow and Ball type colour could be selected.
Child restrictor:	Required