



HIGHWAY SPECIFICATION

45mm OF HRA 30/14F SURFACE COURSE

70mm OF 20mm DBM BINDER COURSE

130mm OF 32mm DBM ROAD BASE

150mm TYPE 1 SUB-BASE OVER 400mm OF 6F2 CAPPING ON A GEOTEXTILE (CBR BETWEEN 2% AND 8%) OR OVER 600mm OF 6F2 CAPPING ON A GEOTEXTILE (CBR LESS THAN 2%)

...							OAKMERE HOMES	ROAD ACCESS	<div>REFORD</div> <div>Consulting Engineers Limited</div> <div>7 Hall Road, Fulwood, Preston, PR2 9QD</div> <div>Mobile: 07970 265 334</div> <div>Email: r.e.ford@virginmedia.com</div>
	-		ORIGINAL ISSUE	SB	BF	BF	ACCRINGTON ROAD WHALLEY		
	Rev	Date	Description	Drn	Chk	App		SCALE: 1:1000@A3	REV -
								C250-125	