



Product description		QU	PU	BP	Art. No.
Roof hook aluminium HD 152-9-45 complete		pcs	20	480	720-200-050
Material	Aluminium EN-AW-6063 T66				
Material screw	Stainless steel X5CrNi18-10 A2-70				
Base plate	152 mm x 90 mm; drillings 8 x 7 mm and 8 x 9 mm				
Type of roofing	Tile, pan				
Weight	0.520 kg				
Article supplement	Roof hooks suitable for high snow loads, pre-assembled; incl. hammer-head bolt set M8x25				



S:FLEX roof hook plain tile 30x6 complete		pcs	20	960	720-200-071
Material	Stainless steel A2; 1.4301				
Material screw	Stainless steel X5CrNi18-10 A2-70				
Type of roofing	Plain tile				
Weight	0.592 kg				
Dimensions W x H	Material thickness 30x6 mm				
Drilling	2x9 mm for plate head wood screws				
Article supplement	pre-assembled; incl. hammer-head bolt set				



S:FLEX roof hook slate 30x5 complete		pcs	20	1,080	720-200-061
Material	Stainless steel A2; 1.4301				
Material screw	Stainless steel X5CrNi18-10 A2-70				
Type of roofing	Slate				
Weight	0.450 kg				
Dimensions W x H	Material thickness 30x5 mm				
Drilling	3x7 mm for countersunk wood screws				
Article supplement	pre-assembled; incl. hammer-head bolt set				