



Church Raike, Chipping

Report to Discharge Drainage Related Planning Condition

Project number: 3081

Date: June 2018

Revision: 4

Document Control Sheet

Project No.: 3081

Project Title: Church Rake, Chipping

Report Title: Report to Discharge Drainage Related Planning Condition

Report Reference: 3081/PC/001

Issue: 4

Status: Final

Date: 13.06.18

Record of Issue

Issue	Status	Author	Approved	Date
1	Final	Ann Bacon	Paul Graveney	07.08.17
2	Final	Ann Bacon	Paul Graveney	09.02.18
3	Final	Ann Bacon	Paul Graveney	21.05.18
4	Final	Ann Bacon	Paul Graveney	13.06.18

Distribution

Issue	Organisation	Quantity
1	RVBC/LCC	1
2	RVBC/LCC	1
3	RVBC/LCC	1
4	RVBC/LCC	1

Table of Contents

1.0	Introduction	3
2.0	Outline Drainage Strategy.....	4
2.1	Surface Water Strategy	4
3.0	Drainage Related Planning Conditions.....	6
3.1	Planning Condition	6
3.2	Input to Remove Drainage Conditions	7
Appendix A – Scott Hughes Design Drawings.....	8	
Appendix B – Hydraulic Calculations	9	
Appendix C – United Utilities Correspondence	10	

1.0 Introduction

In 2017 a Reserved Matters application no. 3/2017/0183 was submitted to Ribble Valley Borough Council for the construction of a residential development on land off Church Rake in Chipping. The reserved matters application relates to the development of a piece of land in the Site Wide Planning Guide Drawing No. 05024_mp_00_105. A Site Wide Flood Risk Assessment for the development was submitted with the original planning application in October 2013. Planning approval has been granted subject to a number of planning conditions, including three conditions relating to the drainage of the development.

This report has been prepared to remove the drainage related planning condition applicable for the application.

2.0 Outline Drainage Strategy

2.1 Surface Water Strategy

The current site is undeveloped and is therefore defined as greenfield.

The outline drainage strategy is to provide new separate surface water and foul water adopted drainage networks. Foul water generated by the development will discharge unrestricted to the combined public sewer in Church Raike, as agreed with United Utilities. Correspondence with United Utilities is included in Appendix C of this report.

The Planning Policy Guidance (PPG) hierarchy for the disposal of surface water was considered and taking into consideration the local site conditions, details of the various options are illustrated in the table below:

Table 1: SuDS Hierarchical Approach

Method	Suitability	Suitability for Development
Infiltration to Ground	No	Site investigation has confirmed that infiltration based options would not be suitable
Connection to Watercourse	Yes	Connection to watercourse to north of the site.
Connection to Surface Water Sewer	No	Connection to watercourse is the preferred option.
Connection to a Combined Sewer	No	Connection to watercourse is the preferred option.

Ground Investigations have confirmed that the ground conditions are generally clay and therefore not suitable for infiltration methods of drainage. Therefore, discharge of surface water to the unnamed watercourse to the north of the site was considered to be the preferred option. An extract from the Grouund Investigation Report is shown below.

5.6 Soakaways

- 5.6.1 The use of soakaways within the natural ground is not feasible at the site due to the presence of relatively impermeable strata underlying the site.

The surface water drainage strategy is to provide private surface water drainage networks which will discharge into a new surface water public sewer network to be adopted by United Utilities. A private surface water package pumping station will be used to lift flows from a low-lying area in the south west of the development up to the adoptable drainage network. The discharge rate from the development will be restricted to greenfield run off rates using a Hydrobrake flow control device. Below ground surface water attenuation will be provided by

oversized pipes within the proposed public sewer system and geocellular storage crates in the private drainage network.

Drawings 3081-SHD-00-ZZ-DR-C-0100 and 0101 – Proposed Drainage GA in Appendix A defines the agreed drainage strategy.

Hydraulic calculations are included in Appendix B of this report.

The proposed private drainage layout for the new development site has been designed in accordance with BS EN 752: 2008 and Building Regulations Part H guidance, i.e. up to the 30 year storm return period criterion and tested for the extreme 100 year event to confirm no flood risk to the buildings. Note that the below ground drainage network has been sized to retain the peak 100 year plus 40% climate change event.

3.0 Drainage Related Planning Conditions

3.1 Planning Condition

Planning Condition No. 41

The written planning condition is:

Notwithstanding any indication on the approved plans, no development approved by this permission shall commence on a land parcel (as defined on Dwg No 05024_MP_00_105) until a scheme for the disposal of foul and surface waters for the parcel has been submitted to and approved in writing by the Local Planning Authority. For the avoidance of doubt, surface water must drain separate from the foul and no surface water will be permitted to discharge directly or indirectly into existing sewerage systems. The development shall be completed, maintained and managed in accordance with the approved details.

Planning Condition No. 42

The written planning condition is:

The development permitted by this planning permission shall only be carried out in accordance with the approved FRA (v1.1, dated October 2013) and the following mitigation measures detailed within the FRA: i) Limiting the surface water run-off generated by the 1 in 100 year plus climate change critical storm so that it will not exceed the run-off from the undeveloped site and not increase the risk of flooding off-site. ii) Implementation of all mitigation measures set out in Sections 4 and 7 of the FRA (v1.1, dated October 2013). The mitigation measures shall be fully implemented prior to occupation and subsequently in accordance with the timing / phasing arrangements embodied within the scheme, or within any other period as may subsequently be agreed, in writing, by the Local Planning Authority.

Planning Condition No. 43

The written planning condition is:

No development shall take place until a surface water drainage scheme for a land parcel (as defined on Dwg No 05024_MP_00_105), based on sustainable drainage principles and an assessment of the hydrological and hydrogeological context of the development, has been submitted to and approved in writing by the Local Planning Authority. The drainage strategy for that land parcel should demonstrate the surface water run-off generated up to and including the 1 in 100 year plus climate change critical storm will not exceed the run-off from the undeveloped site following the corresponding rainfall event. The scheme for that land parcel shall subsequently be implemented in accordance with the approved details before the development is completed.

3.2 Input to Remove Drainage Conditions

Planning Condition No. 41

The proposed drainage strategy for the site is indicated in Section 2. The drainage layout drawing in Appendix A and the supporting calculations in Appendix B are deemed sufficient to remove the condition.

Planning Condition No. 42

Surface water discharge rates are to be restricted to the equivalent greenfield run-off rates for the site. The surface water drainage system has been designed so that no flooding will occur for events up to 1 in 30 year return period. Some minor exceedance flooding will occur for events of 1 in 100 year plus 40% climate change return period however due to the proposed levels of the site these will runoff away from properties whilst being contained within the development. The drainage layout drawing in Appendix A and the supporting calculations in Appendix B are deemed sufficient to remove this part of the condition.

The reserve matters application to which this report refers, relates to a land parcel which is part of a wider development as defined on Dwg No. 05024_MP_00_105. The FRA submitted with the initial outline planning application relates to the wider development and the land parcel to which this application relates to is referred to as The Hive in the FRA. The Hive lies within a Flood Zone 1 area. The mitigation measures outlined in the FRA were designed to provide flood protection to the other land parcels which are at greater risk of flooding. Therefore, the mitigation measures are not required for this particular land parcel.

Planning Condition No. 43

The proposed drainage strategy for the site is indicated in Section 2. The drainage layout drawing in Appendix A and the supporting calculations in Appendix B are deemed sufficient to remove the condition.

Appendix A – Scott Hughes Design Drawings

CONTENTS	
Identifier	Name
3081-SHD-00-ZZ-DR-C-0100 & 0101	Proposed Drainage GA – Sheets 1 and 2

GENERAL NOTES

- DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL RELEVANT SPECIFICATIONS, ENGINEERS, ARCHITECTS & SERVICES DRAWINGS, INCLUDING APPROVED BUILDERS WORK DRAWINGS. CONTRACTOR TO NOTIFY ENGINEER OF DISCREPANCIES BETWEEN STRUCTURAL DRAWINGS AND SPECIFICATIONS OR OTHER DRAWINGS.
- ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE.
- DO NOT SCALE FROM THIS DRAWING, WORK TO DIMENSIONS OR CO-ORDINATES PROVIDED. ALL LEVELS ARE IN METRES AND ALL DIMENSIONS ARE IN MILLIMETRES, UNLESS OTHERWISE NOTED. ANY AMBIGUITIES, OMISSIONS AND ERRORS ON DRAWINGS SHALL BE BROUGHT TO THE ENGINEERS ATTENTION IMMEDIATELY.

DRAINAGE KEY

- EXISTING SW DRAIN
- EXISTING SW DRAIN MANHOLE
- EXISTING FW SEWER
- EXISTING FW SEWER MANHOLE
- EXISTING CW SEWER
- EXISTING CW SEWER MANHOLE
- PROPOSED LATERAL CW DRAIN
- PROPOSED LATERAL CW MANHOLE
- PROPOSED ADOPTED FW SEWER
- PROPOSED ADOPTED FW MANHOLE
- PROPOSED LATERAL FW DRAIN
- PROPOSED LATERAL FW PPIC
- PROPOSED FW RISING MAIN
- PROPOSED PRIVATE FW DRAIN
- PROPOSED PRIVATE FW PPIC
- PROPOSED PRIVATE FW RISING MAIN
- PROPOSED PRIVATE FW MINI-PPIC (600mm)
- PROPOSED WASTE POINT CONNECTION
- PROPOSED ADOPTED SW SEWER
- PROPOSED ADOPTED SW MANHOLE
- PROPOSED LATERAL SW DRAIN
- PROPOSED LATERAL SW PPIC
- PROPOSED SW RISING MAIN
- PROPOSED PRIVATE SW DRAINAGE
- PROPOSED PRIVATE SW DRAINAGE
- PROPOSED SW PPIC
- PROPOSED PRIVATE SW RISING MAIN
- PROPOSED RAINWATER PIPE
- PROPOSED PRIVATE ROAD GULLY
- PROPOSED DRAINAGE CHANNEL
- PROPOSED HIGHWAY DRAIN MANHOLE
- PROPOSED HIGHWAY ROAD GULLY
- SITE BOUNDARY
- FINISHED FLOOR LEVEL

P7	08.06.18	AB	PG	LAYOUT UPDATED
P6	14.05.18	JS	PG	CONTRACT ISSUE
P5	09.02.18	AB	PG	CLOUDED REVISIONS
P4	23.11.17	AB	PG	CLODDED REVISIONS
P3	24.10.17	AB	PG	TENDER ISSUE
P2	17.10.17	AB	PG	LAYOUT UPDATED
P1	09.05.17	LED	PG	PRELIMINARY ISSUE
No	DATE	DRAWN	REVD	AMENDMENT


STATUS	PURPOSE OF ISSUE
A1	CONTRACT

©COPYRIGHT
The concepts and the information contained in this document are the copyright of Scott Hughes Design Ltd. Use or copying of the document in whole or in part without written permission of Scott Hughes Design Ltd. constitutes an infringement of copyright.

Scott Hughes Design Ltd.
The Flint Glass Works,
64 Jersey Street,
Manchester M4 5JW
t: 0161 605 0831
f: 0161 605 0832
e: mail@scotthughesdesign.co.uk
Reg No. 4899745

CLIENT CHIPPING HOMES LTD
PROJECT CHURCH RAIKE, CHIPPING
DRAFTER MD ENGINEER PG
TITLE PROPOSED DRAINAGE GA
SHEET 1 OF 2

SCALE 1:250 SHEET A1 DRAWING No 3081-SHD-00-ZZ-DR-C-0100 REV P7



GENERAL NOTES

1. DRAWINGS TO BE READ IN CONJUNCTION WITH ALL RELEVANT SPECIFICATIONS, ENGINEERS, ARCHITECTS & SERVICES DRAWINGS, INCLUDING APPROVED BUILDERS WORK DRAWINGS. CONTRACTOR TO NOTIFY ENGINEER OF DISCREPANCIES BETWEEN STRUCTURAL DRAWINGS AND SPECIFICATIONS OR OTHER DRAWINGS.

2. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE.

3. DO NOT SCALE FROM THIS DRAWING, WORK TO DIMENSIONS OR CO-ORDINATES PROVIDED. ALL LEVELS ARE IN METRES AND ALL DIMENSIONS ARE IN MILLIMETRES, UNLESS OTHERWISE NOTED. ANY AMBIGUITIES, OMISSIONS AND ERRORS ON DRAWINGS SHALL BE BROUGHT TO THE ENGINEERS ATTENTION IMMEDIATELY.

DRAINAGE KEY

EXISTING SW DRAIN
EXISTING SW DRAIN MANHOLE
EXISTING FW SEWER
EXISTING FW SEWER MANHOLE
EXISTING CW SEWER
EXISTING CW SEWER MANHOLE
PROPOSED LATERAL CW DRAIN
PROPOSED LATERAL CW MANHOLE
PROPOSED ADOPTED FW SEWER
PROPOSED ADOPTED FW MANHOLE
PROPOSED LATERAL FW DRAIN
PROPOSED LATERAL FW PPIC
PROPOSED FW RISING MAIN
PROPOSED PRIVATE FW DRAIN
PROPOSED PRIVATE FW PPIC
PROPOSED PRIVATE FW MINI-PPIC (600mm DP)
PROPOSED PRIVATE FW RISING MAIN
PROPOSED WASTE POINT CONNECTION
PROPOSED ADOPTED SW SEWER
PROPOSED ADOPTED SW MANHOLE
PROPOSED LATERAL SW DRAIN
PROPOSED LATERAL SW PPIC
PROPOSED SW RISING MAIN
PROPOSED PRIVATE SW DRAINAGE
PROPOSED PRIVATE SW DRAIN
PROPOSED SW PPIC
PROPOSED PRIVATE ROAD GULLY
PROPOSED DRAINAGE CHANNEL
PROPOSED HIGHWAY DRAIN
PROPOSED HIGHWAY ROAD GULLY
SITE BOUNDARY

124.1m			
FINISHED FLOOR LEVEL			
P10	08.06.18	AB	PG
P9	18.05.18	AB	PG
P8	14.05.18	JS	PG
P7	22.03.18	AB	PG
P6	09.02.18	AB	PG
P5	23.11.17	AB	PG
P4	24.10.17	AB	PG
P3	17.10.17	AB	PG
No	DATE	DRAWN	REVD ENG.
			AMENDMENT

STATUS	PURPOSE OF ISSUE
A1	CONTRACT

COPYRIGHT - The concepts and the information contained in this document are the copyright of Scott Hughes Design Ltd. Use or copying of the document in whole or in part without written permission of Scott Hughes Design Ltd. constitutes an infringement of copyright.

Scott Hughes Design Ltd.
The Flint Glass Works,
64 Jersey Street,
Manchester M4 5JW
L 0161 605 0831
f. 0161 605 0832
e-mail@scottushughesdesign.co.uk
Reg No. 4899745

CLIENT CHIPPING HOMES LTD

PROJECT CHURCH RAIKE, CHIPPING

DRAFTER MD ENGINEER PG

TITLE PROPOSED DRAINAGE GA
SHEET 2 OF 2

Appendix B – Hydraulic Calculations

Outputs from the Microdrainage software for the surface water drainage networks serving the development are provided. Pipe references from the hydraulic models can be located on the Proposed Drainage GA's.

Scott Hughes Design Ltd The Flint Glass Works 64 Jersey Street Manchester M4 6JW		Page 1
Date 25/04/2017 14:34 File	Designed by SHD18 Checked by	
Micro Drainage	Source Control 2016.1	

ICP SUDS Mean Annual Flood

Input

Return Period (years)	2	Soil	0.450
Area (ha)	1.770	Urban	0.000
SAAR (mm)	1187	Region Number	Region 10

Results 1/s

QBAR Rural 14.4
QBAR Urban 14.4

Q2 years 13.4

Q1 year 12.5
Q30 years 24.5
Q100 years 30.0

Scott Hughes Design Ltd										Page 1
The Flint Glass Works 64 Jersey Street Manchester M4 6JW			Church Raike Chipping							
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX			Designed by AB Checked by PG							
Micro Drainage Network 2017.1.1										



Existing Network Details for Storm

* - Indicates pipe has been modified outside of System 1

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	k (mm)	HYD SECT	DIA (mm)	Section Type
1.000	12.130	0.438	27.7	0.007	5.00	0.600	o	100	Pipe/Conduit
1.001	13.774	0.138	99.8	0.004	0.00	0.600	o	100	Pipe/Conduit
2.000	12.280	0.639	19.2	0.004	5.00	0.600	o	100	Pipe/Conduit
1.002	7.074	0.729	9.7	0.020	0.00	0.600	o	100	Pipe/Conduit
3.000	12.368	0.124	99.7	0.006	5.00	0.600	o	100	Pipe/Conduit
3.001	5.744	0.057	100.8	0.000	0.00	0.600	o	100	Pipe/Conduit
4.000	14.503	1.481	9.8	0.004	5.00	0.600	o	100	Pipe/Conduit
3.002	16.189	0.274	59.1	0.007	0.00	0.600	o	100	Pipe/Conduit
3.003	8.181	0.300	27.3	0.000	0.00	0.600	o	100	Pipe/Conduit
1.003	25.181	2.140	11.8	0.000	0.00	0.600	o	150	Pipe/Conduit
5.000	9.905	0.125	79.2	0.008	5.00	0.600	o	100	Pipe/Conduit
5.001	14.030	0.676	20.8	0.001	0.00	0.600	o	100	Pipe/Conduit

PN	US/MH Name	US/CL (m)	US/IL (m)	US C.Depth (m)	DS/CL (m)	DS/IL (m)	DS C.Depth (m)	Ctrl	US/MH (mm)
1.000	R1	136.578	135.850	0.628	136.012	135.412	0.500		450
1.001	S01	136.012	135.412	0.500	135.990	135.274	0.616		450
2.000	R2	136.513	135.913	0.500	135.990	135.274	0.616		450
1.002	S02	135.990	135.274	0.616	135.845	134.545	1.200		450
3.000	R5	135.900	135.300	0.500	136.086	135.176	0.810		450
3.001	S03	136.086	135.176	0.810	136.418	135.119	1.199		450
4.000	R4	136.953	136.600	0.253	136.418	135.119	1.199		450
3.002	S04	136.418	135.119	1.199	136.003	134.845	1.058		450
3.003	S05	136.003	134.845	1.058	135.845	134.545	1.200		450
1.003	S06	135.845	134.495	1.200	133.368	132.355	0.863		1200
5.000	R7	134.325	133.625	0.600	134.300	133.500	0.700		450
5.001	S07	134.300	133.500	0.700	134.018	132.824	1.094		450

Scott Hughes Design Ltd								Page 2
The Flint Glass Works 64 Jersey Street Manchester M4 6JW			Church Raike Chipping					
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX			Designed by AB Checked by PG					
Micro Drainage			Network 2017.1.1					



Existing Network Details for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	k (mm)	HYD SECT	DIA (mm)	Section Type
6.000	20.911	1.304	16.0	0.007	5.00	0.600	o	100	Pipe/Conduit
5.002	7.107	0.419	17.0	0.006	0.00	0.600	o	100	Pipe/Conduit
1.004	12.963	0.507	25.6	0.025	0.00	0.600	o	675	Pipe/Conduit
7.000	15.070	0.512	29.4	0.009	5.00	0.600	o	100	Pipe/Conduit
7.001	12.191	0.122	99.9	0.000	0.00	0.600	o	100	Pipe/Conduit
8.000	14.443	0.546	26.5	0.005	5.00	0.600	o	100	Pipe/Conduit
8.001	14.860	0.551	27.0	0.005	0.00	0.600	o	100	Pipe/Conduit
7.002	8.810	0.567	15.5	0.003	0.00	0.600	o	100	Pipe/Conduit
9.000	11.954	0.168	71.2	0.004	5.00	0.600	o	100	Pipe/Conduit
9.001	18.787	0.188	99.9	0.004	0.00	0.600	o	100	Pipe/Conduit
9.002	14.276	0.095	150.3	0.012	0.00	0.600	o	150	Pipe/Conduit
7.003	6.416	0.064	100.3	0.000	0.00	0.600	o	150	Pipe/Conduit
7.004	8.698	0.101	86.1	0.000	0.00	0.600	o	150	Pipe/Conduit

PN	US/MH Name	US/CL (m)	US/IL (m)	US C.Depth (m)	DS/CL (m)	DS/IL (m)	DS C.Depth (m)	Ctrl (mm)	US/MH
6.000	R8	134.800	134.128	0.572	134.018	132.824	1.094	450	
5.002	S08	134.018	132.824	1.094	133.368	132.405	0.863	450	
1.004	S09	133.368	131.000	1.693	133.223	130.493	2.055	1800	
7.000	R9	133.047	132.434	0.513	132.956	131.922	0.934	450	
7.001	S10	132.956	131.922	0.934	132.519	131.800	0.619	450	
8.000	R10	133.497	132.897	0.500	133.059	132.351	0.608	450	
8.001	S11	133.059	132.351	0.608	132.519	131.800	0.619	450	
7.002	S12	132.519	131.800	0.619	132.607	131.233	1.274	450	
9.000	R11	132.284	131.684	0.500	132.279	131.516	0.663	450	
9.001	S13	132.279	131.516	0.663	132.389	131.328	0.961	450	
9.002	S14	132.389	131.278	0.961	132.607	131.183	1.274	450	
7.003	S15	132.607	131.183	1.274	132.893	131.119	1.624	450	
7.004	S16	132.893	131.119	1.624	133.223	131.018	2.055	450	

Scott Hughes Design Ltd								Page 3
The Flint Glass Works 64 Jersey Street Manchester M4 6JW			Church Raike Chipping					
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX			Designed by AB Checked by PG					
Micro Drainage Network 2017.1.1								



Existing Network Details for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	k (mm)	HYD SECT	DIA (mm)	Section Type
1.005	27.837	0.268	103.9	0.044	0.00	0.600	o	900	Pipe/Conduit
10.000	32.195	0.603	53.4	0.011	5.00	0.600	o	100	Pipe/Conduit
11.000	10.920	0.109	100.2	0.002	5.00	0.600	o	100	Pipe/Conduit
10.001	18.123	0.602	30.1	0.000	0.00	0.600	o	100	Pipe/Conduit
12.000	10.730	0.107	100.3	0.009	5.00	0.600	o	100	Pipe/Conduit
10.002	12.540	0.125	100.3	0.011	0.00	0.600	o	100	Pipe/Conduit
13.000	21.651	0.986	22.0	0.005	5.00	0.600	o	100	Pipe/Conduit
10.003	6.576	0.080	82.2	0.009	0.00	0.600	o	100	Pipe/Conduit
1.006	25.607	0.079	324.1	0.000	0.00	0.600	o	900	Pipe/Conduit
14.000	13.228	0.128	103.3	0.004	5.00	0.600	o	100	Pipe/Conduit
14.001	9.272	0.180	51.5	0.004	0.00	0.600	o	100	Pipe/Conduit
14.002	15.585	0.161	96.8	0.011	0.00	0.600	o	100	Pipe/Conduit

PN	US/MH Name	US/CL (m)	US/IL (m)	US C.Depth (m)	DS/CL (m)	DS/IL (m)	DS C.Depth (m)	Ctrl (mm)	US/MH
1.005	S17	133.223	130.268	2.055	133.700	130.000	2.800	2100	
10.000	R12	134.495	133.800	0.595	134.199	133.197	0.902	450	
11.000	R13	134.005	133.306	0.599	134.199	133.197	0.902	450	
10.001	S18	134.199	133.197	0.902	133.603	132.595	0.908	450	
12.000	R14	133.325	132.702	0.523	133.603	132.595	0.908	450	
10.002	S19	133.603	132.595	0.908	133.760	132.470	1.190	450	
13.000	R15	133.928	133.456	0.372	133.760	132.470	1.190	450	
10.003	S20	133.760	132.470	1.190	133.700	132.390	1.210	450	
1.006	S21	133.700	130.000	2.800	132.627	129.921	1.806	2400	
14.000	R16	133.600	133.000	0.500	133.901	132.872	0.929	450	
14.001	S22	133.901	132.872	0.929	133.864	132.692	1.072	450	
14.002	S23	133.864	132.692	1.072	133.547	132.531	0.916	450	

Scott Hughes Design Ltd								Page 4
The Flint Glass Works 64 Jersey Street Manchester M4 6JW		Church Raike Chipping						
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX		Designed by AB Checked by PG						
Micro Drainage		Network 2017.1.1						



Existing Network Details for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	k (mm)	HYD SECT	DIA (mm)	Section Type
14.003	17.675	0.371	47.6	0.010	0.00	0.600	o	100	Pipe/Conduit
15.000	11.509	0.128	89.9	0.004	5.00	0.600	o	100	Pipe/Conduit
15.001	13.456	0.272	49.5	0.004	0.00	0.600	o	100	Pipe/Conduit
14.004	6.280	0.750	8.4	0.000	0.00	0.600	o	100	Pipe/Conduit
16.000	21.015	0.349	60.2	0.008	5.00	0.600	o	100	Pipe/Conduit
16.001	14.053	0.238	59.0	0.003	0.00	0.600	o	100	Pipe/Conduit
16.002	3.790	0.064	59.2	0.003	0.00	0.600	o	100	Pipe/Conduit
17.000	19.719	0.814	24.2	0.016	5.00	0.600	o	100	Pipe/Conduit
16.003	5.872	1.128	5.2	0.000	0.00	0.600	o	100	Pipe/Conduit
1.007	21.717	0.072	301.6	0.042	0.00	0.600	o	300	Pipe/Conduit
1.008	10.036	0.050	200.7	0.000	0.00	0.600	o	1500	Pipe/Conduit
18.000	12.005	0.120	100.0	0.004	5.00	0.600	o	100	Pipe/Conduit
18.001	10.114	0.236	42.9	0.003	0.00	0.600	o	100	Pipe/Conduit

PN	US/MH Name	US/CL (m)	US/IL (m)	US C.Depth (m)	DS/CL (m)	DS/IL (m)	DS C.Depth (m)	Ctrl	US/MH (mm)
14.003	S24	133.547	132.531	0.916	132.874	132.160	0.614		450
15.000	S25	133.161	132.560	0.501	133.543	132.432	1.011		450
15.001	S26	133.543	132.432	1.011	132.874	132.160	0.614		450
14.004	S28	132.874	132.160	0.614	132.627	131.410	1.117		450
16.000	R17	133.100	132.500	0.500	132.851	132.151	0.600		450
16.001	S29	132.851	132.151	0.600	132.797	131.913	0.784		450
16.002	S30	132.797	131.913	0.784	132.788	131.849	0.839		450
17.000	R18	133.424	132.663	0.661	132.788	131.849	0.839		450
16.003	S31	132.788	131.849	0.839	132.627	130.721	1.806		450
1.007	S32	132.627	129.921	2.406	131.550	129.849	1.401	Orifice	2100
1.008	48	131.550	126.128	3.922	131.084	126.078	3.506		2400
18.000	49	130.085	129.383	0.602	130.300	129.263	0.937		1200
18.001	S33	130.300	129.263	0.937	129.921	129.027	0.794		450

Scott Hughes Design Ltd								Page 5
The Flint Glass Works 64 Jersey Street Manchester M4 6JW				Church Raike Chipping				
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX				Designed by AB Checked by PG				
Micro Drainage								Network 2017.1.1



Existing Network Details for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	k (mm)	HYD SECT	DIA (mm)	Section Type
19.000	12.481	0.437	28.6	0.004	5.00	0.600	o	100	Pipe/Conduit
18.002	11.335	0.113	100.3	0.006	0.00	0.600	o	100	Pipe/Conduit
18.003	19.965	0.214	93.3	0.015	0.00	0.600	o	100	Pipe/Conduit
20.000	15.367	0.104	147.8	0.004	5.00	0.600	o	100	Pipe/Conduit
20.001	16.829	0.192	87.7	0.005	0.00	0.600	o	100	Pipe/Conduit
20.002	8.356	1.004	8.3	0.003	0.00	0.600	o	100	Pipe/Conduit
18.004	8.809	0.239	36.9	0.002	0.00	0.600	o	150	Pipe/Conduit
18.005	8.457	0.333	25.4	0.000	0.00	0.600	o	150	Pipe/Conduit
21.000	6.785	0.068	99.8	0.003	5.00	0.600	o	100	Pipe/Conduit
21.001	11.575	0.196	59.1	0.005	0.00	0.600	o	100	Pipe/Conduit
21.002	29.154	1.413	20.6	0.014	0.00	0.600	o	100	Pipe/Conduit
22.000	20.875	1.286	16.2	0.010	5.00	0.600	o	100	Pipe/Conduit
22.001	3.637	0.036	101.0	0.000	0.00	0.600	o	100	Pipe/Conduit
22.002	12.756	0.128	99.7	0.008	0.00	0.600	o	100	Pipe/Conduit
23.000	16.845	0.343	49.1	0.008	5.00	0.600	o	150	Pipe/Conduit

PN	US/MH Name	US/CL (m)	US/IL (m)	US C.Depth (m)	DS/CL (m)	DS/IL (m)	DS C.Depth (m)	Ctrl	US/MH
19.000	50	130.064	129.464	0.500	129.921	129.027	0.794	1200	
18.002	S34	129.921	129.027	0.794	130.546	128.914	1.532	450	
18.003	S35	130.546	128.914	1.532	131.069	128.700	2.269	450	
20.000	R21	130.600	130.000	0.500	130.657	129.896	0.661	450	
20.001	S36	130.657	129.896	0.661	131.443	129.704	1.639	450	
20.002	S37	131.443	129.704	1.639	131.069	128.700	2.269	450	
18.004	S38	131.069	128.650	2.269	131.347	128.411	2.786	450	
18.005	57	131.347	128.411	2.786	131.084	128.078	2.856	1200	
21.000	R22	132.100	131.500	0.500	132.188	131.432	0.656	450	
21.001	S39	132.188	131.432	0.656	132.357	131.236	1.021	450	
21.002	S40	132.357	131.236	1.021	131.237	129.823	1.314	450	
22.000	R23	131.811	131.273	0.438	131.098	129.987	1.011	450	
22.001	S41	131.098	129.987	1.011	131.061	129.951	1.010	450	
22.002	63	131.061	129.951	1.010	131.237	129.823	1.314	1200	
23.000	R25	130.766	130.116	0.500	131.237	129.773	1.314	450	

Scott Hughes Design Ltd								Page 6
The Flint Glass Works 64 Jersey Street Manchester M4 6JW			Church Raike Chipping					
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX			Designed by AB Checked by PG					
Micro Drainage								Network 2017.1.1



Existing Network Details for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	k (mm)	HYD SECT	DIA (mm)	Section Type
----	---------------	-------------	----------------	----------------	----------------	-----------	-------------	-------------	--------------

21.003	5.919	0.059	100.3	0.004	0.00	0.600	o	150	Pipe/Conduit
24.000	10.125	0.060	168.8	0.031	5.00	0.600	o	225	Pipe/Conduit
24.001	24.010	0.220	109.1	0.000	0.00	0.600	o	225	Pipe/Conduit
1.009	17.386	0.087	199.8	0.000	0.00	0.600	o	1500	Pipe/Conduit
1.010	16.483	0.082	201.0	0.000	0.00	0.600	o	1500	Pipe/Conduit
25.000	8.005	0.616	13.0	0.003	5.00	0.600	o	100	Pipe/Conduit
25.001	10.139	0.106	95.7	0.010	0.00	0.600	o	100	Pipe/Conduit
26.000	12.271	0.777	15.8	0.003	5.00	0.600	o	100	Pipe/Conduit
27.000	5.712	0.106	53.9	0.003	5.00	0.600	o	100	Pipe/Conduit
25.002	5.679	1.411	4.0	0.000	0.00	0.600	o	100	Pipe/Conduit
1.011	21.729	0.109	199.3	0.000	0.00	0.600	o	1800	Pipe/Conduit
28.000	13.507	0.530	25.5	0.002	5.00	0.600	o	100	Pipe/Conduit

PN	US/MH Name	US/CL (m)	US/IL (m)	US C.Depth (m)	DS/CL (m)	DS/IL (m)	DS C.Depth (m)	Ctrl	US/MH
----	---------------	--------------	--------------	----------------------	--------------	--------------	----------------------	------	-------

21.003	S42	131.237	129.773	1.314	131.084	129.714	1.220	450	
24.000	H01	129.663	127.633	1.805	130.448	127.573	2.650	450	
24.001	H02	130.448	127.573	2.650	131.084	127.353	3.506	1200	
1.009	S43	131.084	126.078	3.506	130.408	125.991	2.917	2700	
1.010	S44	130.408	125.991	2.917	129.822	125.909	2.413	2400	
25.000	R26	130.316	129.716	0.500	129.952	129.100	0.752	450	
25.001	S45	129.952	129.100	0.752	129.816	128.994	0.722	450	
26.000	R27	130.371	129.771	0.500	129.816	128.994	0.722	450	
27.000	R28	129.700	129.100	0.500	129.816	128.994	0.722	450	
25.002	S46	129.816	128.994	0.722	129.822	127.583	2.139	450	
1.011	S47	129.822	125.609	2.413	129.154	125.500	1.854	2700	
28.000	R29	129.730	129.130	0.500	129.496	128.600	0.796	450	

Scott Hughes Design Ltd								Page 7
The Flint Glass Works 64 Jersey Street Manchester M4 6JW			Church Raike Chipping					
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX			Designed by AB Checked by PG					
Micro Drainage								Network 2017.1.1



Existing Network Details for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	k (mm)	HYD SECT	DIA (mm)	Section Type
----	---------------	-------------	----------------	----------------	----------------	-----------	-------------	-------------	--------------

29.000	8.997	0.264	34.1	0.003	5.00	0.600	o	100	Pipe/Conduit
28.001	12.025	0.295	40.8	0.005	0.00	0.600	o	100	Pipe/Conduit
28.002	7.497	0.127	59.0	0.002	0.00	0.600	o	100	Pipe/Conduit
30.000	6.044	0.554	10.9	0.003	5.00	0.600	o	100	Pipe/Conduit
28.003	7.813	0.065	120.2	0.000	0.00	0.600	o	150	Pipe/Conduit
31.000	6.618	0.406	16.3	0.004	5.00	0.600	o	100	Pipe/Conduit
31.001	21.177	0.212	99.9	0.013	0.00	0.600	o	100	Pipe/Conduit
31.002	7.570	0.618	12.2	0.000	0.00	0.600	o	150	Pipe/Conduit
32.000	11.963	0.120	99.7	0.005	5.00	0.600	o	100	Pipe/Conduit
32.001	18.858	0.126	149.7	0.008	0.00	0.600	o	150	Pipe/Conduit
31.003	15.181	0.101	150.3	0.001	0.00	0.600	o	150	Pipe/Conduit
33.000	7.916	0.423	18.7	0.007	5.00	0.600	o	100	Pipe/Conduit

PN	US/MH Name	US/CL (m)	US/IL (m)	US C.Depth (m)	DS/CL (m)	DS/IL (m)	DS C.Depth (m)	Ctrl	US/MH
----	---------------	--------------	--------------	----------------------	--------------	--------------	----------------------	------	-------

29.000	R30	129.502	128.864	0.538	129.496	128.600	0.796	450	
28.001	S49	129.496	128.600	0.796	129.005	128.305	0.600	450	
28.002	S50	129.005	128.305	0.600	129.218	128.178	0.940	450	
30.000	R31	129.371	128.732	0.539	129.218	128.178	0.940	450	
28.003	S51	129.218	128.128	0.940	129.154	128.063	0.941	450	
31.000	S52	128.532	127.973	0.459	128.568	127.567	0.901	450	
31.001	S53	128.568	127.567	0.901	127.978	127.355	0.523	450	
31.002	S54	127.978	127.305	0.523	127.648	126.687	0.811	450	
32.000	RE37	127.853	126.983	0.770	127.540	126.863	0.577	450	
32.001	S55	127.540	126.813	0.577	127.648	126.687	0.811	450	
31.003	S56	127.648	126.687	0.811	127.772	126.586	1.036	450	
33.000	S57A	127.659	127.059	0.500	127.772	126.636	1.036	450	

Scott Hughes Design Ltd								Page 8
The Flint Glass Works 64 Jersey Street Manchester M4 6JW			Church Raike Chipping					
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX			Designed by AB Checked by PG					
Micro Drainage								Network 2017.1.1



Existing Network Details for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	k (mm)	HYD SECT	DIA (mm)	Section Type
31.004	15.705	0.079	200.0	0.027	0.00	0.600	o	225	Pipe/Conduit
*	34.000	10.000	0.060	166.7	0.000	5.00	0.600	o	225 Pipe/Conduit
31.005	18.376	0.092	199.7	0.016	0.00	0.600	o	225	Pipe/Conduit
35.000	22.275	0.247	90.2	0.010	5.00	0.600	o	100	Pipe/Conduit
35.001	6.388	0.691	9.3	0.000	0.00	0.600	o	100	Pipe/Conduit
*	31.006	7.140	-0.714	-10.0	0.000	0.00	0.600	o	100 Pipe/Conduit
*	31.007	6.920	-0.136	-50.9	0.000	0.00	0.600	o	150 Pipe/Conduit
36.000	10.096	0.083	121.6	0.004	5.00	0.600	o	100	Pipe/Conduit
36.001	2.804	0.894	3.1	0.000	0.00	0.600	o	100	Pipe/Conduit
*	31.008	13.133	0.040	328.3	0.020	0.00	0.600	o	1800 Pipe/Conduit
1.012	11.122	0.066	168.5	0.000	0.00	0.600	o	225	Pipe/Conduit
1.013	33.645	0.200	168.2	0.000	0.00	0.600	o	225	Pipe/Conduit
37.000	19.782	0.752	26.3	0.011	5.00	0.600	o	100	Pipe/Conduit

PN	US/MH Name	US/CL (m)	US/IL (m)	US C.Depth (m)	DS/CL (m)	DS/IL (m)	DS C.Depth (m)	Ctrl	US/MH (mm)	
31.004	S57	127.772	126.511	1.036	127.888	126.432	1.231		1500	
*	34.000	Tank	127.888	126.890	0.773	127.888	126.830	0.833	1200	
31.005	S58	127.888	126.432	1.231	128.068	126.340	1.503		1800	
35.000	RE39	127.889	127.278	0.511	128.113	127.031	0.982		450	
35.001	S59	128.113	127.031	0.982	128.068	126.340	1.628		450	
*	31.006	S60	128.068	126.340	1.628	128.404	127.054	1.250	Pump 1500	
*	31.007	S60A	128.404	127.054	1.200	128.860	127.190	1.520	1200	
36.000	RE40	128.826	128.226	0.500	128.925	128.143	0.682		450	
36.001	S62	128.925	128.143	0.682	128.860	127.249	1.511		450	
*	31.008	S63	128.860	125.540	1.520	129.154	125.500	1.854		2700
1.012	S64	129.154	125.500	3.429	129.326	125.434	3.667	Orifice	3000	
1.013	99	129.326	125.434	3.667	128.811	125.234	3.352		1200	
37.000	R32	130.764	130.154	0.510	130.452	129.402	0.950		450	

Scott Hughes Design Ltd								Page 9
The Flint Glass Works 64 Jersey Street Manchester M4 6JW			Church Raike Chipping					
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX			Designed by AB Checked by PG					
Micro Drainage								Network 2017.1.1



Existing Network Details for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	k (mm)	HYD SECT	DIA (mm)	Section Type
37.001	16.054	0.161	99.7	0.014	0.00	0.600	o	100	Pipe/Conduit
38.000	25.525	0.859	29.7	0.009	5.00	0.600	o	100	Pipe/Conduit
37.002	14.598	0.941	15.5	0.003	0.00	0.600	o	100	Pipe/Conduit
39.000	8.191	0.102	80.3	0.010	5.00	0.600	o	100	Pipe/Conduit
39.001	15.685	0.549	28.6	0.006	0.00	0.600	o	100	Pipe/Conduit
37.003	15.964	0.534	29.9	0.004	0.00	0.600	o	150	Pipe/Conduit
40.000	9.868	0.348	28.4	0.002	5.00	0.600	o	100	Pipe/Conduit
40.001	19.720	1.178	16.7	0.004	0.00	0.600	o	100	Pipe/Conduit
37.004	12.942	0.117	110.6	0.004	0.00	0.600	o	150	Pipe/Conduit
37.005	9.378	0.112	83.7	0.000	0.00	0.600	o	150	Pipe/Conduit
41.000	38.402	0.863	44.5	0.025	5.00	0.600	o	100	Pipe/Conduit
37.006	2.335	0.087	26.8	0.000	0.00	0.600	o	150	Pipe/Conduit

PN	US/MH Name	US/CL (m)	US/IL (m)	US C.Depth (m)	DS/CL (m)	DS/IL (m)	DS C.Depth (m)	Ctrl	US/MH (mm)
37.001	S53	130.452	129.402	0.950	130.018	129.241	0.677	450	
38.000	R33	130.700	130.100	0.500	130.018	129.241	0.677	450	
37.002	S54	130.018	129.241	0.677	128.920	128.300	0.520	450	
39.000	R34	129.709	129.075	0.534	129.962	128.973	0.889	450	
39.001	S55	129.962	128.973	0.889	128.920	128.424	0.396	450	
37.003	S56	128.920	128.250	0.520	128.804	127.716	0.938	450	
40.000	R35	129.892	129.292	0.500	129.644	128.944	0.600	450	
40.001	S57	129.644	128.944	0.600	128.804	127.766	0.938	450	
37.004	S58	128.804	127.716	0.938	128.595	127.599	0.846	450	
37.005	110	128.595	127.599	0.846	128.437	127.487	0.800	1200	
41.000	R36	129.247	128.400	0.747	128.437	127.537	0.800	450	
37.006	S59	128.437	127.487	0.800	128.811	127.400	1.261	450	

Scott Hughes Design Ltd		Page 10
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

Existing Network Details for Storm

PN	Length	Fall	Slope	I.Area	T.E.	k	HYD	DIA	Section	Type
	(m)	(m)	(1:X)	(ha)	(mins)	(mm)	SECT	(mm)		
1.014	21.986	0.474	46.4	0.000	0.00	0.600	o	225	Pipe/Conduit	
1.015	18.842	0.598	31.5	0.000	0.00	0.600	o	225	Pipe/Conduit	
1.016	4.994	0.262	19.1	0.015	0.00	0.600	o	225	Pipe/Conduit	

PN	US/MH	US/CL	US/IL	US	DS/CL	DS/IL	DS	Ctrl	US/MH
Name	(m)	(m)	C.Depth	(m)	(m)	(m)	C.Depth	(mm)	
			(m)				(m)		
1.014	112	128.811	125.234	3.352	126.116	124.760	1.131	Complex	1500
1.015	113	126.116	124.760	1.131	126.616	124.162	2.229		1200
1.016	114	126.616	124.162	2.229	126.000	123.900	1.875		1200

Scott Hughes Design Ltd								Page 11
The Flint Glass Works 64 Jersey Street Manchester M4 6JW				Church Raike Chipping				
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX				Designed by AB Checked by PG				
Micro Drainage Network 2017.1.1								

Pipeline Schedules for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	o	100	R1	136.578	135.850	0.628	Open Manhole	450
1.001	o	100	S01	136.012	135.412	0.500	Open Manhole	450
2.000	o	100	R2	136.513	135.913	0.500	Open Manhole	450
1.002	o	100	S02	135.990	135.274	0.616	Open Manhole	450
3.000	o	100	R5	135.900	135.300	0.500	Open Manhole	450
3.001	o	100	S03	136.086	135.176	0.810	Open Manhole	450
4.000	o	100	R4	136.953	136.600	0.253	Open Manhole	450
3.002	o	100	S04	136.418	135.119	1.199	Open Manhole	450
3.003	o	100	S05	136.003	134.845	1.058	Open Manhole	450
1.003	o	150	S06	135.845	134.495	1.200	Open Manhole	1200
5.000	o	100	R7	134.325	133.625	0.600	Open Manhole	450
5.001	o	100	S07	134.300	133.500	0.700	Open Manhole	450
6.000	o	100	R8	134.800	134.128	0.572	Open Manhole	450

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	12.130	27.7	S01	136.012	135.412	0.500	Open Manhole	450
1.001	13.774	99.8	S02	135.990	135.274	0.616	Open Manhole	450
2.000	12.280	19.2	S02	135.990	135.274	0.616	Open Manhole	450
1.002	7.074	9.7	S06	135.845	134.545	1.200	Open Manhole	1200
3.000	12.368	99.7	S03	136.086	135.176	0.810	Open Manhole	450
3.001	5.744	100.8	S04	136.418	135.119	1.199	Open Manhole	450
4.000	14.503	9.8	S04	136.418	135.119	1.199	Open Manhole	450
3.002	16.189	59.1	S05	136.003	134.845	1.058	Open Manhole	450
3.003	8.181	27.3	S06	135.845	134.545	1.200	Open Manhole	1200
1.003	25.181	11.8	S09	133.368	132.355	0.863	Open Manhole	1800
5.000	9.905	79.2	S07	134.300	133.500	0.700	Open Manhole	450
5.001	14.030	20.8	S08	134.018	132.824	1.094	Open Manhole	450
6.000	20.911	16.0	S08	134.018	132.824	1.094	Open Manhole	450

Scott Hughes Design Ltd								Page 12
The Flint Glass Works 64 Jersey Street Manchester M4 6JW				Church Raike Chipping				
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX				Designed by AB Checked by PG				
Micro Drainage Network 2017.1.1								

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
5.002	o	100	S08	134.018	132.824	1.094	Open Manhole	450
1.004	o	675	S09	133.368	131.000	1.693	Open Manhole	1800
7.000	o	100	R9	133.047	132.434	0.513	Open Manhole	450
7.001	o	100	S10	132.956	131.922	0.934	Open Manhole	450
8.000	o	100	R10	133.497	132.897	0.500	Open Manhole	450
8.001	o	100	S11	133.059	132.351	0.608	Open Manhole	450
7.002	o	100	S12	132.519	131.800	0.619	Open Manhole	450
9.000	o	100	R11	132.284	131.684	0.500	Open Manhole	450
9.001	o	100	S13	132.279	131.516	0.663	Open Manhole	450
9.002	o	150	S14	132.389	131.278	0.961	Open Manhole	450
7.003	o	150	S15	132.607	131.183	1.274	Open Manhole	450
7.004	o	150	S16	132.893	131.119	1.624	Open Manhole	450
1.005	o	900	S17	133.223	130.268	2.055	Open Manhole	2100

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
5.002	7.107	17.0	S09	133.368	132.405	0.863	Open Manhole	1800
1.004	12.963	25.6	S17	133.223	130.493	2.055	Open Manhole	2100
7.000	15.070	29.4	S10	132.956	131.922	0.934	Open Manhole	450
7.001	12.191	99.9	S12	132.519	131.800	0.619	Open Manhole	450
8.000	14.443	26.5	S11	133.059	132.351	0.608	Open Manhole	450
8.001	14.860	27.0	S12	132.519	131.800	0.619	Open Manhole	450
7.002	8.810	15.5	S15	132.607	131.233	1.274	Open Manhole	450
9.000	11.954	71.2	S13	132.279	131.516	0.663	Open Manhole	450
9.001	18.787	99.9	S14	132.389	131.328	0.961	Open Manhole	450
9.002	14.276	150.3	S15	132.607	131.183	1.274	Open Manhole	450
7.003	6.416	100.3	S16	132.893	131.119	1.624	Open Manhole	450
7.004	8.698	86.1	S17	133.223	131.018	2.055	Open Manhole	2100
1.005	27.837	103.9	S21	133.700	130.000	2.800	Open Manhole	2400

Scott Hughes Design Ltd		Page 13
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
10.000	o	100	R12	134.495	133.800	0.595	Open Manhole	450	
11.000	o	100	R13	134.005	133.306	0.599	Open Manhole	450	
10.001	o	100	S18	134.199	133.197	0.902	Open Manhole	450	
12.000	o	100	R14	133.325	132.702	0.523	Open Manhole	450	
10.002	o	100	S19	133.603	132.595	0.908	Open Manhole	450	
13.000	o	100	R15	133.928	133.456	0.372	Open Manhole	450	
10.003	o	100	S20	133.760	132.470	1.190	Open Manhole	450	
1.006	o	900	S21	133.700	130.000	2.800	Open Manhole	2400	
14.000	o	100	R16	133.600	133.000	0.500	Open Manhole	450	
14.001	o	100	S22	133.901	132.872	0.929	Open Manhole	450	
14.002	o	100	S23	133.864	132.692	1.072	Open Manhole	450	
14.003	o	100	S24	133.547	132.531	0.916	Open Manhole	450	

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
10.000	32.195	53.4	S18	134.199	133.197	0.902	Open Manhole	450	
11.000	10.920	100.2	S18	134.199	133.197	0.902	Open Manhole	450	
10.001	18.123	30.1	S19	133.603	132.595	0.908	Open Manhole	450	
12.000	10.730	100.3	S19	133.603	132.595	0.908	Open Manhole	450	
10.002	12.540	100.3	S20	133.760	132.470	1.190	Open Manhole	450	
13.000	21.651	22.0	S20	133.760	132.470	1.190	Open Manhole	450	
10.003	6.576	82.2	S21	133.700	132.390	1.210	Open Manhole	2400	
1.006	25.607	324.1	S32	132.627	129.921	1.806	Open Manhole	2100	
14.000	13.228	103.3	S22	133.901	132.872	0.929	Open Manhole	450	
14.001	9.272	51.5	S23	133.864	132.692	1.072	Open Manhole	450	
14.002	15.585	96.8	S24	133.547	132.531	0.916	Open Manhole	450	
14.003	17.675	47.6	S28	132.874	132.160	0.614	Open Manhole	450	

Scott Hughes Design Ltd								Page 14
The Flint Glass Works 64 Jersey Street Manchester M4 6JW				Church Raike Chipping				
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX				Designed by AB Checked by PG				
Micro Drainage				Network 2017.1.1				



PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
15.000	o	100	S25	133.161	132.560	0.501	Open Manhole	450	
15.001	o	100	S26	133.543	132.432	1.011	Open Manhole	450	
14.004	o	100	S28	132.874	132.160	0.614	Open Manhole	450	
16.000	o	100	R17	133.100	132.500	0.500	Open Manhole	450	
16.001	o	100	S29	132.851	132.151	0.600	Open Manhole	450	
16.002	o	100	S30	132.797	131.913	0.784	Open Manhole	450	
17.000	o	100	R18	133.424	132.663	0.661	Open Manhole	450	
16.003	o	100	S31	132.788	131.849	0.839	Open Manhole	450	
1.007	o	300	S32	132.627	129.921	2.406	Open Manhole	2100	
1.008	o	1500	48	131.550	126.128	3.922	Open Manhole	2400	
18.000	o	100	49	130.085	129.383	0.602	Open Manhole	1200	
18.001	o	100	S33	130.300	129.263	0.937	Open Manhole	450	
19.000	o	100	50	130.064	129.464	0.500	Open Manhole	1200	

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
15.000	11.509	89.9	S26	133.543	132.432	1.011	Open Manhole	450	
15.001	13.456	49.5	S28	132.874	132.160	0.614	Open Manhole	450	
14.004	6.280	8.4	S32	132.627	131.410	1.117	Open Manhole	2100	
16.000	21.015	60.2	S29	132.851	132.151	0.600	Open Manhole	450	
16.001	14.053	59.0	S30	132.797	131.913	0.784	Open Manhole	450	
16.002	3.790	59.2	S31	132.788	131.849	0.839	Open Manhole	450	
17.000	19.719	24.2	S31	132.788	131.849	0.839	Open Manhole	450	
16.003	5.872	5.2	S32	132.627	130.721	1.806	Open Manhole	2100	
1.007	21.717	301.6	48	131.550	129.849	1.401	Open Manhole	2400	
1.008	10.036	200.7	S43	131.084	126.078	3.506	Open Manhole	2700	
18.000	12.005	100.0	S33	130.300	129.263	0.937	Open Manhole	450	
18.001	10.114	42.9	S34	129.921	129.027	0.794	Open Manhole	450	
19.000	12.481	28.6	S34	129.921	129.027	0.794	Open Manhole	450	

Scott Hughes Design Ltd								Page 15
The Flint Glass Works 64 Jersey Street Manchester M4 6JW				Church Raike Chipping				
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX				Designed by AB Checked by PG				
Micro Drainage								
Network 2017.1.1								

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
18.002	o	100	S34	129.921	129.027	0.794	Open Manhole	450	
18.003	o	100	S35	130.546	128.914	1.532	Open Manhole	450	
20.000	o	100	R21	130.600	130.000	0.500	Open Manhole	450	
20.001	o	100	S36	130.657	129.896	0.661	Open Manhole	450	
20.002	o	100	S37	131.443	129.704	1.639	Open Manhole	450	
18.004	o	150	S38	131.069	128.650	2.269	Open Manhole	450	
18.005	o	150	57	131.347	128.411	2.786	Open Manhole	1200	
21.000	o	100	R22	132.100	131.500	0.500	Open Manhole	450	
21.001	o	100	S39	132.188	131.432	0.656	Open Manhole	450	
21.002	o	100	S40	132.357	131.236	1.021	Open Manhole	450	
22.000	o	100	R23	131.811	131.273	0.438	Open Manhole	450	
22.001	o	100	S41	131.098	129.987	1.011	Open Manhole	450	
22.002	o	100	63	131.061	129.951	1.010	Open Manhole	1200	
23.000	o	150	R25	130.766	130.116	0.500	Open Manhole	450	

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
18.002	11.335	100.3	S35	130.546	128.914	1.532	Open Manhole	450	
18.003	19.965	93.3	S38	131.069	128.700	2.269	Open Manhole	450	
20.000	15.367	147.8	S36	130.657	129.896	0.661	Open Manhole	450	
20.001	16.829	87.7	S37	131.443	129.704	1.639	Open Manhole	450	
20.002	8.356	8.3	S38	131.069	128.700	2.269	Open Manhole	450	
18.004	8.809	36.9	57	131.347	128.411	2.786	Open Manhole	1200	
18.005	8.457	25.4	S43	131.084	128.078	2.856	Open Manhole	2700	
21.000	6.785	99.8	S39	132.188	131.432	0.656	Open Manhole	450	
21.001	11.575	59.1	S40	132.357	131.236	1.021	Open Manhole	450	
21.002	29.154	20.6	S42	131.237	129.823	1.314	Open Manhole	450	
22.000	20.875	16.2	S41	131.098	129.987	1.011	Open Manhole	450	
22.001	3.637	101.0	63	131.061	129.951	1.010	Open Manhole	1200	
22.002	12.756	99.7	S42	131.237	129.823	1.314	Open Manhole	450	
23.000	16.845	49.1	S42	131.237	129.773	1.314	Open Manhole	450	

Scott Hughes Design Ltd								Page 16
The Flint Glass Works 64 Jersey Street Manchester M4 6JW				Church Raike Chipping				
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX				Designed by AB Checked by PG				
Micro Drainage Network 2017.1.1								



Pipeline Schedules for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
21.003	o	150	S42	131.237	129.773	1.314	Open Manhole	450	
24.000	o	225	H01	129.663	127.633	1.805	Open Manhole	450	
24.001	o	225	H02	130.448	127.573	2.650	Open Manhole	1200	
1.009	o	1500	S43	131.084	126.078	3.506	Open Manhole	2700	
1.010	o	1500	S44	130.408	125.991	2.917	Open Manhole	2400	
25.000	o	100	R26	130.316	129.716	0.500	Open Manhole	450	
25.001	o	100	S45	129.952	129.100	0.752	Open Manhole	450	
26.000	o	100	R27	130.371	129.771	0.500	Open Manhole	450	
27.000	o	100	R28	129.700	129.100	0.500	Open Manhole	450	
25.002	o	100	S46	129.816	128.994	0.722	Open Manhole	450	
1.011	o	1800	S47	129.822	125.609	2.413	Open Manhole	2700	
28.000	o	100	R29	129.730	129.130	0.500	Open Manhole	450	

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
21.003	5.919	100.3	S43	131.084	129.714	1.220	Open Manhole	2700	
24.000	10.125	168.8	H02	130.448	127.573	2.650	Open Manhole	1200	
24.001	24.010	109.1	S43	131.084	127.353	3.506	Open Manhole	2700	
1.009	17.386	199.8	S44	130.408	125.991	2.917	Open Manhole	2400	
1.010	16.483	201.0	S47	129.822	125.909	2.413	Open Manhole	2700	
25.000	8.005	13.0	S45	129.952	129.100	0.752	Open Manhole	450	
25.001	10.139	95.7	S46	129.816	128.994	0.722	Open Manhole	450	
26.000	12.271	15.8	S46	129.816	128.994	0.722	Open Manhole	450	
27.000	5.712	53.9	S46	129.816	128.994	0.722	Open Manhole	450	
25.002	5.679	4.0	S47	129.822	127.583	2.139	Open Manhole	2700	
1.011	21.729	199.3	S64	129.154	125.500	1.854	Open Manhole	3000	
28.000	13.507	25.5	S49	129.496	128.600	0.796	Open Manhole	450	

Scott Hughes Design Ltd								Page 17
The Flint Glass Works 64 Jersey Street Manchester M4 6JW				Church Raike Chipping				
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX				Designed by AB Checked by PG				
Micro Drainage				Network 2017.1.1				



Pipeline Schedules for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
29.000	o	100	R30	129.502	128.864	0.538	Open Manhole	450	
28.001	o	100	S49	129.496	128.600	0.796	Open Manhole	450	
28.002	o	100	S50	129.005	128.305	0.600	Open Manhole	450	
30.000	o	100	R31	129.371	128.732	0.539	Open Manhole	450	
28.003	o	150	S51	129.218	128.128	0.940	Open Manhole	450	
31.000	o	100	S52	128.532	127.973	0.459	Open Manhole	450	
31.001	o	100	S53	128.568	127.567	0.901	Open Manhole	450	
31.002	o	150	S54	127.978	127.305	0.523	Open Manhole	450	
32.000	o	100	RE37	127.853	126.983	0.770	Open Manhole	450	
32.001	o	150	S55	127.540	126.813	0.577	Open Manhole	450	
31.003	o	150	S56	127.648	126.687	0.811	Open Manhole	450	
33.000	o	100	S57A	127.659	127.059	0.500	Open Manhole	450	
31.004	o	225	S57	127.772	126.511	1.036	Open Manhole	1500	

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
29.000	8.997	34.1	S49	129.496	128.600	0.796	Open Manhole	450	
28.001	12.025	40.8	S50	129.005	128.305	0.600	Open Manhole	450	
28.002	7.497	59.0	S51	129.218	128.178	0.940	Open Manhole	450	
30.000	6.044	10.9	S51	129.218	128.178	0.940	Open Manhole	450	
28.003	7.813	120.2	S64	129.154	128.063	0.941	Open Manhole	3000	
31.000	6.618	16.3	S53	128.568	127.567	0.901	Open Manhole	450	
31.001	21.177	99.9	S54	127.978	127.355	0.523	Open Manhole	450	
31.002	7.570	12.2	S56	127.648	126.687	0.811	Open Manhole	450	
32.000	11.963	99.7	S55	127.540	126.863	0.577	Open Manhole	450	
32.001	18.858	149.7	S56	127.648	126.687	0.811	Open Manhole	450	
31.003	15.181	150.3	S57	127.772	126.586	1.036	Open Manhole	1500	
33.000	7.916	18.7	S57	127.772	126.636	1.036	Open Manhole	1500	
31.004	15.705	200.0	S58	127.888	126.432	1.231	Open Manhole	1800	

Scott Hughes Design Ltd The Flint Glass Works 64 Jersey Street Manchester M4 6JW		Church Raike Chipping	Page 18
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX		Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1			

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
34.000	o	225	Tank	127.888	126.890	0.773	Open Manhole	1200	
31.005	o	225	S58	127.888	126.432	1.231	Open Manhole	1800	
35.000	o	100	RE39	127.889	127.278	0.511	Open Manhole	450	
35.001	o	100	S59	128.113	127.031	0.982	Open Manhole	450	
31.006	o	100	S60	128.068	126.340	1.628	Open Manhole	1500	
31.007	o	150	S60A	128.404	127.054	1.200	Open Manhole	1200	
36.000	o	100	RE40	128.826	128.226	0.500	Open Manhole	450	
36.001	o	100	S62	128.925	128.143	0.682	Open Manhole	450	
31.008	o	1800	S63	128.860	125.540	1.520	Open Manhole	2700	
1.012	o	225	S64	129.154	125.500	3.429	Open Manhole	3000	
1.013	o	225	99	129.326	125.434	3.667	Open Manhole	1200	
37.000	o	100	R32	130.764	130.154	0.510	Open Manhole	450	
37.001	o	100	S53	130.452	129.402	0.950	Open Manhole	450	

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
34.000	10.000	166.7	S58	127.888	126.830	0.833	Open Manhole	1800	
31.005	18.376	199.7	S60	128.068	126.340	1.503	Open Manhole	1500	
35.000	22.275	90.2	S59	128.113	127.031	0.982	Open Manhole	450	
35.001	6.388	9.3	S60	128.068	126.340	1.628	Open Manhole	1500	
31.006	7.140	-10.0	S60A	128.404	127.054	1.250	Open Manhole	1200	
31.007	6.920	-50.9	S63	128.860	127.190	1.520	Open Manhole	2700	
36.000	10.096	121.6	S62	128.925	128.143	0.682	Open Manhole	450	
36.001	2.804	3.1	S63	128.860	127.249	1.511	Open Manhole	2700	
31.008	13.133	328.3	S64	129.154	125.500	1.854	Open Manhole	3000	
1.012	11.122	168.5	99	129.326	125.434	3.667	Open Manhole	1200	
1.013	33.645	168.2	112	128.811	125.234	3.352	Open Manhole	1500	
37.000	19.782	26.3	S53	130.452	129.402	0.950	Open Manhole	450	
37.001	16.054	99.7	S54	130.018	129.241	0.677	Open Manhole	450	

Scott Hughes Design Ltd								Page 19
The Flint Glass Works 64 Jersey Street Manchester M4 6JW				Church Raike Chipping				
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX				Designed by AB Checked by PG				
Micro Drainage				Network 2017.1.1				



PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
38.000	o	100	R33	130.700	130.100	0.500	Open Manhole	450	
37.002	o	100	S54	130.018	129.241	0.677	Open Manhole	450	
39.000	o	100	R34	129.709	129.075	0.534	Open Manhole	450	
39.001	o	100	S55	129.962	128.973	0.889	Open Manhole	450	
37.003	o	150	S56	128.920	128.250	0.520	Open Manhole	450	
40.000	o	100	R35	129.892	129.292	0.500	Open Manhole	450	
40.001	o	100	S57	129.644	128.944	0.600	Open Manhole	450	
37.004	o	150	S58	128.804	127.716	0.938	Open Manhole	450	
37.005	o	150	110	128.595	127.599	0.846	Open Manhole	1200	
41.000	o	100	R36	129.247	128.400	0.747	Open Manhole	450	
37.006	o	150	S59	128.437	127.487	0.800	Open Manhole	450	
1.014	o	225	112	128.811	125.234	3.352	Open Manhole	1500	

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
38.000	25.525	29.7	S54	130.018	129.241	0.677	Open Manhole	450	
37.002	14.598	15.5	S56	128.920	128.300	0.520	Open Manhole	450	
39.000	8.191	80.3	S55	129.962	128.973	0.889	Open Manhole	450	
39.001	15.685	28.6	S56	128.920	128.424	0.396	Open Manhole	450	
37.003	15.964	29.9	S58	128.804	127.716	0.938	Open Manhole	450	
40.000	9.868	28.4	S57	129.644	128.944	0.600	Open Manhole	450	
40.001	19.720	16.7	S58	128.804	127.766	0.938	Open Manhole	450	
37.004	12.942	110.6	110	128.595	127.599	0.846	Open Manhole	1200	
37.005	9.378	83.7	S59	128.437	127.487	0.800	Open Manhole	450	
41.000	38.402	44.5	S59	128.437	127.537	0.800	Open Manhole	450	
37.006	2.335	26.8	112	128.811	127.400	1.261	Open Manhole	1500	
1.014	21.986	46.4	113	126.116	124.760	1.131	Open Manhole	1200	

Scott Hughes Design Ltd		Page 20
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
1.015	o	225	113	126.116	124.760	1.131	Open Manhole		1200
1.016	o	225	114	126.616	124.162	2.229	Open Manhole		1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
1.015	18.842	31.5	114	126.616	124.162	2.229	Open Manhole		1200
1.016	4.994	19.1		126.000	123.900	1.875	Open Manhole		0

Scott Hughes Design Ltd The Flint Glass Works 64 Jersey Street Manchester M4 6JW		Church Raike Chipping	Page 21
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX		Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1			

Online Controls for Storm

Orifice Manhole: S32, DS/PN: 1.007, Volume (m³): 24.3

Diameter (m) 0.101 Discharge Coefficient 0.600 Invert Level (m) 129.921

Pump Manhole: S60, DS/PN: 31.006, Volume (m³): 3.8

Invert Level (m) 126.340

Depth (m)	Flow (l/s)						
0.200	3.0000	1.800	3.0000	3.400	3.0000	5.000	3.0000
0.400	3.0000	2.000	3.0000	3.600	3.0000	5.200	3.0000
0.600	3.0000	2.200	3.0000	3.800	3.0000	5.400	3.0000
0.800	3.0000	2.400	3.0000	4.000	3.0000	5.600	3.0000
1.000	3.0000	2.600	3.0000	4.200	3.0000	5.800	3.0000
1.200	3.0000	2.800	3.0000	4.400	3.0000	6.000	3.0000
1.400	3.0000	3.000	3.0000	4.600	3.0000		
1.600	3.0000	3.200	3.0000	4.800	3.0000		

Orifice Manhole: S64, DS/PN: 1.012, Volume (m³): 100.1

Diameter (m) 0.135 Discharge Coefficient 0.600 Invert Level (m) 125.500

Complex Manhole: 112, DS/PN: 1.014, Volume (m³): 7.6

Hydro-Brake® Optimum

Unit Reference	MD-SHE-0138-1000-1500-1000
Design Head (m)	1.500
Design Flow (l/s)	10.0
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	138
Invert Level (m)	125.234
Minimum Outlet Pipe Diameter (mm)	225
Suggested Manhole Diameter (mm)	1200

Control Points Head (m) Flow (l/s)

Design Point (Calculated)	1.500	10.0
Flush-Flo™	0.441	10.0
Kick-Flo®	0.933	8.0
Mean Flow over Head Range	-	8.7

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

The Flint Glass Works
64 Jersey Street
Manchester M4 6JW

Church Raike
Chipping

Date 07/06/2018 09:55

Designed by AB

File Church Raike 06.06.18.MDX

Checked by PG

Micro Drainage

Network 2017.1.1



Hydro-Brake® Optimum

Depth (m)	Flow (l/s)						
0.100	5.0	1.200	9.0	3.000	13.9	7.000	20.8
0.200	9.0	1.400	9.7	3.500	14.9	7.500	21.5
0.300	9.7	1.600	10.3	4.000	15.9	8.000	22.2
0.400	10.0	1.800	10.9	4.500	16.8	8.500	22.8
0.500	10.0	2.000	11.4	5.000	17.7	9.000	23.5
0.600	9.8	2.200	12.0	5.500	18.5	9.500	24.1
0.800	9.1	2.400	12.5	6.000	19.3		
1.000	8.3	2.600	13.0	6.500	20.1		

Orifice

Diameter (m) 0.102 Discharge Coefficient 0.600 Invert Level (m) 127.584

Scott Hughes Design Ltd		Page 23
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coeffiecient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1
Number of Online Controls 4 Number of Time/Area Diagrams 0
Number of Offline Controls 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.281
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 18.800 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status ON
DVD Status ON
Inertia Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
720, 960, 1440
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 0, 40

US/MH PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	R1	15 Winter	2	+0%					135.871
1.001	S01	15 Winter	2	+0%	100/15	Summer			135.448
2.000	R2	15 Winter	2	+0%					135.927
1.002	S02	15 Winter	2	+0%	100/15	Summer			135.309
3.000	R5	15 Winter	2	+0%					135.327
3.001	S03	15 Winter	2	+0%	100/15	Summer			135.204
4.000	R4	15 Winter	2	+0%					136.612
3.002	S04	15 Winter	2	+0%	100/15	Summer			135.158
3.003	S05	15 Winter	2	+0%					134.877
1.003	S06	15 Winter	2	+0%					134.533
5.000	R7	15 Winter	2	+0%					133.655
5.001	S07	15 Winter	2	+0%					133.522
6.000	R8	15 Winter	2	+0%					134.146
5.002	S08	15 Winter	2	+0%					132.857
1.004	S09	15 Winter	2	+0%	100/15	Winter			131.048
7.000	R9	15 Winter	2	+0%	100/60	Winter			132.458
7.001	S10	15 Winter	2	+0%	100/30	Summer			131.955
8.000	R10	15 Winter	2	+0%					132.914

Scott Hughes Design Ltd		Page 24
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

US/MH PN	Name	Surcharged Flooded			Pipe		
		Depth (m)	Volume (m³)	Flow / Overflow Cap.	Flow (l/s)	Status	Level Exceeded
1.000	R1	-0.079	0.000	0.10	1.1	OK	
1.001	S01	-0.064	0.000	0.27	1.5	OK	
2.000	R2	-0.086	0.000	0.05	0.6	OK	
1.002	S02	-0.065	0.000	0.26	4.7	OK	
3.000	R5	-0.073	0.000	0.16	0.9	OK	
3.001	S03	-0.072	0.000	0.17	0.9	OK	
4.000	R4	-0.088	0.000	0.03	0.6	OK	
3.002	S04	-0.061	0.000	0.32	2.4	OK	
3.003	S05	-0.068	0.000	0.22	2.4	OK	
1.003	S06	-0.112	0.000	0.14	7.1	OK	
5.000	R7	-0.070	0.000	0.19	1.2	OK	
5.001	S07	-0.078	0.000	0.10	1.3	OK	
6.000	R8	-0.082	0.000	0.07	1.1	OK	
5.002	S08	-0.067	0.000	0.23	3.1	OK	
1.004	S09	-0.627	0.000	0.01	13.4	OK	
7.000	R9	-0.076	0.000	0.13	1.4	OK	
7.001	S10	-0.067	0.000	0.23	1.3	OK	
8.000	R10	-0.083	0.000	0.07	0.8	OK	

Scott Hughes Design Ltd		Page 25
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

US/MH PN	Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
8.001	S11	15 Winter	2	+0%	100/30	Winter		
7.002	S12	15 Winter	2	+0%	100/15	Winter		
9.000	R11	15 Winter	2	+0%	100/15	Winter	100/30	Winter
9.001	S13	15 Winter	2	+0%	100/15	Winter	100/30	Winter
9.002	S14	15 Winter	2	+0%	100/15	Summer	100/30	Winter
7.003	S15	15 Winter	2	+0%	100/15	Summer		
7.004	S16	15 Winter	2	+0%	100/15	Summer		
1.005	S17	30 Winter	2	+0%	100/15	Summer		
10.000	R12	15 Winter	2	+0%				
11.000	R13	15 Winter	2	+0%	100/15	Summer		
10.001	S18	15 Winter	2	+0%	100/15	Summer		
12.000	R14	15 Winter	2	+0%	30/15	Summer		
10.002	S19	15 Winter	2	+0%	30/15	Summer		
13.000	R15	15 Winter	2	+0%				
10.003	S20	15 Winter	2	+0%	2/15	Winter		
1.006	S21	30 Winter	2	+0%	30/60	Winter		
14.000	R16	15 Winter	2	+0%	100/15	Summer		
14.001	S22	15 Winter	2	+0%	100/15	Summer		
14.002	S23	15 Winter	2	+0%	100/15	Summer		
14.003	S24	15 Winter	2	+0%	100/15	Summer		
15.000	S25	15 Winter	2	+0%	100/60	Winter		
15.001	S26	15 Winter	2	+0%	100/30	Winter		
14.004	S28	15 Winter	2	+0%	100/30	Winter		
16.000	R17	15 Winter	2	+0%	100/30	Winter		
16.001	S29	15 Winter	2	+0%	100/30	Winter		
16.002	S30	15 Winter	2	+0%	100/15	Summer		
17.000	R18	15 Winter	2	+0%				
16.003	S31	15 Winter	2	+0%	100/30	Summer		
1.007	S32	30 Winter	2	+0%	2/15	Summer	100/60	Winter
1.008	48	180 Winter	2	+0%	100/60	Winter		
18.000	49	15 Winter	2	+0%	100/15	Summer		
18.001	S33	15 Winter	2	+0%	100/15	Summer		
19.000	50	15 Winter	2	+0%	100/15	Summer		
18.002	S34	15 Winter	2	+0%	30/15	Summer		
18.003	S35	15 Winter	2	+0%	30/15	Summer		
20.000	R21	15 Winter	2	+0%				
20.001	S36	15 Winter	2	+0%				
20.002	S37	15 Winter	2	+0%				
18.004	S38	15 Winter	2	+0%				
18.005	57	15 Winter	2	+0%				
21.000	R22	15 Winter	2	+0%				
21.001	S39	15 Winter	2	+0%				
21.002	S40	15 Winter	2	+0%				
22.000	R23	15 Winter	2	+0%				
22.001	S41	15 Winter	2	+0%	100/15	Summer		
22.002	63	15 Winter	2	+0%	100/15	Summer		
23.000	R25	15 Winter	2	+0%				
21.003	S42	15 Winter	2	+0%	100/15	Summer		

Scott Hughes Design Ltd								Page 26		
The Flint Glass Works 64 Jersey Street Manchester M4 6JW			Church Raike Chipping							
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX			Designed by AB Checked by PG							
Micro Drainage			Network 2017.1.1							



2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

US/MH PN	Water Level Name	Surcharged Depth (m)	Flooded Volume (m³)	Pipe			Status	Level Exceeded
				Flow / Cap.	Overflow (l/s)	Flow (l/s)		
8.001	S11	132.374	-0.077	0.000	0.12	1.4	OK	
7.002	S12	131.832	-0.068	0.000	0.22	3.1	OK	
9.000	R11	131.704	-0.080	0.000	0.09	0.6	OK	5
9.001	S13	131.546	-0.070	0.000	0.19	1.1	OK	5
9.002	S14	131.323	-0.105	0.000	0.20	2.6	OK	5
7.003	S15	131.248	-0.085	0.000	0.39	5.8	OK	
7.004	S16	131.179	-0.090	0.000	0.34	5.8	OK	
1.005	S17	130.445	-0.723	0.000	0.02	20.9	OK	
10.000	R12	133.831	-0.069	0.000	0.20	1.6	OK	
11.000	R13	133.321	-0.085	0.000	0.05	0.3	OK	
10.001	S18	133.226	-0.071	0.000	0.18	1.9	OK	
12.000	R14	132.735	-0.067	0.000	0.24	1.4	OK	
10.002	S19	132.665	-0.030	0.000	0.82	4.7	OK	
13.000	R15	133.472	-0.084	0.000	0.06	0.8	OK	
10.003	S20	132.579	0.009	0.000	1.07	6.4 SURCHARGED		
1.006	S21	130.444	-0.456	0.000	0.02	13.6	OK	
14.000	R16	133.022	-0.078	0.000	0.11	0.6	OK	
14.001	S22	132.897	-0.075	0.000	0.14	1.1	OK	
14.002	S23	132.738	-0.054	0.000	0.43	2.5	OK	
14.003	S24	132.578	-0.053	0.000	0.45	3.8	OK	
15.000	S25	132.581	-0.079	0.000	0.10	0.6	OK	
15.001	S26	132.457	-0.075	0.000	0.13	1.1	OK	
14.004	S28	132.195	-0.065	0.000	0.26	4.9	OK	
16.000	R17	132.527	-0.073	0.000	0.16	1.2	OK	
16.001	S29	132.182	-0.069	0.000	0.21	1.6	OK	
16.002	S30	131.950	-0.063	0.000	0.29	2.0	OK	
17.000	R18	132.694	-0.069	0.000	0.20	2.4	OK	
16.003	S31	131.878	-0.071	0.000	0.18	4.3	OK	
1.007	S32	130.442	0.221	0.000	0.26	14.6 SURCHARGED	1	
1.008	48	126.429	-1.199	0.000	0.01	11.5	OK	
18.000	49	129.405	-0.078	0.000	0.10	0.6	OK	
18.001	S33	129.285	-0.078	0.000	0.11	1.0	OK	
19.000	50	129.479	-0.085	0.000	0.06	0.6	OK	
18.002	S34	129.072	-0.055	0.000	0.41	2.3	OK	
18.003	S35	128.977	-0.037	0.000	0.71	4.3	OK	
20.000	R21	130.024	-0.076	0.000	0.13	0.6	OK	
20.001	S36	129.926	-0.070	0.000	0.20	1.2	OK	
20.002	S37	129.723	-0.081	0.000	0.08	1.6	OK	
18.004	S38	128.699	-0.101	0.000	0.24	6.1	OK	
18.005	57	128.456	-0.105	0.000	0.20	6.1	OK	
21.000	R22	131.519	-0.081	0.000	0.08	0.4	OK	
21.001	S39	131.458	-0.074	0.000	0.15	1.1	OK	
21.002	S40	131.268	-0.068	0.000	0.22	2.9	OK	
22.000	R23	131.294	-0.079	0.000	0.10	1.5	OK	
22.001	S41	130.024	-0.063	0.000	0.30	1.5	OK	
22.002	63	129.998	-0.053	0.000	0.44	2.5	OK	
23.000	R25	130.138	-0.128	0.000	0.05	1.2	OK	

Scott Hughes Design Ltd The Flint Glass Works 64 Jersey Street Manchester M4 6JW		Church Raike Chipping	Page 27
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX		Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1			

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Water Surcharged Flooded			Pipe			Level Exceeded
		Level (m)	Depth (m)	Volume (m³)	Flow / Overflow Cap.	Flow (l/s)	Status	
21.003	S42	129.847	-0.076	0.000	0.48	7.1	OK	

Scott Hughes Design Ltd		Page 28
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

US/MH PN	Storm Name	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
24.000	H01	15 Winter	2	+0%	100/120 Summer		
24.001	H02	15 Winter	2	+0%	100/120 Summer		
1.009	S43	180 Winter	2	+0%	100/60 Winter		
1.010	S44	180 Winter	2	+0%	100/60 Winter		
25.000	R26	15 Winter	2	+0%			
25.001	S45	15 Winter	2	+0%	100/15 Summer		
26.000	R27	15 Winter	2	+0%			
27.000	R28	15 Winter	2	+0%			
25.002	S46	15 Winter	2	+0%			
1.011	S47	180 Winter	2	+0%	100/60 Summer		
28.000	R29	15 Winter	2	+0%			
29.000	R30	15 Winter	2	+0%			
28.001	S49	15 Winter	2	+0%			
28.002	S50	15 Winter	2	+0%	100/120 Winter		
30.000	R31	15 Winter	2	+0%			
28.003	S51	15 Winter	2	+0%	100/120 Winter		
31.000	S52	15 Winter	2	+0%			
31.001	S53	15 Winter	2	+0%	100/15 Summer		
31.002	S54	15 Winter	2	+0%			
32.000	RE37	15 Winter	2	+0%	30/15 Summer		
32.001	S55	30 Winter	2	+0%	30/15 Summer		
31.003	S56	30 Winter	2	+0%	2/30 Winter		
33.000	S57A	15 Winter	2	+0%	30/15 Winter		
31.004	S57	30 Winter	2	+0%	2/15 Summer		
34.000	Tank	120 Winter	2	+0%	100/15 Winter		
31.005	S58	30 Winter	2	+0%	2/15 Summer		
35.000	RE39	15 Winter	2	+0%	100/15 Summer		
35.001	S59	15 Winter	2	+0%	30/15 Winter		
31.006	S60	30 Winter	2	+0%	2/15 Summer		0
31.007	S60A	180 Winter	2	+0%	2/15 Summer	100/120 Winter	
36.000	RE40	15 Winter	2	+0%	100/120 Winter		
36.001	S62	15 Winter	2	+0%	100/120 Winter		
31.008	S63	180 Winter	2	+0%	100/60 Summer		
1.012	S64	180 Winter	2	+0%	2/15 Summer		
1.013	99	180 Winter	2	+0%	2/15 Summer		
37.000	R32	15 Winter	2	+0%	100/15 Summer		
37.001	S53	15 Winter	2	+0%	30/15 Summer		
38.000	R33	15 Winter	2	+0%			
37.002	S54	15 Winter	2	+0%	100/15 Summer		
39.000	R34	15 Winter	2	+0%			
39.001	S55	15 Winter	2	+0%	100/15 Winter		
37.003	S56	15 Winter	2	+0%	100/15 Summer		
40.000	R35	15 Winter	2	+0%			
40.001	S57	15 Winter	2	+0%			
37.004	S58	15 Winter	2	+0%	30/15 Summer		
37.005	110	15 Winter	2	+0%	30/15 Summer		
41.000	R36	15 Winter	2	+0%	100/15 Summer		
37.006	S59	15 Winter	2	+0%	30/15 Summer		

Scott Hughes Design Ltd								Page 29
The Flint Glass Works 64 Jersey Street Manchester M4 6JW								
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX								
Micro Drainage Network 2017.1.1								



2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Pipe			Status	Level Exceeded
					Flow / Cap.	Overflow (l/s)	Flow (l/s)		
24.000	H01	127.689	-0.169	0.000	0.14		4.7	OK	
24.001	H02	127.621	-0.177	0.000	0.10		4.6	OK	
1.009	S43	126.429	-1.149	0.000	0.01		16.6	OK	
1.010	S44	126.429	-1.062	0.000	0.01		15.7	OK	
25.000	R26	129.727	-0.089	0.000	0.03		0.5	OK	
25.001	S45	129.138	-0.062	0.000	0.30		1.7	OK	
26.000	R27	129.783	-0.088	0.000	0.03		0.5	OK	
27.000	R28	129.116	-0.084	0.000	0.06		0.5	OK	
25.002	S46	129.015	-0.079	0.000	0.10		2.6	OK	
1.011	S47	126.429	-0.980	0.000	0.00		14.5	OK	
28.000	R29	129.141	-0.089	0.000	0.03		0.3	OK	
29.000	R30	128.878	-0.086	0.000	0.05		0.5	OK	
28.001	S49	128.626	-0.074	0.000	0.15		1.4	OK	
28.002	S50	128.338	-0.067	0.000	0.23		1.6	OK	
30.000	R31	128.743	-0.089	0.000	0.03		0.5	OK	
28.003	S51	128.167	-0.111	0.000	0.15		2.1	OK	
31.000	S52	127.987	-0.086	0.000	0.04		0.6	OK	
31.001	S53	127.610	-0.057	0.000	0.39		2.3	OK	
31.002	S54	127.327	-0.128	0.000	0.05		2.3	OK	
32.000	RE37	127.007	-0.076	0.000	0.13		0.8	OK	
32.001	S55	126.881	-0.082	0.000	0.11		1.5	OK	
31.003	S56	126.879	0.042	0.000	0.27		3.6	SURCHARGED	
33.000	S57A	127.078	-0.081	0.000	0.08		1.1	OK	
31.004	S57	126.875	0.139	0.000	0.18		5.8	SURCHARGED	
34.000	Tank	126.890	-0.225	0.000	0.00		0.0	OK	
31.005	S58	126.871	0.213	0.000	0.13		4.2	SURCHARGED	
35.000	RE39	127.312	-0.066	0.000	0.24		1.5	OK	
35.001	S59	127.050	-0.081	0.000	0.08		1.5	OK	
31.006	S60	126.865	0.425	0.000	1.05	0.0	3.0	SURCHARGED	7
31.007	S60A	127.340	0.136	0.000	0.40		3.0	SURCHARGED	
36.000	RE40	128.249	-0.077	0.000	0.12		0.6	OK	
36.001	S62	128.153	-0.090	0.000	0.02		0.6	OK	
31.008	S63	126.428	-0.912	0.000	0.00		2.9	OK	
1.012	S64	126.428	0.703	0.000	0.36		12.1	SURCHARGED	
1.013	99	126.362	0.703	0.000	0.29		10.9	SURCHARGED	
37.000	R32	130.179	-0.075	0.000	0.14		1.7	OK	
37.001	S53	129.458	-0.044	0.000	0.59		3.4	OK	
38.000	R33	130.124	-0.076	0.000	0.12		1.3	OK	
37.002	S54	129.282	-0.059	0.000	0.35		5.1	OK	
39.000	R34	129.108	-0.067	0.000	0.24		1.5	OK	
39.001	S55	129.004	-0.069	0.000	0.21		2.3	OK	
37.003	S56	128.302	-0.098	0.000	0.26		7.9	OK	
40.000	R35	129.303	-0.089	0.000	0.03		0.3	OK	
40.001	S57	128.959	-0.085	0.000	0.06		0.8	OK	
37.004	S58	127.801	-0.065	0.000	0.60		9.3	OK	
37.005	110	127.677	-0.072	0.000	0.54		9.3	OK	
41.000	R36	128.445	-0.055	0.000	0.41		3.7	OK	

Scott Hughes Design Ltd The Flint Glass Works 64 Jersey Street Manchester M4 6JW		Church Raike Chipping	Page 30
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX		Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1			

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Water Surcharged Flooded			Pipe			Level Exceeded
		Level (m)	Depth (m)	Volume (m³)	Flow / Overflow Cap.	Flow (l/s)	Status	
37.006	S59	127.579	-0.058	0.000	0.70		12.9	OK

Scott Hughes Design Ltd		Page 31
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

US/MH	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
PN	Name	Storm					
1.014	112	180 Winter	2	+0%	2/15 Summer		126.341
1.015	113	1440 Summer	2	+0%			124.810
1.016	114	15 Winter	2	+0%			124.222

US/MH	Depth	Volume	Flow / Overflow Cap.	Flow (l/s)	Flow (l/s)	Pipe Status	Level Exceeded
PN	Name	(m)	(m³)				
1.014	112	0.882	0.000	0.14		9.5 SURCHARGED	
1.015	113	-0.175	0.000	0.11		9.6 OK	
1.016	114	-0.165	0.000	0.16		11.4 OK	

Scott Hughes Design Ltd		Page 32
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coeffiecient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1
Number of Online Controls 4 Number of Time/Area Diagrams 0
Number of Offline Controls 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.281
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 18.800 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status ON
DVD Status ON
Inertia Status ON

Profile(s)
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, Summer and Winter
720, 960, 1440
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 0, 40

US/MH PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	R1	15 Winter	30	+0%					135.879
1.001	S01	15 Winter	30	+0%	100/15	Summer			135.466
2.000	R2	15 Winter	30	+0%					135.933
1.002	S02	15 Winter	30	+0%	100/15	Summer			135.329
3.000	R5	15 Winter	30	+0%					135.337
3.001	S03	15 Winter	30	+0%	100/15	Summer			135.215
4.000	R4	15 Winter	30	+0%					136.616
3.002	S04	15 Winter	30	+0%	100/15	Summer			135.179
3.003	S05	15 Winter	30	+0%					134.893
1.003	S06	15 Winter	30	+0%					134.552
5.000	R7	15 Winter	30	+0%					133.667
5.001	S07	15 Winter	30	+0%					133.531
6.000	R8	15 Winter	30	+0%					134.152
5.002	S08	15 Winter	30	+0%					132.873
1.004	S09	15 Winter	30	+0%	100/15	Winter			131.079
7.000	R9	15 Winter	30	+0%	100/60	Winter			132.467
7.001	S10	15 Winter	30	+0%	100/30	Summer			131.969
8.000	R10	15 Winter	30	+0%					132.921

Scott Hughes Design Ltd		Page 33
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

US/MH PN	Name	Surcharged Flooded			Pipe		
		Depth (m)	Volume (m³)	Flow / Overflow Cap.	Flow (l/s)	Status	Level Exceeded
1.000	R1	-0.071	0.000	0.18	2.0	OK	
1.001	S01	-0.046	0.000	0.55	3.2	OK	
2.000	R2	-0.080	0.000	0.09	1.1	OK	
1.002	S02	-0.045	0.000	0.58	10.3	OK	
3.000	R5	-0.063	0.000	0.30	1.7	OK	
3.001	S03	-0.061	0.000	0.32	1.7	OK	
4.000	R4	-0.084	0.000	0.06	1.1	OK	
3.002	S04	-0.040	0.000	0.65	4.9	OK	
3.003	S05	-0.052	0.000	0.45	4.8	OK	
1.003	S06	-0.093	0.000	0.30	15.1	OK	
5.000	R7	-0.058	0.000	0.36	2.3	OK	
5.001	S07	-0.069	0.000	0.20	2.6	OK	
6.000	R8	-0.076	0.000	0.14	2.0	OK	
5.002	S08	-0.051	0.000	0.47	6.3	OK	
1.004	S09	-0.596	0.000	0.03	28.8	OK	
7.000	R9	-0.067	0.000	0.24	2.6	OK	
7.001	S10	-0.053	0.000	0.44	2.5	OK	
8.000	R10	-0.076	0.000	0.13	1.4	OK	

Scott Hughes Design Ltd		Page 34
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

US/MH PN	US/MH Name	US/MH Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
8.001	S11	15 Winter	30	+0%	100/30	Winter		
7.002	S12	15 Winter	30	+0%	100/15	Winter		
9.000	R11	15 Winter	30	+0%	100/15	Winter	100/30	Winter
9.001	S13	15 Winter	30	+0%	100/15	Winter	100/30	Winter
9.002	S14	15 Winter	30	+0%	100/15	Summer	100/30	Winter
7.003	S15	15 Winter	30	+0%	100/15	Summer		
7.004	S16	15 Winter	30	+0%	100/15	Summer		
1.005	S17	60 Winter	30	+0%	100/15	Summer		
10.000	R12	15 Winter	30	+0%				
11.000	R13	15 Winter	30	+0%	100/15	Summer		
10.001	S18	15 Winter	30	+0%	100/15	Summer		
12.000	R14	15 Winter	30	+0%	30/15	Summer		
10.002	S19	15 Winter	30	+0%	30/15	Summer		
13.000	R15	15 Winter	30	+0%				
10.003	S20	15 Winter	30	+0%	2/15	Winter		
1.006	S21	60 Winter	30	+0%	30/60	Winter		
14.000	R16	15 Winter	30	+0%	100/15	Summer		
14.001	S22	15 Winter	30	+0%	100/15	Summer		
14.002	S23	15 Winter	30	+0%	100/15	Summer		
14.003	S24	15 Winter	30	+0%	100/15	Summer		
15.000	S25	15 Winter	30	+0%	100/60	Winter		
15.001	S26	15 Winter	30	+0%	100/30	Winter		
14.004	S28	15 Winter	30	+0%	100/30	Winter		
16.000	R17	15 Winter	30	+0%	100/30	Winter		
16.001	S29	15 Winter	30	+0%	100/30	Winter		
16.002	S30	15 Winter	30	+0%	100/15	Summer		
17.000	R18	15 Winter	30	+0%				
16.003	S31	15 Winter	30	+0%	100/30	Summer		
1.007	S32	60 Winter	30	+0%	2/15	Summer	100/60	Winter
1.008	48	240 Winter	30	+0%	100/60	Winter		
18.000	49	15 Winter	30	+0%	100/15	Summer		
18.001	S33	15 Winter	30	+0%	100/15	Summer		
19.000	50	15 Winter	30	+0%	100/15	Summer		
18.002	S34	15 Winter	30	+0%	30/15	Summer		
18.003	S35	15 Winter	30	+0%	30/15	Summer		
20.000	R21	15 Winter	30	+0%				
20.001	S36	15 Winter	30	+0%				
20.002	S37	15 Winter	30	+0%				
18.004	S38	15 Winter	30	+0%				
18.005	57	15 Winter	30	+0%				
21.000	R22	15 Winter	30	+0%				
21.001	S39	15 Winter	30	+0%				
21.002	S40	15 Winter	30	+0%				
22.000	R23	15 Winter	30	+0%				
22.001	S41	15 Winter	30	+0%	100/15	Summer		
22.002	63	15 Winter	30	+0%	100/15	Summer		
23.000	R25	15 Winter	30	+0%				
21.003	S42	15 Winter	30	+0%	100/15	Summer		

Scott Hughes Design Ltd								Page 35
The Flint Glass Works 64 Jersey Street Manchester M4 6JW								
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX								
Micro Drainage Network 2017.1.1								



30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH	Water Surcharged Flooded			Pipe			Status	Level Exceeded
		Name	Level (m)	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)		
8.001	S11	132.386	-0.065	0.000	0.26		2.9	OK	
7.002	S12	131.847	-0.053	0.000	0.44		6.3	OK	
9.000	R11	131.712	-0.072	0.000	0.17		1.1	OK	5
9.001	S13	131.560	-0.056	0.000	0.40		2.3	OK	5
9.002	S14	131.349	-0.079	0.000	0.44		5.9	OK	5
7.003	S15	131.288	-0.045	0.000	0.81		12.1	OK	
7.004	S16	131.215	-0.054	0.000	0.73		12.2	OK	
1.005	S17	130.918	-0.250	0.000	0.02		27.4	OK	
10.000	R12	133.843	-0.057	0.000	0.38		3.1	OK	
11.000	R13	133.327	-0.079	0.000	0.10		0.6	OK	
10.001	S18	133.238	-0.059	0.000	0.34		3.6	OK	
12.000	R14	133.064	0.262	0.000	0.43		2.4	FLOOD RISK	
10.002	S19	133.046	0.351	0.000	1.44		8.2	SURCHARGED	
13.000	R15	133.478	-0.078	0.000	0.11		1.4	OK	
10.003	S20	132.787	0.217	0.000	1.90		11.4	SURCHARGED	
1.006	S21	130.915	0.015	0.000	0.02		17.0	SURCHARGED	
14.000	R16	133.031	-0.069	0.000	0.20		1.1	OK	
14.001	S22	132.909	-0.063	0.000	0.30		2.3	OK	
14.002	S23	132.775	-0.017	0.000	0.96		5.6	OK	
14.003	S24	132.630	-0.001	0.000	1.00		8.4	OK	
15.000	S25	132.590	-0.070	0.000	0.19		1.1	OK	
15.001	S26	132.469	-0.063	0.000	0.29		2.3	OK	
14.004	S28	132.214	-0.046	0.000	0.57		10.7	OK	
16.000	R17	132.538	-0.062	0.000	0.30		2.2	OK	
16.001	S29	132.197	-0.054	0.000	0.42		3.1	OK	
16.002	S30	131.970	-0.043	0.000	0.60		4.0	OK	
17.000	R18	132.706	-0.057	0.000	0.38		4.5	OK	
16.003	S31	131.891	-0.058	0.000	0.35		8.5	OK	
1.007	S32	130.913	0.692	0.000	0.37		20.7	SURCHARGED	1
1.008	48	127.069	-0.559	0.000	0.01		16.0	OK	
18.000	49	129.413	-0.070	0.000	0.20		1.1	OK	
18.001	S33	129.296	-0.067	0.000	0.23		2.0	OK	
19.000	50	129.486	-0.078	0.000	0.11		1.1	OK	
18.002	S34	129.276	0.149	0.000	0.83		4.7	SURCHARGED	
18.003	S35	129.207	0.193	0.000	1.36		8.2	SURCHARGED	
20.000	R21	130.033	-0.067	0.000	0.24		1.1	OK	
20.001	S36	129.942	-0.054	0.000	0.42		2.6	OK	
20.002	S37	129.733	-0.071	0.000	0.18		3.5	OK	
18.004	S38	128.723	-0.077	0.000	0.47		12.1	OK	
18.005	57	128.476	-0.085	0.000	0.39		12.1	OK	
21.000	R22	131.526	-0.074	0.000	0.16		0.9	OK	
21.001	S39	131.471	-0.061	0.000	0.32		2.4	OK	
21.002	S40	131.286	-0.050	0.000	0.50		6.6	OK	
22.000	R23	131.303	-0.070	0.000	0.19		2.8	OK	
22.001	S41	130.041	-0.046	0.000	0.56		2.8	OK	
22.002	63	130.027	-0.024	0.000	0.90		5.2	OK	
23.000	R25	130.147	-0.119	0.000	0.10		2.3	OK	

Scott Hughes Design Ltd The Flint Glass Works 64 Jersey Street Manchester M4 6JW		Page 36
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX		Designed by AB Checked by PG
Micro Drainage		
Network 2017.1.1		

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Water Surcharged Flooded			Pipe			Level Exceeded
		Level (m)	Depth (m)	Volume (m³)	Flow / Overflow Cap.	Flow (l/s)	Status	
21.003	S42	129.911	-0.012	0.000	1.00		14.8	OK

Scott Hughes Design Ltd		Page 37
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

US/MH PN	Storm Name	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
24.000	H01	15 Winter	30	+0%	100/120 Summer		
24.001	H02	15 Winter	30	+0%	100/120 Summer		
1.009	S43	240 Winter	30	+0%	100/60 Winter		
1.010	S44	240 Winter	30	+0%	100/60 Winter		
25.000	R26	15 Winter	30	+0%			
25.001	S45	15 Winter	30	+0%	100/15 Summer		
26.000	R27	15 Winter	30	+0%			
27.000	R28	15 Winter	30	+0%			
25.002	S46	15 Winter	30	+0%			
1.011	S47	240 Winter	30	+0%	100/60 Summer		
28.000	R29	15 Winter	30	+0%			
29.000	R30	15 Winter	30	+0%			
28.001	S49	15 Winter	30	+0%			
28.002	S50	15 Winter	30	+0%	100/120 Winter		
30.000	R31	15 Winter	30	+0%			
28.003	S51	15 Winter	30	+0%	100/120 Winter		
31.000	S52	15 Winter	30	+0%			
31.001	S53	15 Winter	30	+0%	100/15 Summer		
31.002	S54	15 Winter	30	+0%			
32.000	RE37	30 Winter	30	+0%	30/15 Summer		
32.001	S55	30 Winter	30	+0%	30/15 Summer		
31.003	S56	30 Winter	30	+0%	2/30 Winter		
33.000	S57A	30 Winter	30	+0%	30/15 Winter		
31.004	S57	30 Winter	30	+0%	2/15 Summer		
34.000	Tank	60 Winter	30	+0%	100/15 Winter		
31.005	S58	30 Winter	30	+0%	2/15 Summer		
35.000	RE39	15 Winter	30	+0%	100/15 Summer		
35.001	S59	30 Winter	30	+0%	30/15 Winter		
31.006	S60	30 Winter	30	+0%	2/15 Summer		0
31.007	S60A	720 Winter	30	+0%	2/15 Summer	100/120 Winter	
36.000	RE40	15 Winter	30	+0%	100/120 Winter		
36.001	S62	15 Winter	30	+0%	100/120 Winter		
31.008	S63	240 Winter	30	+0%	100/60 Summer		
1.012	S64	240 Winter	30	+0%	2/15 Summer		
1.013	99	240 Winter	30	+0%	2/15 Summer		
37.000	R32	15 Winter	30	+0%	100/15 Summer		
37.001	S53	15 Winter	30	+0%	30/15 Summer		
38.000	R33	15 Winter	30	+0%			
37.002	S54	15 Winter	30	+0%	100/15 Summer		
39.000	R34	15 Winter	30	+0%			
39.001	S55	15 Winter	30	+0%	100/15 Winter		
37.003	S56	15 Winter	30	+0%	100/15 Summer		
40.000	R35	15 Winter	30	+0%			
40.001	S57	15 Winter	30	+0%			
37.004	S58	15 Winter	30	+0%	30/15 Summer		
37.005	110	15 Winter	30	+0%	30/15 Summer		
41.000	R36	15 Winter	30	+0%	100/15 Summer		
37.006	S59	15 Winter	30	+0%	30/15 Summer		

Scott Hughes Design Ltd		Page 38
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Pipe			Status	Level Exceeded
					Flow / Cap.	Overflow (l/s)	Flow (l/s)		
24.000	H01	127.712	-0.146	0.000	0.26		8.8	OK	
24.001	H02	127.640	-0.158	0.000	0.19		8.7	OK	
1.009	S43	127.069	-0.509	0.000	0.01		20.4	OK	
1.010	S44	127.068	-0.423	0.000	0.01		15.8	OK	
25.000	R26	129.731	-0.085	0.000	0.06		0.9	OK	
25.001	S45	129.160	-0.040	0.000	0.67		3.9	OK	
26.000	R27	129.787	-0.084	0.000	0.06		0.9	OK	
27.000	R28	129.123	-0.077	0.000	0.12		0.9	OK	
25.002	S46	129.025	-0.069	0.000	0.21		5.6	OK	
1.011	S47	127.068	-0.341	0.000	0.00		14.3	OK	
28.000	R29	129.144	-0.086	0.000	0.05		0.6	OK	
29.000	R30	128.884	-0.080	0.000	0.09		0.9	OK	
28.001	S49	128.639	-0.061	0.000	0.33		2.9	OK	
28.002	S50	128.355	-0.050	0.000	0.49		3.5	OK	
30.000	R31	128.747	-0.085	0.000	0.05		0.9	OK	
28.003	S51	128.186	-0.092	0.000	0.31		4.3	OK	
31.000	S52	127.992	-0.081	0.000	0.08		1.1	OK	
31.001	S53	127.639	-0.028	0.000	0.87		5.1	OK	
31.002	S54	127.339	-0.116	0.000	0.11		5.0	OK	
32.000	RE37	127.209	0.126	0.000	0.19		1.1	SURCHARGED	
32.001	S55	127.200	0.237	0.000	0.18		2.5	SURCHARGED	
31.003	S56	127.189	0.352	0.000	0.44		5.9	SURCHARGED	
33.000	S57A	127.176	0.017	0.000	0.13		1.6	SURCHARGED	
31.004	S57	127.165	0.429	0.000	0.38		12.1	SURCHARGED	
34.000	Tank	127.029	-0.086	0.000	0.07		2.5	OK	
31.005	S58	127.143	0.485	0.000	0.14		4.7	SURCHARGED	
35.000	RE39	127.326	-0.052	0.000	0.45		2.8	OK	
35.001	S59	127.154	0.023	0.000	0.12		2.2	SURCHARGED	
31.006	S60	127.142	0.702	0.000	1.05	0.0	3.0	SURCHARGED	
31.007	S60A	127.340	0.136	0.000	0.38		2.9	SURCHARGED	7
36.000	RE40	128.258	-0.068	0.000	0.22		1.1	OK	
36.001	S62	128.156	-0.087	0.000	0.04		1.1	OK	
31.008	S63	127.068	-0.272	0.000	0.00		3.4	OK	
1.012	S64	127.067	1.342	0.000	0.34		11.6	SURCHARGED	
1.013	99	126.986	1.327	0.000	0.28		10.7	SURCHARGED	
37.000	R32	130.190	-0.064	0.000	0.27		3.1	OK	
37.001	S53	129.590	0.088	0.000	1.23	0.0	7.1	SURCHARGED	
38.000	R33	130.133	-0.067	0.000	0.23		2.5	OK	
37.002	S54	129.304	-0.037	0.000	0.71		10.4	OK	
39.000	R34	129.123	-0.052	0.000	0.46		2.8	OK	
39.001	S55	129.019	-0.054	0.000	0.43		4.6	OK	
37.003	S56	128.329	-0.071	0.000	0.53		16.0	OK	
40.000	R35	129.307	-0.085	0.000	0.05		0.6	OK	
40.001	S57	128.967	-0.077	0.000	0.12		1.8	OK	
37.004	S58	127.984	0.118	0.000	1.20	0.0	18.4	SURCHARGED	
37.005	110	127.825	0.076	0.000	1.05	0.0	18.1	SURCHARGED	
41.000	R36	128.468	-0.032	0.000	0.78		7.0	OK	

Scott Hughes Design Ltd The Flint Glass Works 64 Jersey Street Manchester M4 6JW		Church Raike Chipping	Page 39
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX		Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1			

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Water Surcharged Flooded			Pipe			Level Exceeded
		Level (m)	Depth (m)	Volume (m³)	Flow / Overflow Cap.	Flow (l/s)	Status	
37.006	S59	127.700	0.063	0.000	1.33		24.6 SURCHARGED	

Scott Hughes Design Ltd		Page 40
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Storm	Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Water Level
			Period	Change	Surcharge	Flood	Overflow	Act.	(m)
1.014	112	240 Winter	30	+0%	2/15 Summer				126.961
1.015	113	240 Winter	30	+0%					124.813
1.016	114	15 Summer	30	+0%					124.229

PN	US/MH Name	Surcharged Flooded		Pipe			Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow / Overflow Cap.	Flow (l/s)			
1.014	112	1.502	0.000	0.15		10.7	SURCHARGED	
1.015	113	-0.172	0.000	0.13		10.7		OK
1.016	114	-0.158	0.000	0.19		13.7		OK

Scott Hughes Design Ltd		Page 41
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

100 year Return Period Summary of Critical Results by Maximum Level (Rank
1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coeffiecient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 1
 Number of Online Controls 4 Number of Time/Area Diagrams 0
 Number of Offline Controls 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.281
 Region England and Wales Cv (Summer) 0.750
 M5-60 (mm) 18.800 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status ON
 DVD Status ON
 Inertia Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
 720, 960, 1440
 Return Period(s) (years) 2, 30, 100
 Climate Change (%) 0, 0, 40

US/MH PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	R1	15 Winter	100	+40%					135.890
1.001	S01	15 Winter	100	+40%	100/15	Summer			135.531
2.000	R2	15 Winter	100	+40%					135.939
1.002	S02	15 Winter	100	+40%	100/15	Summer			135.399
3.000	R5	15 Winter	100	+40%					135.353
3.001	S03	15 Winter	100	+40%	100/15	Summer			135.305
4.000	R4	15 Winter	100	+40%					136.622
3.002	S04	15 Winter	100	+40%	100/15	Summer			135.288
3.003	S05	15 Winter	100	+40%					134.912
1.003	S06	15 Winter	100	+40%					134.573
5.000	R7	15 Winter	100	+40%					133.684
5.001	S07	15 Winter	100	+40%					133.542
6.000	R8	15 Winter	100	+40%					134.162
5.002	S08	15 Winter	100	+40%					132.896
1.004	S09	60 Winter	100	+40%	100/15	Winter			132.636
7.000	R9	60 Winter	100	+40%	100/60	Winter			132.554
7.001	S10	60 Winter	100	+40%	100/30	Summer			132.529
8.000	R10	15 Winter	100	+40%					132.929

Scott Hughes Design Ltd		Page 42
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

100 year Return Period Summary of Critical Results by Maximum Level (Rank
1) for Storm

US/MH PN	Name	Surcharged Flooded			Pipe			Level Exceeded
		Depth (m)	Volume (m³)	Flow / Overflow Cap. (l/s)	Flow (l/s)	Status		
1.000	R1	-0.060	0.000	0.33	3.6	OK		
1.001	S01	0.019	0.000	0.98	5.6	SURCHARGED		
2.000	R2	-0.074	0.000	0.16	2.1	OK		
1.002	S02	0.025	0.000	1.01	18.0	SURCHARGED		
3.000	R5	-0.047	0.000	0.53	3.0	OK		
3.001	S03	0.029	0.000	0.62	3.3	SURCHARGED		
4.000	R4	-0.078	0.000	0.11	2.1	OK		
3.002	S04	0.069	0.000	1.11	8.4	SURCHARGED		
3.003	S05	-0.033	0.000	0.78	8.4	OK		
1.003	S06	-0.072	0.000	0.53	26.3	OK		
5.000	R7	-0.041	0.000	0.65	4.1	OK		
5.001	S07	-0.058	0.000	0.36	4.6	OK		
6.000	R8	-0.066	0.000	0.24	3.6	OK		
5.002	S08	-0.028	0.000	0.85	11.4	OK		
1.004	S09	0.961	0.000	0.03	28.0	SURCHARGED		
7.000	R9	0.020	0.000	0.26	2.7	SURCHARGED		
7.001	S10	0.507	0.000	0.48	2.7	SURCHARGED		
8.000	R10	-0.068	0.000	0.23	2.6	OK		

Scott Hughes Design Ltd		Page 43
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

100 year Return Period Summary of Critical Results by Maximum Level (Rank
1) for Storm

US/MH PN	Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
8.001	S11	60 Winter	100	+40%	100/30 Winter			
7.002	S12	60 Winter	100	+40%	100/15 Winter			
9.000	R11	120 Winter	100	+40%	100/15 Winter	100/30 Winter		
9.001	S13	60 Winter	100	+40%	100/15 Winter	100/30 Winter		
9.002	S14	60 Winter	100	+40%	100/15 Summer	100/30 Winter		
7.003	S15	60 Winter	100	+40%	100/15 Summer			
7.004	S16	60 Winter	100	+40%	100/15 Summer			
1.005	S17	60 Winter	100	+40%	100/15 Summer			
10.000	R12	15 Winter	100	+40%				
11.000	R13	15 Winter	100	+40%	100/15 Summer			
10.001	S18	15 Winter	100	+40%	100/15 Summer			
12.000	R14	15 Winter	100	+40%	30/15 Summer			
10.002	S19	15 Winter	100	+40%	30/15 Summer			
13.000	R15	15 Winter	100	+40%				
10.003	S20	15 Winter	100	+40%	2/15 Winter			
1.006	S21	60 Winter	100	+40%	30/60 Winter			
14.000	R16	15 Winter	100	+40%	100/15 Summer			
14.001	S22	15 Winter	100	+40%	100/15 Summer			
14.002	S23	15 Winter	100	+40%	100/15 Summer			
14.003	S24	15 Winter	100	+40%	100/15 Summer			
15.000	S25	60 Winter	100	+40%	100/60 Winter			
15.001	S26	60 Winter	100	+40%	100/30 Winter			
14.004	S28	60 Winter	100	+40%	100/30 Winter			
16.000	R17	60 Winter	100	+40%	100/30 Winter			
16.001	S29	60 Winter	100	+40%	100/30 Winter			
16.002	S30	60 Winter	100	+40%	100/15 Summer			
17.000	R18	60 Winter	100	+40%				
16.003	S31	60 Winter	100	+40%	100/30 Summer			
1.007	S32	60 Winter	100	+40%	2/15 Summer	100/60 Winter		
1.008	48	240 Winter	100	+40%	100/60 Winter			
18.000	49	15 Winter	100	+40%	100/15 Summer			
18.001	S33	15 Winter	100	+40%	100/15 Summer			
19.000	50	15 Winter	100	+40%	100/15 Summer			
18.002	S34	15 Winter	100	+40%	30/15 Summer			
18.003	S35	15 Winter	100	+40%	30/15 Summer			
20.000	R21	15 Winter	100	+40%				
20.001	S36	15 Winter	100	+40%				
20.002	S37	15 Winter	100	+40%				
18.004	S38	15 Winter	100	+40%				
18.005	57	15 Winter	100	+40%				
21.000	R22	15 Winter	100	+40%				
21.001	S39	15 Winter	100	+40%				
21.002	S40	15 Winter	100	+40%				
22.000	R23	15 Winter	100	+40%				
22.001	S41	15 Winter	100	+40%	100/15 Summer			
22.002	63	15 Winter	100	+40%	100/15 Summer			
23.000	R25	15 Winter	100	+40%				
21.003	S42	15 Winter	100	+40%	100/15 Summer			

Scott Hughes Design Ltd		Page 44
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Water Level (m)	Surcharged Flooded			Pipe			Status	Level Exceeded
			Depth (m)	Volume (m³)	Flow / Overflow Cap. (l/s)	Flow (l/s)	Flow (l/s)			
8.001	S11	132.537	0.086	0.000	0.27		3.0	SURCHARGED		
7.002	S12	132.516	0.616	0.000	0.47		6.7	FLOOD RISK		
9.000	R11	132.284	0.500	0.191	0.30		2.1	FLOOD	5	
9.001	S13	132.286	0.670	6.782	1.97		11.4	FLOOD	5	
9.002	S14	132.395	0.967	6.352	0.90		11.9	FLOOD	5	
7.003	S15	132.499	1.166	0.000	0.86		12.9	FLOOD RISK		
7.004	S16	132.560	1.291	0.000	0.78		13.0	SURCHARGED		
1.005	S17	132.633	1.465	0.000	0.03		38.2	SURCHARGED		
10.000	R12	133.862	-0.038	0.000	0.68		5.5	OK		
11.000	R13	133.595	0.189	0.000	0.18		1.0	SURCHARGED		
10.001	S18	133.587	0.290	0.000	0.61		6.5	SURCHARGED		
12.000	R14	133.324	0.522	0.000	1.37		7.7	FLOOD RISK		
10.002	S19	133.381	0.686	0.000	1.81		10.3	FLOOD RISK		
13.000	R15	133.487	-0.069	0.000	0.20		2.6	OK		
10.003	S20	133.074	0.504	0.000	2.67		16.0	SURCHARGED		
1.006	S21	132.631	1.731	0.000	0.04		28.8	SURCHARGED		
14.000	R16	133.410	0.310	0.000	0.39		2.2	FLOOD RISK		
14.001	S22	133.395	0.423	0.000	0.53		4.1	SURCHARGED		
14.002	S23	133.362	0.570	0.000	1.37		8.0	SURCHARGED		
14.003	S24	133.057	0.426	0.000	1.45		12.2	SURCHARGED		
15.000	S25	132.737	0.077	0.000	0.20		1.2	SURCHARGED		
15.001	S26	132.731	0.199	0.000	0.30		2.4	SURCHARGED		
14.004	S28	132.717	0.457	0.000	0.59		11.1	FLOOD RISK		
16.000	R17	132.735	0.135	0.000	0.32		2.4	SURCHARGED		
16.001	S29	132.718	0.467	0.000	0.45		3.4	FLOOD RISK		
16.002	S30	132.698	0.685	0.000	0.64		4.3	FLOOD RISK		
17.000	R18	132.740	-0.023	0.000	0.41		4.9	OK		
16.003	S31	132.688	0.739	0.000	0.38		9.1	FLOOD RISK		
1.007	S32	132.629	2.408	2.079	0.62		34.7	FLOOD	1	
1.008	48	128.467	0.839	0.000	0.01		29.7	SURCHARGED		
18.000	49	129.727	0.244	0.000	0.44		2.5	SURCHARGED		
18.001	S33	129.713	0.350	0.000	0.46		3.9	SURCHARGED		
19.000	50	129.704	0.140	0.000	0.24		2.6	SURCHARGED		
18.002	S34	129.698	0.571	0.000	1.28		7.2	FLOOD RISK		
18.003	S35	129.601	0.587	0.000	1.90		11.4	SURCHARGED		
20.000	R21	130.046	-0.054	0.000	0.43		2.0	OK		
20.001	S36	129.963	-0.033	0.000	0.76		4.7	OK		
20.002	S37	129.743	-0.061	0.000	0.32		6.3	OK		
18.004	S38	128.746	-0.054	0.000	0.72		18.5	OK		
18.005	57	128.495	-0.066	0.000	0.60		18.6	OK		
21.000	R22	131.536	-0.064	0.000	0.28		1.5	OK		
21.001	S39	131.487	-0.045	0.000	0.58		4.3	OK		
21.002	S40	131.311	-0.025	0.000	0.91		11.9	OK		
22.000	R23	131.314	-0.059	0.000	0.35		5.1	OK		
22.001	S41	130.342	0.255	0.000	0.96		4.9	SURCHARGED		
22.002	63	130.308	0.257	0.000	1.49		8.5	SURCHARGED		
23.000	R25	130.158	-0.108	0.000	0.17		4.1	OK		

Scott Hughes Design Ltd The Flint Glass Works 64 Jersey Street Manchester M4 6JW		Church Raike Chipping	Page 45
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX		Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1			

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Water Surcharged Flooded			Pipe			Level Exceeded
		Level (m)	Depth (m)	Volume (m ³)	Flow / Overflow Cap.	Flow (l/s)	Status	
21.003	S42	130.038	0.115	0.000	1.73		25.5 SURCHARGED	

Scott Hughes Design Ltd		Page 46
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

100 year Return Period Summary of Critical Results by Maximum Level (Rank
1) for Storm

US/MH PN	Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.
24.000	H01	240 Winter	100	+40%	100/120 Summer			
24.001	H02	240 Winter	100	+40%	100/120 Summer			
1.009	S43	240 Winter	100	+40%	100/60 Winter			
1.010	S44	240 Winter	100	+40%	100/60 Winter			
25.000	R26	15 Winter	100	+40%				
25.001	S45	15 Winter	100	+40%	100/15 Summer			
26.000	R27	15 Winter	100	+40%				
27.000	R28	15 Winter	100	+40%				
25.002	S46	15 Winter	100	+40%				
1.011	S47	240 Winter	100	+40%	100/60 Summer			
28.000	R29	15 Winter	100	+40%				
29.000	R30	15 Winter	100	+40%				
28.001	S49	15 Winter	100	+40%				
28.002	S50	240 Winter	100	+40%	100/120 Winter			
30.000	R31	15 Winter	100	+40%				
28.003	S51	240 Winter	100	+40%	100/120 Winter			
31.000	S52	15 Winter	100	+40%				
31.001	S53	15 Winter	100	+40%	100/15 Summer			
31.002	S54	15 Winter	100	+40%				
32.000	RE37	15 Winter	100	+40%	30/15 Summer			
32.001	S55	15 Winter	100	+40%	30/15 Summer			
31.003	S56	120 Winter	100	+40%	2/30 Winter			
33.000	S57A	120 Winter	100	+40%	30/15 Winter			
31.004	S57	120 Winter	100	+40%	2/15 Summer			
34.000	Tank	120 Winter	100	+40%	100/15 Winter			
31.005	S58	120 Winter	100	+40%	2/15 Summer			
35.000	RE39	120 Winter	100	+40%	100/15 Summer			
35.001	S59	120 Winter	100	+40%	30/15 Winter			
31.006	S60	120 Winter	100	+40%	2/15 Summer			0
31.007	S60A	240 Winter	100	+40%	2/15 Summer	100/120 Winter		
36.000	RE40	240 Winter	100	+40%	100/120 Winter			
36.001	S62	240 Winter	100	+40%	100/120 Winter			
31.008	S63	240 Winter	100	+40%	100/60 Summer			
1.012	S64	240 Winter	100	+40%	2/15 Summer			
1.013	99	360 Winter	100	+40%	2/15 Summer			
37.000	R32	15 Winter	100	+40%	100/15 Summer			
37.001	S53	15 Winter	100	+40%	30/15 Summer			
38.000	R33	15 Winter	100	+40%				
37.002	S54	15 Winter	100	+40%	100/15 Summer			
39.000	R34	15 Winter	100	+40%				
39.001	S55	15 Winter	100	+40%	100/15 Winter			
37.003	S56	15 Winter	100	+40%	100/15 Summer			
40.000	R35	15 Winter	100	+40%				
40.001	S57	15 Winter	100	+40%				
37.004	S58	15 Winter	100	+40%	30/15 Summer			
37.005	110	15 Winter	100	+40%	30/15 Summer			
41.000	R36	15 Winter	100	+40%	100/15 Summer			
37.006	S59	360 Winter	100	+40%	30/15 Summer			

Scott Hughes Design Ltd								Page 47
The Flint Glass Works 64 Jersey Street Manchester M4 6JW								
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX								
Micro Drainage								
Network 2017.1.1								

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH	Water Surcharged Flooded			Pipe				Status	Level Exceeded
		Name	Level (m)	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Flow (l/s)		
24.000	H01	128.471		0.613	0.000	0.12		3.9	SURCHARGED	
24.001	H02	128.469		0.671	0.000	0.08		3.9	SURCHARGED	
1.009	S43	128.467		0.889	0.000	0.01		40.9	SURCHARGED	
1.010	S44	128.466		0.975	0.000	0.01		29.7	SURCHARGED	
25.000	R26	129.737		-0.079	0.000	0.10		1.5	OK	
25.001	S45	129.248		0.048	0.000	1.21		7.0	SURCHARGED	
26.000	R27	129.793		-0.078	0.000	0.11		1.5	OK	
27.000	R28	129.131		-0.069	0.000	0.21		1.5	OK	
25.002	S46	129.036		-0.058	0.000	0.37		10.0	OK	
1.011	S47	128.465		1.056	0.000	0.01		30.3	SURCHARGED	
28.000	R29	129.150		-0.080	0.000	0.09		1.0	OK	
29.000	R30	128.891		-0.073	0.000	0.16		1.5	OK	
28.001	S49	128.656		-0.044	0.000	0.59		5.3	OK	
28.002	S50	128.470		0.065	0.000	0.21		1.5	SURCHARGED	
30.000	R31	128.753		-0.079	0.000	0.09		1.5	OK	
28.003	S51	128.467		0.189	0.000	0.13		1.9	SURCHARGED	
31.000	S52	127.999		-0.074	0.000	0.15		2.1	OK	
31.001	S53	127.940		0.273	0.000	1.49		8.7	SURCHARGED	
31.002	S54	127.440		-0.015	0.000	0.20		8.6	OK	
32.000	RE37	127.467		0.384	0.000	0.42		2.4	SURCHARGED	
32.001	S55	127.445		0.482	0.000	0.42		5.7	FLOOD RISK	
31.003	S56	127.438		0.601	0.000	0.46		6.2	FLOOD RISK	
33.000	S57A	127.436		0.277	0.000	0.11		1.4	FLOOD RISK	
31.004	S57	127.434		0.698	0.000	0.40		12.9	SURCHARGED	
34.000	Tank	127.430		0.315	0.000	0.08		2.7	SURCHARGED	
31.005	S58	127.430		0.772	0.000	0.10		3.4	SURCHARGED	
35.000	RE39	127.431		0.053	0.000	0.32		2.0	SURCHARGED	
35.001	S59	127.427		0.296	0.000	0.11		2.0	SURCHARGED	
31.006	S60	127.425		0.985	0.000	1.05	0.0	3.0	SURCHARGED	
31.007	S60A	128.421		1.217	17.337	2.40		18.0	FLOOD	7
36.000	RE40	128.466		0.140	0.000	0.10		0.5	SURCHARGED	
36.001	S62	128.465		0.222	0.000	0.02		0.5	SURCHARGED	
31.008	S63	128.465		1.125	0.000	0.01		18.6	SURCHARGED	
1.012	S64	128.465		2.740	0.000	0.70		23.8	SURCHARGED	
1.013	99	128.082		2.423	0.000	0.62		23.4	SURCHARGED	
37.000	R32	130.400		0.146	0.000	0.45		5.2	SURCHARGED	
37.001	S53	130.299		0.797	0.000	1.85		10.7	FLOOD RISK	
38.000	R33	130.146		-0.054	0.000	0.42		4.6	OK	
37.002	S54	129.840		0.499	0.000	1.01		14.9	FLOOD RISK	
39.000	R34	129.149		-0.026	0.000	0.83		5.1	OK	
39.001	S55	129.097		0.024	0.000	0.76		8.2	SURCHARGED	
37.003	S56	128.868		0.468	0.000	0.77		23.4	FLOOD RISK	
40.000	R35	129.313		-0.079	0.000	0.10		1.0	OK	
40.001	S57	128.976		-0.068	0.000	0.22		3.2	OK	
37.004	S58	128.551		0.685	0.000	1.78		27.4	FLOOD RISK	
37.005	110	128.182		0.433	0.000	1.57		27.0	SURCHARGED	
41.000	R36	129.097		0.597	0.000	1.17		10.4	FLOOD RISK	

Scott Hughes Design Ltd The Flint Glass Works 64 Jersey Street Manchester M4 6JW		Church Raike Chipping	Page 48
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX		Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1			

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Water Surcharged Flooded			Pipe			Level Exceeded
		Level (m)	Depth (m)	Volume (m ³)	Flow / Overflow Cap.	Flow (l/s)	Status	
37.006	S59 128.014	0.377	0.000	0.47		8.6 SURCHARGED		

Scott Hughes Design Ltd		Page 49
The Flint Glass Works 64 Jersey Street Manchester M4 6JW	Church Raike Chipping	
Date 07/06/2018 09:55 File Church Raike 06.06.18.MDX	Designed by AB Checked by PG	
Micro Drainage Network 2017.1.1		

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Water Level
								(m)
1.014	112	360 Winter	100	+40%	2/15 Summer			128.009
1.015	113	360 Winter	100	+40%				124.847
1.016	114	360 Winter	100	+40%				124.258

PN	US/MH Name	Surcharged Flooded		Pipe			Level Exceeded
		Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Flow (l/s)	
1.014	112	2.550	0.000	0.38		26.7	SURCHARGED
1.015	113	-0.138	0.000	0.32		26.7	OK
1.016	114	-0.129	0.000	0.38		27.3	OK

Ann Bacon

From: Dodd, Matthew <Matthew.Dodd@uuplc.co.uk>
Sent: 29 November 2016 10:16
To: Chris Finneran
Cc: Wastewater Developer Services
Subject: Pre Development Enquiry for Church Rake, Chipping - Our ref - DE2891

Importance: High

Chris

We have carried out an assessment of your application which is based on the information provided; this pre development advice will be valid for 12 months

Foul

Foul will be allowed to drain to the public combined sewer network at an unrestricted rate.

Surface Water

Surface water from this site should drain to either soak away or directly to watercourse. Discharge rates and consents must be discussed and agreed with all interested parties.

Connection Application

Although we may discuss and agree discharge points & rates in principle, please be aware that you will have to apply for a formal sewer connection. This is so that we can assess the method of construction, Health & Safety requirements and to ultimately inspect the connection when it is made. Details of the application process and the form itself can be obtained from our website by following the link below

<http://www.unitedutilities.com/connecting-public-sewer.aspx>

Sewer Adoption Agreement

You may wish to offer the proposed new sewers for adoption. United Utilities assess adoption application based on Sewers adoption 6th Edition and for any pumping stations our company addenda document. Please refer to link below to obtain further guidance and application pack:

<http://www.unitedutilities.com/sewer-adoption.aspx>

Please be aware that on site drainage must be designed in accordance with Building Regulations, National Planning Policy, and local flood authority guidelines, we would recommend that you speak and make suitable agreements with the relevant statutory bodies.

Please note, if you intend to put forward your wastewater assets for adoption by United Utilities, the proposed detail design will be subject to a technical appraisal by an Adoption Engineer as we need to be sure that the proposals meets the requirements of Sewers for adoption and United Utilities Asset Standards. The proposed design should give consideration to long term operability and give United Utilities a cost effective proposal for the life of the assets. Therefore, further to this enquiry should you wish to progress a Section 104 agreement, we strongly recommend that no construction commences until the detailed drainage design, submitted as part of the Section 104 agreement, has been assessed and accepted in writing by United Utilities. Any works carried out prior to the technical assessment being approved is done entirely at the developers own risk and could be subject to change.

Regards

Matthew Dodd
Assistant Developer Engineer
Developer Services and Planning
Operational Services
United Utilities
T: 01925 679369 (internal 79369)
unitedutilities.com

**If you have received a great service today why not tell us?
Visit: unitedutilities.com/wow**

From: Chris Finneran [<mailto:cfinneran@scotthughesdesign.co.uk>]
Sent: 15 November 2016 09:53
To: Wastewater Developer Services <WastewaterDeveloperServices@uuplc.co.uk>
Cc: Paul Graveney <pgraveney@scotthughesdesign.co.uk>
Subject: Pre-development Enquiry - Church Rake, Chipping

Good Morning,

Please find attached a predevelopment enquiry for a scheme in Chipping.

Kind Regards

Chris Finneran
BEng (Hons) MICE
Graduate Civil Engineer



www.scotthughesdesign.co.uk

t 0161 605 0831

Manchester & Leeds

Structural Engineering – Civil Engineering

BREEAM - CSH - Ecohomes - LEED – CEEQUAL

This e-mail is confidential to the addressee only. Please notify the Company immediately should you not be the intended recipient, and delete the message from your computer and/or network. Do not disclose its contents to others. Scott Hughes Design accepts no responsibility or liability for post-dispatch changes or infection by computer viruses, which may result from this document transmittal..
Registered address: The Flint Glass Works, 64 Jersey St Manchester M4 6JW

EMGateway3.uuplc.co.uk made the following annotations

The information contained in this e-mail is intended only for the individual to whom it is addressed. It may contain legally privileged or confidential information or otherwise be exempt from disclosure. If you have received this Message in error or there are any problems, please notify the sender

immediately and delete the message from your computer. You must not use, disclose, copy or alter this message for any unauthorised purpose. Neither United Utilities Group PLC nor any of its subsidiaries will be liable for any direct, special, indirect or consequential damages as a result of any virus being passed on, or arising from the alteration of the contents of this message by a third party.

United Utilities Group PLC, Haweswater House, Lingley Mere Business Park, Lingley Green Avenue, Great Sankey, Warrington, WA5 3LP
Registered in England and Wales. Registered No 6559020

www.unitedutilities.com
www.unitedutilities.com/subsidiaries

Appendix C – United Utilities Correspondence