



Technical Data

end clamp AK II click 30-50

Material - Characteristics

description: end clamp AK II click 30-50
 art.-no.: 30-400-006

Product Data

material identification: EN AW-6063 T6
 (EN AW-AMg0,7Si)

mechanical values:

$F_{rd \text{ suction}}$ = 2030 N
 $F_{rd \text{ thrust lateral}}$ = 150 N
 $F_{rd \text{ thrust parallel}}$ = 600 N

general values:

length = 36,00 mm
 wide = 35,00 mm
 height = 66,60 mm
 weight = 0,055 kg

notice:

height of module frame: 30 - 50 mm
 tightening torque: 8-10 Nm (M8x35)
 static values of the items on request

fitting:

Flat head screw M8x35 ISO 7380 A2-70
 Square nut M8 low form DIN 562 A2-50

