

SIGNIFICANT HAZARDS

ASSESSMENT OF RISK

V. LOW	LOW	MED	HIGH
--------	-----	-----	------

1	Injury to operatives from falling materials				X
2	Injury to trespassers, especially children				X
3	Environmental contamination		X		
4					
5					
6					
7					
8					
9					
10					

ACTIONS ALREADY TAKEN TO REDUCE THE RISKS:

Compliance with:

CDM Regulations 2015

COSHH Regulations 2005

Manual Handling Operations Regulations 1992

Control of Pollution (Oil Storage) (England) Regulations 2001

HSE Guidance Booklet HSG 151 Protecting the public – your next move.

Planning:

Minimum quantities of materials will be supplied to site.

The manufacturer's recommendations will be followed with respect to temperature and humidity requirements, and stacking.

For hazardous materials, COSHH assessments will be required before delivery to site.

Physical:

Palletised loads will not exceed two pallets in height.

Loads will be lifted in the correct manner, avoiding the use of makeshift arrangements.

Compressed gas cylinders will be stored upright in ventilated cages.

Stacks of cylindrical objects such as pipes and cable drums will be stabilised using chokes or wedges.

Material stacks will be limited in height to ensure stability; heights of more than 2m will be avoided unless specifically authorised by site management.

Drums and containers will be marked clearly to indicate contents.

Secure storage will be provided for all hazardous substances, to prevent access by unauthorised persons.

Trays or bunds will be provided where necessary beneath containers to prevent ground contamination.

Guard-rails will be fitted to storage areas where persons could fall more than 2m.

Managerial/Supervisory:

Stockpiles and storage areas will be inspected regularly to ensure stability, and to ensure that the above physical precautions are in place.

Training:

Verbal instructions and training will be given to operatives as necessary to ensure good housekeeping standards are maintained on site. Stability and stacking instructions will be given as needed to site operatives by management.

SITE SPECIFIC ASSESSMENT

SITE/LOCATION: Land off Mill Lane, Gisburn

MAXIMUM NUMBER OF PEOPLE INVOLVED IN ACTIVITY: 30

FREQUENCY & DURATION OF ACTIVITY: 104 weeks

ADDITIONAL SPECIFIC HAZARDS IDENTIFIED:

ADDITIONAL CONTROL MEASURES REQUIRED: None

ASSESSMENT OF REMAINING RISKS: Insignificant / Low / Medium / High

SERIOUS & IMMINENT DANGER RISK IDENTIFIED: No

EMERGENCY ACTION REQUIRED:

NAMES OF COMPETENT PERSON(S) APPOINTED TO TAKE ACTION:

CIRCUMSTANCES WHICH WILL REQUIRE ADDITIONAL ASSESSMENT:

1. Storage of petrol
2. Storage of highly flammable liquids (see EC9)
3. Storage of LPG (see EC8)

ON SITE ASSESSMENT

SIGNED:

EJAldred

DATE

10th August 2018

File Reference

EA7B

