



Visibility splay - 2.4 x <100m

Visibility splay - 2.4 x <100m

Visibility splay - 2.4 x <120 m

Visibility splay - 2.4 x <120 m

Existing farm access track to SW of Bonds farm to have post and rail livestock fence including a trapezoidal kissing gate to BS709:2006 at the Southerly boundary between the 2 farms

Access track widened to 6m for a distance of 32m (min) from Hesketh Lane. Gates set back a minimum of 35m from carriageway bounded by 1.4m high dry stone wall with rounded copings, 1.4m high rounded top stone gate stoops and 4m wide 5 bar gate

Existing farm access track to SW of Bonds farm to have post and rail livestock fence including a trapezoidal kissing gate to BS709:2006 at the Southerly boundary between the 2 farms

Access track widened to 6m for a distance of 32m (min) from Hesketh Lane. Gates set back a minimum of 35m from carriageway bounded by 1.4m high dry stone wall with rounded copings, 1.4m high rounded top stone gate stoops and 4m wide 5 bar gate

Entire length of access track to be at or slightly below existing ground levels

Offline section required due to existing level differences

**Key**

- Proposed new access track - 3.5m wide - 6m wide at access junction Tarmac/concrete for first 32m.
- Current access track re-surfaced (min width 3.5m) - formed in stone
- Proposed passing bay (min width of access track & bay 5.5m)

<b>Mrs K. Kenyon</b>			
<b>Hesketh End Farm</b>		Scale <b>1:1000 @ A2</b>	
<b>Proposed Access</b>		Drawn <b>FR</b>	Checked <b>DW</b>
		Approved	
		Drwg No. <b>T2792/01</b>	
		Date <b>04/05/2018</b>	
		Rev.	A B

www.psadesign.co.uk  
mail@psadesign.co.uk

**PSA**  
DESIGN

engineering your environment  
CIVIL, STRUCTURAL, GEOTECHNICAL, TRANSPORT

PSA Design  
The Old Bank House  
6 Berry Lane, Longridge  
Preston, PR3 3JA  
Tel. 01772 786066  
Fax. 01772 786265

Rev B - Kissing gate added and walled entrance lengthened  
Rev A - Wall and gate added