

No	Location	Species	Hgt (m)	Girth Dia (mm)	Canopy Spread (Radius N/S/E/W in metres)	Age Class YEM/M/LM/OM	Condition (Good/Fair/Poor)	Target rating (H/M/L)	Size of part L/M/S	Likelihood Of failure H/M/L	Risk of Harm	Work required	Urgency H/M/L
T1	See plan	Beech	26	1600	11N	LM	Good. Root plate sound, loss of vigour in upper canopy, no poor attachments or deadwood. Butt sound to test. No recent branch loss	M	S	L	Low	Monitor	
T2	See plan	Sycamore	20	400	9N	M	Good, Tree suppressed to south. No deadwood or evidence of basal decay.	M	S	L	Low		
T5	See plan	Sycamore	26	950	9E	LM	Fair, Upper canopy is loosing Vigour. See photo to illustrate potential height reduction	L	S	H	Low	Reduction of the declining upper canopy by 25% will encourage growth in the lower canopy and make the tree less wind exposed	Low
T6	See plan	Sycamore	25	950	9S	LM	Good, Remove low branch adj minor codominant fork. Fall range of Neighbouring garage	M	M	M	Medium	Remove low branch	Med
T7	See plan	Copper Beech	25	650	8S	M	Good.	L	S	L	Low		
T8	See plan	Copper Beech	25	650	8S	M	Good.	L	S	L	Low		
T11	See Plan	Sycamore twin stem	26	780+850	8S	M	Good, conjoined trees at root plate level, wind protected. Some 50mm dia deadwood	L	S	L		Remove deadwood	low
T9/10	See plan	Birch (2)	12	200	4W	M	Fair, suppressed trees located close to wall and Wardens parking area	M	M	L	Low	Remove yellow spotted birch fouling boundary wall	Med
T12	See Plan	Ash	10	400	5	M	Fair, Large cavity at base, close to wall and canopy over parking area.	M	M	L	Medium	Fell and remove or reduce to nature stump (check Ownership)	High
T14	See Plan	Weeping Birch	10	500	3	LM	Central cavity, decayed buttress root, lean to wall, 25% canopy dieback. Electrics connected to tree	H	H	H	Medium	Fell and poison stump	High
Tag 350	See plan	Sycamore	24	800	9	LM	Fair, bark canker on main stem. No trace of internal decay or Fruiting bodies. Thinning canopy and branch deadwood. Twin stem with low fork	H	M			Remove deadwood and examine upper unions for leisons or fractures. Climber to report any adverse findings	Med
Tag 749	See plan	Sycamore	24	850	7	LM	Fair, slow growth, light deadwood	M	L	L	Low	Remove deadwood and sever ivy	Low
Tag 349	See plan	Beech	22	930	10	M	Good, Triple stem	M	L	L	Low		
Tag 353	See plan	Sycamore	23	880	6	M	Good fastigate form. Light deadwood and hanging deadwood					Remove deadwood and sever ivy	Low
Tag 357	See Plan	Beech	19	740	9	LM	Good, well rooted into bank. No indications of root plate movement,	M	L	L	Low		

T13 referred to two late mature and fire damaged sycamores at the top corner of the garden, The trees have central cavities and have been damaged in the past by garden bonfires. The trees are not near structures and appear stable so no action is recommended at this time. Try to keep fires at least 5m from the trees.