



**NOTES**

- Track to be DEFRA standard RP4: Livestock and machinery hardcore track as specified by the Countryside Stewardship:
- excavate a trench at least 2.4m wide and at least 150mm deep, or down to a naturally occurring hard surface
  - profile the edge of the track with the excavated soil
  - overlay the area with a geotextile membrane if the base of the trench lies on subsoil (a geotextile membrane is not needed if the base is bedrock or chalk)
  - fill the trench with stone or hardcore to a depth of at least 150mm, and compact it
  - finish the top of the track with a finer material (of 18mm to dust) to a depth of 25 to 50mm, and compact it into a convex camber
  - direct any track runoff to a ditch or other stable drainage outlet, or divert it on to grassland

Key:  
 DEFRA Standard RP4 Livestock and Machinery Track

REV	DATE	DRWN	CHKD	REVISION DETAILS
A	15/01/19	EN	RARW	PLANNING ISSUE

**PROJECT TITLE**  
 Proposed Tracks on Land at  
 Squire House  
 Knowle Green, PR3 2YS

**CLIENT**  
 Mr D Robinson

© Harrison & Pitt Architects Ltd

**DRAWING TITLE**  
 As Proposed  
 Site Plan

320190030P

<b>DRAWING STATUS</b> PLANNING	<b>SCALE:</b> 1:1250 @ A1
<b>DRAWING No.</b> 2079-02	<b>DATE:</b> January 2019
<b>REVISION</b> A	<b>DRAWN:</b> EN
	<b>CHECKED:</b> RARW



**HARRISON PITT ARCHITECTS**   
 29 CASTLE HILL  
 LANCASTER  
 LA1 1YN  
 Tel: 01524 32479  
 e-mail: hpa@hparch.co.uk  
 Web: www.hparch.co.uk

DO NOT SCALE SITE DIMENSIONS FROM THIS DRAWING