



LEGEND

- Existing Tree to be Retained
Trees to be retained and protected in line with BS5837:2012. Please refer to Arboricultural Method Statement and TPM Tree Survey Report and Drawing
- Existing Tree to be Removed
For condition and category grading of individual trees to be removed please refer to TPM Tree Survey Report and Drawing
- Root Protection Area (RPA)
RPA calculated inline with BS5837:2012
- Tree Not Surveyed
- Proposed Tree Protection Fence
To be installed prior to any enabling works on site and to remain in position during construction of proposed building and landscape works. Please refer to Arboricultural Method Statement and Figures on this drawing.
- Retaining Wall

Refer to 2630 5018 Arboricultural Survey Report for Method Statement

- GENERAL NOTES**
1. This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company.
 2. This drawing is to be read in conjunction with detail landscape drawings, details and specification.
 3. This drawing is to be read in conjunction with all relevant Architects', Engineer's, Specialist's, Bills of Quantities and Specifications.
 4. The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
 5. The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
 6. All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
 7. All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
 8. All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.

REVISION NOTES

Rev	By	Description	Date
B	GBS	Anomalous retaining wall removed	Feb2019
A	-	layout change and trees removed	feb2019

Client
Chipping Homes Ltd

Project
Chipping House

Description
Tree Retention Removals and Protection

Status
For Approval

Scale @ A1 1:500	Drawn GBS	Checked CT	Date Dec.18
Job number 2630	Drawing number 104	Revision B	