

TEGRAL VILLAR DEL REY SLATES

Product Data Sheet



Villar del Rey are exceptional quality natural slates with a distinctive smooth surface, fine grain and dark charcoal grey colour. They are sourced from Villar del Rey (Village of the King) near Badajoz in Spain, which is one of the most prestigious and historic quarries in the world. They are the most superior slate in our natural slate offering and come with a 75 year guarantee.



TECHNICAL DATA		
Size of slate	600 x 300mm	500 x 250mm
Minimum Pitch	25° (110mm Headlap)	25° (110mm Headlap)
Max Pitch	90°	90°
Typical Headlaps	100,110	100,110
Batten Gauge	245 - 250	200 - 195
Slate Thickness	7-8mm	7-8mm
Covering Capacity	13.1 slates/m2 (100 headlap) 13.4 slates /m2 (110mm headlap)	19.6 slates/m2 (100 headlap) 19.9 slates /m2 (110mm headlap)
Average weight per slate (approx)	3.21kgs	2.23kgs
Typical Quantity per Crate	440 No	560 No
Battens Required (net)	4.00 (net lin.m/m2) at 100 mm headlap	5.00 (net lin.m/m2) at 100 mm headlap
Batten size recommended (fixed as per SR82 : 2017)	50 x 25mm for rafter supports not exceeding 400 mm centres 50 x 35mm for rafter supports not exceeding 600 mm centres	
Fixings	Slate nails (40 x 3.35mm) Slate Hooks 2.5mm - 3.00 mm diameter	
Accreditation	EN 12326-1	EN 12326-1
Thermal Cycle Resistance	Class T1	Class T1
Water Absorption	Class W1	Class W1
Sulphur Dioxide Exposure Resistance	Class S1	Class S1

Tegral Building Products is independently certified as meeting requirements of ISO 9001(quality), ISO 14001 (environment), OHSAS 18001 (safety) and are rated "Excellent" in the BES 6001 Standard for responsible sourcing.

For further information visit www.tegral.com, call +353 (0)59 863 1316 or email our technical support department on support@tegral.com