

**Tree Planting Schedule**

Trees:  
Native specimen trees 3m standards, staked and planted in the planting compost. (8-10cm) 4.5m + spacing.

12 Number trees comprising the following

1x Acer compense (maple)	
1x Betula pendula (birch)	
1x Fagus sylvatica (beech)	
1x Prunus avium (cherry)	
2x Quercus robur (Oak)	
2x Sorbus aucuparia (Rowan)	
2x Taxus baccata (Yew)	
2x Cedrus deodora (Cedar)	

**Hedging:**  
45 - 90cm transplants at 45cm centre in a double staggered row -

**Hedgerow mix :-**

- Blackthorn/Hawthorn 50%
- Hazel/Fred maple/Holly 25%
- Dead spind mullet/Dog rose/Wild Pither/Honey suckle 15%
- Trees could include Ash, English oak and Sessile oak. AVOID ELDER



3 2 0 1 9 0 3 5 3

Amend - A - Proposed House Footprint Moved

**J.HADFIELD.**  
**ENGINEERING SURVEYING.**

Spring House, Chippenham, Wiltshire, PG3 2QD  
Tel: 01793 820068

Project Date: Mr & Mrs. R. Robinson  
Project Name: Proposed site plan.

Project Address: Starlings Farm, Longridge Rd, Chippenham, Wiltshire, PG3 2QD

Project Number: 301A201	Date: JUL/18	Scale: 1:200	By: JH
-------------------------	--------------	--------------	--------

DO NOT SCALE THIS DRAWING. CHECK ALL DIMENSIONS ON SITE

FOR THE RECORD: THIS DRAWING WAS PREPARED FROM THE FOLLOWING: 301A201