
Arboricultural
Impact Assessment
with
Tree Protection Measures

**27 Humber Street
Longridge
PR3 3WD**

GODWINS ARBORICULTURAL LIMITED
www.godwins.co.uk

SUMMARY

Eight individual trees, three groups of trees and one hedge were recorded. In accordance with *BS5837:2012 Trees in relation to design, demolition and construction* one individual tree was recorded as retention category 'B'; and a mixture of seven individual trees, three groups of trees and one hedge were recorded as retention category 'C'.

The trees were generally found to be in a good to fair condition and no trees were classified as retention category 'U' (unsuitable for retention).

No trees shall require removal to enable the construction of the proposed development.

The retained trees will be protected to British Standard *BS5837:2012 Trees in relation to design, demolition and construction* to ensure that they remain in a healthy condition during and post development. The *Tree Protection Plan* to the rear of this report highlights the recommended tree protection measures.

Any arboricultural work undertaken should be done so by a competent arborist in line with British Standard *BS3998:2010 Tree Work*, and after permission has been granted to do so by the local planning authority.

CONTENTS

1. Introduction.....	1
1.1. Project outline	1
1.2. Scope of this report	1
1.3. Data collection.....	1
2. Arboricultural Constraints	2
2.1. Tree retention categories.....	2
2.2. Tree age class and condition	2
2.3. Root Protection Areas	3
2.4. Tree protection status.....	3
3. Arboricultural Impact Assessment	4
3.1. The proposed development.....	4
3.2. Tree removal	4
3.3. Proposed tree pruning works	4
3.4. Site construction traffic and demolition works.....	4
3.5. RPA beyond the protective barriers	4
3.6. Post development impacts	5
4. Tree Protection Measures.....	6
4.1. Tree works prior to development.....	6
4.2. Tree protection barriers	6
4.3. Temporary ground protection	6
4.4. Services within the RPA	7
 Drawing 1. Tree Constraints Plan	 9
Drawing 2. Tree Protection Plan.....	10
 Appendix 1. Tree Schedule	 11
Appendix 2. Explanatory Notes	12
Appendix 3. Report Limitations & General Guidelines	15
Appendix 4. Protective Barrier Construction.....	17

1. Introduction

1.1. Project outline

- 1.1.1. This report has been produced in accordance with *British Standard BS5837: 2012 Trees in relation to design, demolition and construction* to achieve a harmonious and sustainable relationship where tree retention or planting is proposed in conjunction with nearby construction (site-based operations with the potential to affect existing trees).

1.2. Scope of this report


- 1.2.1. This report has been produced to comply with planning requirements where trees are to be considered as part of a proposed development. To achieve this, arboricultural constraints have been identified and a detailed plan (*Tree Constraints Plan*) has been produced showing the location, root protection areas and retention category of trees within the site.
- 1.2.2. In addition, this report provides an *Arboricultural Impact Assessment* that evaluates the direct and indirect effects of the proposed development, and where necessary makes recommendations for mitigation measures. This report also includes *Tree Protection Measures* and a *Tree Protection Plan*, which demonstrate how the retained trees will be protected during construction, and where tree protection measures are to be implemented.
- 1.2.3. This report does not form part of a tree safety inspection. To manage the safety and risk from trees it is advised that trees are inspected in detail for this purpose by an arboriculturist using a suitable risk management strategy.

1.3. Data collection

- 1.3.1. A ground level inspection was undertaken by Godwins Arboricultural Limited on 28th March 2019. As recommended by *BS5837*, the position of all trees within the site with a stem diameter of 75 mm or more, measured at 1.5 m above highest adjacent ground level are recorded. The position of trees with an estimated stem diameter of 75 mm or more that overhang the site or are located beyond the site boundaries within a distance of up to 12 times their estimated stem diameter were also recorded. For individual trees the crown spread taken at four cardinal points; for woodlands or substantial tree groups the overall extent of the canopy was recorded.
- 1.3.2. Tree positions were plotted using a site location plan, aerial photography and on-site measurements, which is the basis for which the *Tree Constraints Plan* has been prepared.


2. Arboricultural Constraints

2.1. Tree retention categories



- 2.1.1. Eight individual trees, three groups of trees and one hedge were recorded. In accordance with *BS5837:2012 Trees in relation to design, demolition and construction* one individual tree was recorded as retention category 'B'; and a mixture of seven individual trees, three groups of trees and one hedge were recorded as retention category 'C'.

2.2. Tree age class and condition



- 2.2.1. The trees were generally found to be in a good to fair condition and no trees were classified as retention category 'U' (unsuitable for retention).
- 2.2.2. Please see *Appendix 1* for the detailed list on existing species, age class, dimensions and condition of trees within the site, and *Appendix 2* for an explanation of retention category criteria. Tree locations can be seen on the *Tree Constraints Plan* at the rear of this report (*Drawing 1*).
- 2.2.3. The inspection of several trees was restricted as detailed at *Appendix 1*. However, sufficient tree related data was collected to fulfil the requirements detailed within the scope of this report.

2.3. Root Protection Areas

- 2.3.1. The tree Root Protection Area (RPA) is a layout design tool indicating the area around a tree that, along with the tree stem and branches, must be considered during development. The protection of the roots and soil structure within the RPA should be treated as a priority. The RPA of each tree or group is marked on the *Tree Constraints Plan* at the rear of this report.

2.4. Tree protection status

- 2.4.1. A statutory tree protection enquiry was made with Ribble Valley Borough Council on 5th April. We are still awaiting the results of the enquiry, and will forward them once they are available.
- 2.4.2. **In the meantime, it is essential that no works are undertaken to any trees within the site prior to consideration and consent of the proposed works under full planning approval by the local planning authority regardless of whether the trees are currently protected or not.**

3. Arboricultural Impact Assessment

3.1. The proposed development

- 3.1.1. A new residential development with associated car parking and driveway is proposed. The proposed layout drawing can be seen within the *Tree Protection Plan* to the rear of this report. This drawing has been used to assess the potential direct and indirect arboricultural impacts.

3.2. Tree removal

- 3.2.1. No trees shall require removal to enable the construction of the proposed development.

3.3. Proposed tree pruning works

- 3.3.1. The formative pruning of tree **T10** is recommended to ensure sufficient clearance between the proposed dwelling and adjacent branches. The proposed pruning works relate to the crown lifting/pruning of small tertiary branches. The proposed pruning works will have no adverse impacts on tree health and longevity.

3.4. Site construction traffic and demolition works

- 3.4.1. To protect the trees from construction site traffic (including demolition works) the remaining trees should be protected by a temporary protective barrier (see *Section 4.2*), put in place prior to any construction activity. The barrier will ensure that the trees remain in a healthy condition during and after development.
- 3.4.2. Several of the retained trees are located beyond existing boundary fencing or away from the proposed development area. As such, these trees shall not require protection via temporary protective barriers as they are already provided protection due to their inaccessible location that is remote from the proposed construction activity.

3.5. RPA beyond the protective barriers

- 3.5.1. Sections of RPA from **T8, T9, T10, T11** and **H12** extend beyond the existing boundary fence and into the proposed working area. It is understood that no ground level changes or excavations are proposed within these RPAs. However, as a precautionary measure, it is recommended that temporary ground protection is installed as indicated on the *Tree Protection Plan*, and put in place to prevent soil compaction and contamination prior to and during the demolition and construction phase.

3.6. Post development impacts

- 3.6.1. No soil samples were taken during the site visit. It is recommended that soil assessment is undertaken by a competent person to determine whether the soil is shrinkable, and that foundation design is undertaken in line with detailed guidance given in the National House Building Council (NHBC) publication *Building near trees, Chapter 4.2*.
- 3.6.2. It is essential that consideration is also given by a suitably qualified professional to how the proposed tree removal may affect soil conditions and the stability of any future foundations.

4. Tree Protection Measures

4.1. Tree works prior to development

- 4.1.1. Care should be taken to ensure during tree removal or remedial work that damage to the retained trees and disturbance to the RPA is avoided. All tree works, as described in *Appendix 1*, should be carried out in accordance with *BS 3998: 2010 Recommendations for tree work*, and after permission has been granted to do so by the local planning authority. It is essential that those appointed to undertake any tree works carry out adequate checks to ensure that no statutory laws are contravened during tree work operations.

4.2. Tree protection barriers

- 4.2.1. Once the tree works have been completed, all trees that may be affected by construction activity and are being retained on site should be protected by barriers before any materials or machinery are brought onto the site, and before any demolition, development or stripping of soil commences. No hardcore, rubble or soil from groundworks should be located within the protective barriers. It should be confirmed by an arboriculturist or the local authority that the barriers have been correctly set out on site, prior to the commencement of any other operations.
- 4.2.2. The protected area should be regarded as off limits, and once installed barriers should not be removed or altered without prior recommendation by an arboriculturist and, where necessary, approval from the local planning authority.
- 4.2.3. Please see *Appendix 4* for suggested barrier construction detail. It is recommended that in this instance the protective barrier shown in *Figure 2* would be appropriate. The suggested location for protective fencing is shown on the *Tree Protection Plan (Drawing 2)*.
- 4.2.4. Only when the development phase is complete and the site machinery has been removed, the local planning authority should be invited to inspect the site to give approval for the removal of the tree protection measures.

4.3. Temporary ground protection

- 4.3.1. Ground protection in the form of ridged material, suitable to distribute the weight of any potential traffic, should be installed. Areas that require temporary ground protection are identified with an orange hatch on the *Tree Protection Plan (Drawing 2)*. British Standard BS5837 recommends that:
The ground protection might comprise one of the following:

- a) for pedestrian movements only, a single thickness of scaffold boards placed either on top of a driven scaffold frame, so as to form a suspended walkway, or on top of a compression-resistant layer (e.g. 100 mm depth of woodchip), laid onto a geotextile membrane;*
- b) for pedestrian-operated plant up to a gross weight of 2 t, proprietary, inter-linked ground protection boards placed on top of a compression-resistant layer (e.g. 150 mm depth of woodchip), laid onto a geotextile membrane;*
- c) for wheeled or tracked construction traffic exceeding 2 t gross weight, an alternative system (e.g. proprietary systems or pre-cast reinforced concrete slabs) to an engineering specification designed in conjunction with arboricultural advice, to accommodate the likely loading to which it will be subjected.*

4.4. Services within the RPA

- 4.4.1.** Wherever possible, under-ground services should be routed outside of the RPA of retained trees, and plans showing the proposed routeing should be drawn up. Where excavations may be required hand-held tools might be acceptable for shallow service runs.

Client: Mrs C Mercer
Project No: AIA.12982
Issue: 01

Date Issued: 5th April 2019
Status: FINAL

Signed for on behalf of Godwins Arboricultural Limited:

R Godwin

Robert Godwin MSc MArborA.
Arboriculturist

Contact Details:

Godwins Arboricultural Limited
Digital World Centre
1 Lowry Plaza, The Quays
Salford
Manchester
M50 3UB

www.godwins.co.uk
info@godwins.co.uk
0800 030 4045

Drawing 1. Tree Constraints Plan



T	G	H	W	S
INDIVIDUAL TREE	GROUP OF TREES	MODERN	WOODLAND GROUP	ARBO


EXISTING LAYOUT

TREE QUALITY ASSESSMENT CATEGORY
CATEGORY 'A' HIGH QUALITY
CATEGORY 'B' MODERATE QUALITY
CATEGORY 'C' LOW QUALITY
CATEGORY 'U' UNSUITABLE FOR RETENTION

Based on British Standard BS5839:2017 Table 1
Please refer to Appendix 2 of the arboricultural report for more detailed category definitions.

ROOT PROTECTION AREA (RPA)

The Root Protection Area (RPA) is a legal design tool highlighting the retention of trees. It is defined as the area around the tree trunk and its roots, which must be protected from any damage during development. Along with the tree trunk and its roots, the RPA must be considered prior to and during development.




Written content must be obtained from Godwins Arboricultural Limited before copying or using the data within this drawing other than for the purpose it was originally supplied.
Do not scale from this drawing.

GODWINS ARBORICULTURAL LIMITED
www.godwins.co.uk Tel: 0800 030 4045 info@godwins.co.uk
Digital World Centre, 1 Leamy Plaza, The Quays, Salford, M69 3UB.

PROJECT TITLE: 27 Humber Street, Longridge			
DRAWING TITLE: TREE CONSTRAINTS PLAN	SCALE: 1:200 @ A2	ISSUE DATE: 29/03/19	
DRAWING NUMBER: TCP 12382	REVISION: .01	DRAWN BY: RG	

Drawing 2. Tree Protection Plan



T	G	H	W	S
Individual Tree	Group of Trees	Heritage	Woodland Group	Status

EXISTING LAYOUT
PROPOSED LAYOUT

PROPOSED TREE WORKS
TREE PROPOSED FOR RETENTION
TREE PROPOSED FOR PRUNING
FOR ARBORICULTURAL REASONS: REASON TO ENABLE DEVELOPMENT: T10
TREE PROPOSED FOR REMOVAL (ARBORICULTURAL REASONS)
None
TREE PROPOSED FOR REMOVAL (TO ENABLE DEVELOPMENT)
None
Please refer to Appendix 1 of the Arboricultural Impact Assessment for details on tree condition and proposed works.
ROOT PROTECTION AREA (RPA)
The Root Protection Area (RPA) is a broad design tool highlighting the underground tree canopy. Along with the tree stem and branches the RPA must be considered prior to any development.
TREE PROTECTION MEASURES
TEMPORARY PROTECTIVE BARRIER To be used to protect the RPA during construction works.
RPA WITHIN PROPOSED WORKING AREA GROUND PROTECTION REQUIRED
T8, T9, T10, T11 & T12
Please refer to Section 3 of the Arboricultural Impact Assessment for details on potential impacts.

Written consent must be obtained from Godwins Arboricultural Limited before copying or using the data within this drawing other than for the purpose it was originally supplied.

© Godwins 2019

PROJECT TITLE: 27 Humber Street, Longridge	
DRAWING TITLE: TREE PROTECTION PLAN	SCALE: 1:200 @ A2
DRAWING NUMBER: TPP.12982	REVISION: .01
	DRAWN BY: RG
ISSUE DATE: 05/04/19	

GODWINS ARBORICULTURAL LIMITED
www.godwins.co.uk Tel: 0800 030 4045 info@godwins.co.uk
Digital World Centre, 1 Lowry Plaza, The Quays, Salford, M6G 3UB.

Appendix 1. Tree Schedule

Tree No.	Species	Age	Stems at 1.5m	Stem Dia (mm)	Height (Crown Hgt)	FSB (D)	Branch Spread (m)					Observations	Cord	Life Exp	Tree Work Recommendations	Root Protection Area (RPA)		Retention Category
							N	E	S	W						Radius (m)	Area (m²)	
T 1	Prunus sp. (Cherry)	Semi-mature	1	320	8.5(2.5)	2.5(E)	5	5	3.5	5		Asymmetrical crown. Limited inspection - situated on adjacent land.	Good to Fair	40+	No action required.	3.8	46.3	B
G 2	Prunus sp. (Cherry)	Young	1	100	5.5(3)	3(E)	2	2	2	2		Limited inspection - situated on adjacent land. Asymmetrical crowns.	Good to Fair	40+	No action required.	1.2	4.5	C
T 3	Prunus sp. (Cherry)	Early-mature	3	170	5(2)	2(E)	4	3.5	3	3		Asymmetrical crown. Multiple pruning wounds.	Fair	20+	No action required.	3.5	39.2	C
T 4	Picea abies (Norway Spruce)	Young	1	90	4(2)	2(E)	0.5	0.5	1	1		Asymmetrical crown.	Fair	10+	No action required.	1.1	3.7	C
G 5	Aucuba japonica (Japanese Laurel)	Semi-mature	1	75	3(0)	0(E)	1	1	1	1		Multi-stemmed from ground level. Linear boundary group.	Good to Fair	20+	No action required.	0.9	2.6	C
T 6	Ilex aquifolium (Holly)	Young	1	90	5(0)	0(W)	1.5	1.5	1.5	1.5		Balanced crown.	Good to Fair	40+	No action required.	1.1	3.7	C
G 7	Cupressus sp. (Cypress)	Semi-mature	1	100	5(0.5)	0.5(S)	1.5	1.5	1.5	1.5		Individuals crowns restricted by group. Linear boundary group.	Good to Fair	40+	No action required.	1.2	4.5	C
T 8	Picea abies (Norway Spruce)	Semi-mature	1	230	8.5(1.5)	1.5(S)	3	3	3	2		Asymmetrical crown. Multiple pruning wounds. Limited inspection - situated on adjacent land.	Good to Fair	40+	No action required.	2.8	23.9	C
T 9	Cupressus macrocarpa (Monterey Cypress)	Semi-mature	1	300	10(2)	2(S)	2.5	2	3.5	1.5		Asymmetrical crown. Limited inspection - situated on adjacent land.	Good to Fair	40+	No action required.	3.6	40.7	C
T 10	Cupressus macrocarpa (Monterey Cypress)	Semi-mature	4	150 200 100 100	10(2)	2(W)	2.5	1.5	3	3		Asymmetrical crown. Limited inspection - situated on adjacent land.	Good to Fair	40+	Crown reduce western canopy edge to ensure minimum 1m distance from the proposed dwelling.	3.4	37.2	C

Tree No.	Species	Age	Stems at 1.5m	Stem Dia (mm)	Height (Crown Hgt) (m)	FSB (D) (m)	Branch Spread (m)				Observations	Cond	Life Exp	Tree Work Recommendations	Root Protection Area (RPA)		Retention Category
							N	E	S	W					Radius (m)	Area (m ²)	
T 11	Sorbus aucuparia (Rowan)	Semi-mature	1	180	7(1)	1(W)	2	1	1	2	Asymmetrical crown. Limited inspection - situated on adjacent land.	Fair	20+	No action required.	2.2	14.7	C
H 12	Cupressus sp. (Cypress)	Semi-mature	1	100	5(3)	3(S)	1	0.5	0.75	0.5	Limited inspection - situated on adjacent land. Linear boundary hedge. Maintained. Several dead stems within hedge.	Fair	20+	No action required.	1.2	4.5	C

Appendix 2. Explanatory Notes

A2.1. Tree statistics and measurements

Survey record	Description
<i>Tree No.</i>	Unique tree reference number. (T) = Individual tree, (G) = Group of trees or woodland that form cohesive arboricultural features, (H) = Hedgerows and substantial internal or boundary hedges.
<i>Species</i>	Species listed by scientific name, with (common name).
<i>Age</i>	Life stage – Young, Semi-mature, Early-mature, Mature, Over-mature and Veteran.
<i>Stem Count</i>	Number of stems recorded at 1.5m above ground level.
<i>Stem Diameter</i>	Stem diameter recorded in millimetres at 1.5 meters above ground. Where the tree is multiple stemmed, each stem has been recorded.
<i>Height (Crown Height)</i>	Height of the tree in metres – to the closest 0.5m. Average canopy height in brackets, e.g. 10(3).
<i>First Significant Branch</i>	Existing height above ground level of first significant branch and direction of growth, e.g. 3(N)
<i>Branch Spread</i>	Branch spread, taken as a minimum at the four cardinal points – North, East, South and West.
<i>Observations</i>	General observations, particularly of structural and/or physiological condition (e.g. the presence of any decay, physical defect or historic pruning).
<i>Cond</i>	Condition of the tree recorded as Good, Good to Fair, Fair, Fair to Poor, Poor or Dead.
<i>Life Exp</i>	Life Expectancy - classed as less than 10 years, 10 plus years, 20 plus years, or more than 40 years.
<i>Tree Work Recommendations</i>	Recommended tree works – including those made to enable the proposed development.
<i>RPA Radius</i>	Radius of the root protection area, when plotted as a circle centred on the base of the stem.
<i>RPA Area</i>	Total area of RPA in metres squared, e.g. 100m ² .
<i>Retention Category</i>	See below – A2.2.

A2.2. Tree retention categories


Retention category and definition	Criteria
<i>U (marked in red on the Tree Constraints Plan) = trees for removal.</i>	Trees in such a condition that they cannot realistically be retained as living trees in the context of the current land use for longer than 10 years.
<i>A (marked green on the Tree Constraints Plan) = Trees of high quality</i>	Trees of high quality with an estimated remaining life expectancy of at least 40 years.
<i>B (marked in blue on the Tree Constraints Plan) = Trees of moderate quality</i>	Trees of moderate quality with an estimated remaining life expectancy of at least 20 years.
<i>C (marked in grey on the Tree Constraints Plan) = Trees of low quality</i>	Trees of low quality with an estimated remaining life expectancy of at least 10 years, or young trees with a stem diameter below 150mm.

Appendix 3. Report Limitations & General Guidelines

- A3.1 Where the inspection of trees was limited (*see Appendix 1*), the 'Tree statistics and measurements' (*Appendix 2.1*) are estimated, and observations, condition and life expectancy are based on an inspection from the available vantage point.
- A3.2 It is recommended that qualified and experienced companies are sought when appointing tree work contractors and they should be approved under the Arboricultural Association Approved Contractors scheme. It is essential that all appointed tree work contractors have adequate Public Liability, Products Liability and Employers Liability Insurance. All tree works must conform to the current BS 3998 "*Recommendations for Tree Work*".
- A3.3 Godwin's Arboricultural Ltd will not accept liability for works undertaken by third party companies. All necessary checks must be made by the appointed tree work contractor prior to undertaking any works to ensure that no statutory tree protection measures or relevant laws are contravened.
- A3.4 The validity, accuracy and findings of this report are directly related to the accuracy of the information made available prior to and during the inspection process. No checking of independent third party data will be undertaken. Godwin's Arboricultural Ltd will not be responsible for the recommendations within this report where essential data are not made available, or are inaccurate.
- A3.5 The assessment and works recommendations relate to conditions found at the time of our inspection. Any significant alteration to the site post our site inspection but pre submission for planning that may affect the trees present, or have a bearing on the planning implications (including level changes, hydrological changes, storms, extreme climatic events or site works) will necessitate a re-assessment of the trees and the site.
- A3.6 This report has been carried out in order to inform the planning process, and not to assess the potential hazards and risks posed by trees. Where clear and obvious hazards have been observed to accessible trees, these have been addressed in the works recommendations. Where inspections were limited by restrictions such as stem ivy, understory vegetation, limited access, epicormic growth or being located on adjacent land, any form of tree condition assessment was restricted. A full assessment of the levels of risk posed by trees can only be informed by considering site use together with assessing any hazards present within a tree.
- A3.7 Trees are dynamic structures that continue to develop and decline; in addition, changes in site use are likely to occur during and as a result from the proposed development. On this basis, regular tree risk assessments are advised.
- A3.8 Godwin's Arboricultural Ltd plans are to scale whenever possible but care should be taken when measuring from a plan without first checking the original data.

Appendix 4. Protective Barrier Construction

- A4.1 The default specification for protective barriers should consist of a vertical and horizontal scaffold framework, well braced to resist impacts, as illustrated below. The vertical tubes should be spaced at a *maximum* interval of 3 m and driven securely into the ground. Onto this framework, welded mesh panels should be securely fixed. Care should be exercised when locating the vertical poles to avoid underground services and, in the case of the bracing poles, also to avoid contact with structural roots.



Key

- 1 Standard scaffold poles
- 2 Heavy gauge 2 m tall galvanized tube and welded mesh infill panels
- 3 Panels secured to uprights and cross-members with wire ties
- 4 Ground level
- 5 Uprights driven into the ground until secure (minimum depth 0.6 m)
- 6 Standard scaffold clamps

Figure 1. Default protective fencing barrier as detailed in *BS 5837: 2012*.

- A4.2 Where the site circumstances and associated risk of damaging incursion into the RPA do not necessitate the default level of protection, an alternative specification may be adopted. This system includes 2 m tall welded mesh panels on rubber or concrete feet, secure enough to provide an adequate level of protection from cars, vans, pedestrians and manually operated plant. In such cases, the fence panels should be joined together using a minimum of two anti-tamper couplers, installed so that they can only be removed from inside the fence. The distance between the fence couplers should be at least 1 m and should be uniform throughout the fence. The panels should be supported on the inner side by stabilizer struts, which should normally be attached to a base plate secured with ground pins (Figure 2a). Where the fencing is to be erected on retained hard surfacing or it is otherwise unfeasible to use ground pins, e.g. due to the presence of underground services, the stabilizer struts should be mounted on a block tray (Figure 2b).




Figure 2. Examples of above-ground stabilizing systems

Godwins Arboricultural Limited © 2019
Tree Surveys and Tree Reports

info@godwins.co.uk | www.godwins.co.uk