



Services and controls

- 1.18** To assist people who have reduced reach, services and controls should comply with all of the following.
- Switches and sockets, including door bells, entry phones, light switches, power sockets, TV aerials and telephone jacks, serving **habitable rooms** throughout the **dwelling** have their centre line 450-1200mm above floor level, as shown in Diagram 1.5.
 - Consumer units are mounted so that the switches are 1350-1450mm above floor level.

