

Calculated by: Sohan Ghimire
Site name: Lincoln Way
Site location: Clitheroe BB7 1QD

Site coordinates

Latitude: 53.87646° N
Longitude: 2.37902° W

This is an estimation of the greenfield runoff rate limits that are needed to meet normal best practice criteria in line with Environment Agency guidance "Preliminary rainfall runoff management for developments", W5-074/A/TR1/1 rev. E (2012) and the SuDS Manual, C753 (Ciria, 2015). This information on greenfield runoff rates may be the basis for setting consents for the drainage of surface water runoff from sites.

Reference: 6504456
Date: 2018-12-08T13:15:47

Methodology

IH124

Site characteristics

Total site area (ha)	0.28
----------------------	------

Methodology

Qbar estimation method	Calculate from SPR and SAAR
SPR estimation method	Calculate from SOIL type

	Default	Edited
SOIL type	4	4
HOST class	---	---
SPR/SPRHOST	0.47	0.47

Hydrological characteristics

	Default	Edited
SAAR (mm)	1241	1241
Hydrological region	10	10
Growth curve factor: 1 year	0.87	0.87
Growth curve factor: 30 year	1.7	1.7
Growth curve factor: 100 year	2.08	2.08

Notes:

(1) Is $Q_{BAR} < 2.0$ l/s/ha?

(2) Are flow rates < 5.0 l/s?

Where flow rates are less than 5.0 l/s consents are usually set at 5.0 l/s if blockage from vegetation and other materials is possible. Lower consent flow rates may be set in which case blockage work must be addressed by using appropriate drainage elements

(3) Is $SPR/SPRHOST \leq 0.3$?

Greenfield runoff rates

	Default	Edited
Qbar (l/s)	2.64	2.64
1 in 1 year (l/s)	2.3	2.3
1 in 30 years (l/s)	4.49	4.49
1 in 100 years (l/s)	5.49	5.49