



# ELEVATION

75mm x 75mm Tanalised Softwood posts at approx. 2000mm centres,  
75mm x 25mm square edged boards at length indicated by detail.  
Boards to be nailed vertically at 100mm ctrs to bearers at  
each board and rail with 50mm galvanised nails.  
100mm x 50mm softwood rails.

# SECTION

REV DATE DESCRIPTION



Helm Bank, Natland, Kendal  
Cumbria LA9 7PS  
Tel:015395 60605 OakmereHomes.co.uk

PROJECT TITLE

DRAWING TITLE  
1800mm -1000mm Hit & Miss Plot Divisional Timber Fence

DRAWING NUMBER SD-FT-02 REVISION -

DATE 01/18 SCALE 1:20@A3