


TARMACADAM



All Tarmac to comply with BS 4987.
Clear access road of debris and rubble on completion and make good.
Supply, lay and compact 70mm of 20mm dense base course bitmac, and 30mm of 6mm hardstone bitmac wearing course to falls and levels.
Supply, lay and compact minimum of 225mm of DTp1 crushed stone sub-base material to falls and levels. Excavate any soft spots in sub-grade as required and dispose. Excavate to reduced depth of at least 200mm below finished level and cart all spoil to licensed, off-site tip.

PROPOSED SITE PLAN
SCALE 1:200



NORTH EAST IMAGE OF ACCESS ROAD



SOUTH WEST IMAGE OF ACCESS ROAD

Client		
Mr Rob Evans		
Job Title		
Development and Conversion of the former Lodematic Premises at Primrose Road, Clitheroe		
Drawing Title		
PROPOSED ACCESS ROAD SURFACING		
Scale	Date	Drawn
1:100 @ A1	Nov 2019	Paul Gudgeon

