



Planting Schedule



Woodland Tree Mix - 2,060 m ²									
Abbrev.	Name	Girth/ Dia. cm	Height cm	Root Zone	Specification	Mix %	Area	Ctr m	Qty
Ac	Acer campestre		200-250	B	2x; Feathered; 5 brks	10		2	52
Bpe	Betula pendula		200-250	B	2x; Feathered; 5 brks	10		2	52
Cav	Corylus avellana		80-100	B	1+2; Transplant - seed raised; branched; 4 brks	10		2	52
Cmo	Crataegus monogyna		175-200	B	2x; Feathered; 5 brks	10		2	52
la	Ilex aquifolium		60-80	3L	Leader with laterals	10		2	52
Psvl	Pinus sylvestris		40-60	3L	Leader with laterals	5		2	26
Pav	Prunus avium		200-250	B	2x; Feathered; 5 brks	10		2	52
Ppa	Prunus padus		200-250	B	2x; Feathered; 5 brks	10		2	52
Qpe	Quercus petraea		250-300	B	2x; Feathered; 5 brks	10		2	52
Sau	Sorbus aucuparia		200-250	B	2x; Feathered; 5 brks	10		2	52
Si	Sorbus intermedia		200-250	B	2x; Feathered; 5 brks	5		2	26
TOTALS						100			520

Hedging Mix - 210 Lm									
Abbrev.	Name	Girth/ Dia. cm	Height cm	Root Zone	Specification	Mix %	Area	2Ctr m	Qty
Cav	Corylus avellana		80-100	B	1+2; Transplant - seed raised; branched; 4 brks	15		0.5	126
Cmo	Crataegus monogyna		100-125	B	1+2; Transplant - seed raised	15		0.5	126
fs	Fagus sylvatica		100-125	B	1+2; Transplant - seed raised	25		0.5	210
la	Ilex aquifolium		60-80	3L	Leader with laterals	30		0.5	252
Psp	Prunus spinosa		100-125	B	1+2; Transplant - seed raised; branched; 4 brks	15		0.5	126
TOTALS						100			840

Willow and Alder Mix - 220 m ²									
Abbrev.	Name	Girth/ Dia. cm	Height cm	Root Zone	Specification	Mix %	Area	Ctr m	Qty
Agf	Alnus glutinosa		125-150	B	2x; Feathered; 2 brks	20		1	44
Sa	Salix alba		100-125	B	0/2; Cutting	20		1	44
Scap	Salix caprea		80-100	B	0/2; Cutting; branched; 2 brks	20		1	44
Sci	Salix cinerea		100-125	B	0/2; Cutting; branched; 3 brks	20		1	44
Svim	Salix viminalis		80-100	B	0/1; Cutting; branched; 2 brks	20		1	44
TOTALS						100			220

KEY

- Proposed Lodges
- Proposed Hedgerow Planting Mix
- Existing Hedgerow Gapping Up
- Existing Hedgerow Retained
- Proposed Planting - Woodland Tree Mix
- Proposed Planting - Willow and Alder Mix
- Existing Canopy Retained
- Existing Post & Wire Fence



Context Plan
Scale 1:5000

- NOTES:
- Ensure that mixes are planted with no more than three of the same species next to each other to ensure a random mix
 - Typical areas for planting shown
 - Hedge to be planted as a double staggered row

Galpin Landscape Architecture
info@galpinlandscape.com
www.galpinlandscape.com

Client: Holgates (Caravan Parks) Ltd
Project: Rimington Caravan Park
Location: Rimington, Lancashire
Drawing: Planting Plan Sheet 1 of 2
Scale@PaperSize: 1:500@A1 Date: Oct 19 Drawn By: AP Chk/App By: SJG
Drawing Nr: RTP 700 Revision: Rev0 Status: Planning