

**Description**

The IP65 driverless range of QuaZar™ Floodlights incorporate the latest in high voltage LED technology. With their ultra slim profile and high performance, now you can light your external areas and gardens without affecting the appearance. Available in 10W, 30W, 50W and 65W versions including black and white housing finishes to suit external fascias.

**Features & Benefits**

- IP65 rated LED floodlight with ultra slim design for minimal visual impact
- Marine voltage LED chips - no driver for improved reliability
- IK08 rated aluminum housing and tempered glass provides excellent protection
- Available in black and white finish housing
- Pre-wired with 500mm of cable
- 1.5kV surge protection
- 3 year warranty

**SLIM PROFILE  
HIGH PERFORMANCE**

**up to 4500 Lumens  
L70 25,000 Hours**



**ENFLH10**  
10W Adjustable IP65  
Driverless LED Floodlight



**ENFLH20**  
20W Adjustable IP65  
Driverless LED Floodlight



**ENFLH30**  
30W Adjustable IP65  
Driverless LED Floodlight



**ENFLH50**  
50W Adjustable IP65  
Driverless LED Floodlight



Cat. No.	Watts	Colour	Lumens	lm/W	L70 Life (hrs)	H x W x D (mm)	Halogen Subst.
ENFLH10*/30	10W	3000K	900lm	80	25,000	90 x 130 x 33mm	60W
ENFLH10*/40	10W	4000K	900lm	80	25,000	90 x 130 x 33mm	60W
ENFLH10*/65	10W	6500K	900lm	80	25,000	90 x 130 x 33mm	60W
ENFLH20*/30	20W	3000K	2000lm	100	25,000	125 x 191 x 34mm	100W
ENFLH20*/40	20W	4000K	2000lm	100	25,000	125 x 191 x 34mm	100W
ENFLH20*/65	20W	6500K	2000lm	100	25,000	125 x 191 x 34mm	100W
ENFLH30*/30	30W	3000K	3000lm	100	25,000	163 x 211 x 37mm	150W
ENFLH30*/40	30W	4000K	3000lm	100	25,000	163 x 211 x 37mm	150W
ENFLH30*/65	30W	6500K	3000lm	100	25,000	163 x 211 x 37mm	150W
ENFLH50*/30	50W	3000K	4500lm	90	25,000	190 x 274 x 42mm	200W
ENFLH50*/40	50W	4000K	4500lm	90	25,000	190 x 274 x 42mm	200W
ENFLH50*/65	50W	6500K	4500lm	90	25,000	190 x 274 x 42mm	200W

\*Add suffix **W** or **BLK** for White or Black finish

†Warranty covers LED chip

**Technical Information**

