Birks Brow

Forty Acre Lane

Brand New Swift Toronto Lodge

extg gated access to remain and be used as entrance to the new unit, contractor to allow for placing tarmac upto gates, and then be in coloured gravel or road plantings, to be determined

new retaining wall to be built in crib-block baskets to allow for planting
wall to form 2 number of car parking spaces 5.0x2.5 wide

extg dry stone wall to remain and have hedgerow planting behind it with a mix of native species of blackthorn and hawthorn

new unit to be cut into the site see section drawing for illustrative purposes and excavated matter to be placed around to form additional screen behind the new hedgerow

new wildflower seed planting to create natural meadow appearance in and around new unit area

new hedgerow to continue around from entrance gate in a southerly direction to the adjoining boundary as shown

N

NOTES

THIS DRAWING IS TO BE READ IN CONJUCTION WITH ALL OTHER DRAWINGS FOR THIS PROJECT.
ALL LEVELS AND DIMENSIONS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR, PRIOR TO PLACING ORDERS OR COMMENCING ANY OF THE RELEVANT WORKS.
ALL DIMENSIONS ARE IN MILLIMETRES UNLESS STATED OTHERWISE.
ANY DISCREPANCIES BETWEEN THE INFORMATION SHOWN ON THE PLAN AND THAT FOUND ON SITE ARE TO BE REPORTED TO THE DESIGNER IMMEDIATELY.

Rev.	Date	Description

A.L.H. Design Services
Barley Cottage, Brewery Street, Longridge, Lancs
PR3 3NB, Tel & Fax : (01772) 785719

Client

Mr G Morgan,
Smithy Cottage,
Birks Brow,
Longridge,
Nr Preston Lancs.PR3 2TY

Job/Scheme Title

ERECTION OF CABIN AND ASSOCIATED SITE WORKS

Please note, the area in blue denotes the remainder of the 4.5 acre field, the area in red is the location for the new lodge

Drawing Title

PROPOSED SITE PLAN

Job/Scheme Number		Drawing Number	
0558/93		Drawing No 12	
Scale	Date	Drawn	Checked
1/200	May 19	a.t.l-h.	