



1. 1400mm o/c all length. Posts at 2.0m centres set in augered hole and back filled with well rammed excavated material. Post to be 75x75mm treated larch rough sawn.

2. NB if specified, 75 diameter prick posts driven into the ground midway between the main posts may be used.

3. 2 No 100x20mm rough sawn rails fixed to all posts with 2 No 75mm galvanised nails per rail.



REDROW
Group Services Ltd

Title POST AND RAIL FENCING.

ADN - RSD - Scale at A4 1:20 Revision - Reference F-SD0900

Notes F SERIES

Published 26.09.2014