

Specification for the first 5m length of track

- 1. Soil stripped to a firm subsoil base.

- Terram membrane layer.
 Layer of compacted MOT type 1 for drainage.
 Layers of reducing size compacted with reducing
- 5. Minimum of 150mm MOT Type 16. 100mm binder course & 25mm surface layer

7. Macadam topping
Existing kerb to be lowered for the section 278 agreement

		7	7	Highway \$ proposed dropped kerb
/6				
	5			
	4			
	3			
	2			

SITE ENTRANCE DEATIL



Peter Hitchen ^rchitects

Marathon House The Sidings Business Park Whalley, BB7 9SE

01254 823 885

www.peterhitchenarchitects.co.uk

NOTES:

GRASSCRETE TO BE USED FOR TRACK MATERIAL

No.	Description	Date	

CLIENT:

BARRY TURNER

PROJECT:

PROPOSED HOLIDAY LODGES AND ACCOCIATED WORKS

SHEET:

SITE ENTRANCE

Project number	385
Date	11/02/21
Drawn by	DC
Checked by	PH

Λ	2	\cap	1
		U	4

1:100 Scale

Sheet size **A**1