



CHARLES J. NUTTER LLP

Building & Slating Contractor

Bankhurst Cottage, Off Knowles Brow, Stonyhurst, Clitheroe, BB7 9PW

Telephone: 01254 826698

VAT REG NO 776 9963 45

24th March 2021

Hall Barns Farm, Stonyhurst

Report on condition & proposed repair/replacement of structural timbers on partially collapsed roof elevation.

Wall plate to be retained over entire elevation.

Trusses: 3 complete trusses to be replaced in green oak.

All trusses to be mortice & tenon & peg jointed.

Lengths & sections to be as existing.

1 truss principal rafter to be renewed as above specification.

Purlins: 8 purlins to be replaced in green oak.

All joints to be oak peg jointed as existing.

All lengths & sections to be as existing.

Purlins: 5 to be strengthened by bolting 200 x 75 softwood purlins alongside, in order to keep timber replacement to a minimum.

Replacement & repaired timber locations marked on attached drawing.