

Notes

- Floodlighting Equipment**
 4 x 6m Mast (M1-M2 & M5-M6)
 2 x 6.5m Mast (M3-M4)
- Each carrying the following Floodlights :-
 M1-M2 & M5-M6
1 x Philips BV/P851/CF/FLDX80
 M3-M4
2 x Philips BV/P851/CF/FLDX80
- Illuminance Levels**
 Bath, Tennis courts
 (Initial)
 (100hrs) E.I.ave = 484Lux
 (400hrs) E.I.ave = 438Lux
- Uniformity**
 Em/ave = 0.70
- Grid values in Lux (Initial).**
 Grid interval = 5m.
 Contour values in Lux (Initial).
 Contours: 5, 15, 25, 50 Lux.
- Maintenance Factor = 0.80**

HALLIDAY

www.haliday-lighting.co.uk

Project
 Stronstone Tennis Club

Drawing Title
 Proposed floodlighting

Drawn By	Printed	Date
JM		05/07/2021
Project No	Scale	Status
2009	1:250 @ A3	Proposal
Drawing No	Drawing No	
HLS2808	HLS2808	

