

Schedule of works: Flat 8 Hodder Court

This will comprise the removal of the flat ceiling over the lounge, and the reinstatement of a flat ceiling to the underside of the existing trusses. The panes of glass within W01 and W02 are also to be replaced, but the frames will stay in place.

The new flat ceiling will be attached to the existing trusses as per the existing arrangement via batons.