

22045 – Lidl Clitheroe

Surface Water Drainage Maintenance and Management Schedule:

Soakaway

Maintenance Schedule	Required Action	Frequency
Regular Maintenance	Inspect and identify areas that are not operating correctly. If required take remedial action	Monthly for the first 3 months of operation then annually
	Recover debris from catchment surface area where it may cause risk to performance	Monthly
	Remove sediment and debris from pre-tank system	Annually
Remedial Actions	Repair inlets/outlets/vents/overflows	As necessary
Monitoring	Inspect all inlets/outlets and upstream drainage system to ensure they are in good condition and operating as designed	Annually
	Survey inside of tank for sediment and build up and remove if necessary	Every 5 years

ACO Channel/Gullies

Maintenance Schedule	Required Action	Frequency
Regular Maintenance	Remove sediment and debris from gullies and channel drain	Quarterly