

Chris Swinscoe T/A



www.cmstreeservices.co.uk

Date : 15/03/2022

Works Schedule for :

Jane
16 The Grange
Wilpshire
BB11 9JU

All tree's in the rear garden on the woodland banking.

T1-4 all Beech.

T1 is a large tall mature beech tree. Due to close proximity and growing area these trees are taller than they are wide. T1 has several major structural defects.... At approx 2m from the ground there is a large bark inclusion / tight union of one of the main competing leading stems.... This stem then extends some 40-45' above this bad union. This being the smaller stem with a lot of leverage, if it were to fail the only place foreseeable would be for it to fail and fall onto the patio area and the house. Due to the frequency in which we now get storms and the fact the target area cannot be moved, this risk is unacceptable to leave the tree in situ. This is a house hold with small children whom often play in the rear garden as it is safe away from the road and cars etc. There are several other tight unions and included bark issues on the rest of the main attachments to the stem further up and throughout this tree. This tree would have been thrown out at a nursery / not sold due to defects at a young age and is not worthy of a tpo. This site ' The Grange' in question has had a lot of dangerous foreseeable preventable failures in the last 12 months.

Removal of this tree before failure.

T2 + T3 Beech crownlift to 4.5-5m to allow better lower light levels for the garden, patio area and the back of the house.

T4 Small suppressed beech tree, remove. Tree I suppressed by others around it and is of no amenity value. Removal of this tree to allow better lower light levels for the customer. The site is surrounded by woodland and would be very little negative impact on amenity / visuals.

Acceptance of quote means automatic accept:

Please see : www.cmstreeservices.co.uk

1 Lane Bottom, Barnoldswick, Lancashir
Nptc Qualified & Fully Insured

VAT NUMBER

info@cmstrees