



Features

Maximum sash sizes

Top hung: 1400mm (w) x 1400mm (h)

Side hung: 800mm (w) x 1550mm (h)

Fixed light: 3000mm (w) x 3000mm (h)

Outer frames

56mm, 72mm and 84mm outer frames

Mullions

70mm or 95mm mullions

Sash

75mm casement sash

Finishes

Available in a large assortment of colours and woodgrain options from the Variations range and SPECTRAL*

Glazing beads

24mm sculptured

24mm bevelled

28mm sculptured

28mm bevelled

32mm sculptured

32mm bevelled

36mm bevelled

40mm bevelled

Ancillaries

Frame extensions, cills and weathering trims

Range of coupling options

Range of bay pole options

Thermal performance**

Achieves U-values as low as 1.3 W/m²K using double glazing

Achieves U-values as low as 0.95 W/m²K using triple glazing

* SPECTRAL is only available on bevelled or flat surfaces.

** Figures can vary dependent on specification.

Technical Drawing

