



320230281P

SCALE BAR in METRES

NEW NATIVE HEDGEROW -
 New hedgerows to be double row staggered planted at a density of 1m centres.
 Species composition as follows ;
 40% - Hawthorn
 30% - Blackthorn
 10% - Hazel
 10% - Holly
 10% - Crab apple

grassed areas :
 general grass seed mix - 35g/m2 in 150mm deep top soil cultivated to a depth of 150mm to form a smooth and even profile
 fertiliser - general pre-seeding fertiliser 6% n, 9% p, 6% k 70kg/m2. Included within top 25mm of topsoil.

Revisions	
Project:	PROPOSED HOLIDAY LODGE DEVELOPMENT LAND AT MORANS FARM, PENDLETON RD, NISWELL
Drawing:	site layout & landscaping
Client:	MRS. L. SAGAR
adm design	
Rydes House, Harden Road, Kellbrook, Barnoldswick, BB18 6TS Tel : 07931 557214 Email: admdesign@btconnect.com	
Scale(s)	1:200 @ A1 Date OCTOBER 2022
Drawing no.	ADP123/04/01 Rev.