



Package Pumping Stations with Extension Turret

Installation - Product Manual



Contents

Introduction and Contact Information	2
Site design	3
Driveways and Roads	3
Receipt Check	3
Preparation	4
Handling	4
Extension Turret Methodology	4
Installation.....	7
Excavation	7
Positioning	8
Civil Installation Diagram	9
Concrete Specification	11
Fabricated Steel Access Covers and Frames - Fitting Instructions	11
Control System and Explanation	13
Float Switch Setup and Adjustment	13
Electrical Connections	13
Part B Compliance	14
Commissioning of your Pumping Station	14
Impeller Rotation	14
Operation, Maintenance and Safety Procedures	15
Fault Finding Guide	16
Hygiene	18
Removal / Installation of Pumping Equipment	18
General Maintenance	18
Disposal and Recycling	19
After Sales Service	19

Introduction and Contact Information


This manual is intended to give an outline to the correct method of civil installation of your pumping station and you are advised to read the manual prior to attempting the installation of your pumping station.

When installed and maintained correctly, your pumping station should provide reliable operation over a long period. It is essential that regular maintenance and if necessary prompt repairs are carried out to ensure satisfactory and reliable operation. Therefore we urge you to use the T-T PUMPS Service Agreement system, for continued attention to your pumping station by T-T PUMPS Service Engineers.

Our products are manufactured to high standards at economic prices and are complemented by our warranty which covers all items for 12 months from date of delivery or the date of commissioning when T-T PUMPS is employed to commission the pumping station. We offer full after sales support for your pumping station for spares, repairs and servicing. For warranty claims please contact our Service Department who will always give you a prompt response.

Any enquiry made to T-T PUMPS in connection with the equipment should include these details:-

T-T Pumps Contact No.:	K11618
Original Purchaser Name:	COMPLETE PROPERTY MANAGEMENT
Customer Order Number:	CPM13/09
Pump Chamber	DUAL VENUS 50MM
Pump Type	DGO 100/2/G50H 230V



Site Design

Initial planning can save a lot of time and effort in the later stages, and we suggest that you carefully consider the following points:-

- 1) Location of pumping station, usually at the lowest ground level on site. Will it be accessible for future service work?
- 2) Will the incoming pipework have sufficient gradient?
- 3) At what level will the lowest inlet invert level be in relation to the base level of the chamber and will this allow a sufficient storage volume?

For standard installations we recommend a minimum of 1000mm below the lowest incoming inlet invert level to the base of the pump chamber to allow the pumping station to operate efficiently. For non standard installations this may have to be reduced owing to site restrictions. If in doubt please contact our Internal Sales Department.

- 4) Will the inlet and rising main pipe work be sufficiently buried underground, inline with the pipe work manufacturer's recommendations?
- 5) Will the power supply be adequate and will the size of supply cable be sufficiently sized to allow for any voltage drop?

All necessary health and safety measures must be observed during the installation process of the pumping station chamber and cover slab.

Driveways and Roads

If the pumping station is located in a driveway, it is essential that the concrete cover slab and the access cover are sufficiently rated to accept the required loading. On a Venus or Mercury pumping station, a pedestrian-loading cover is supplied as standard. This may be upgraded to suit the relevant loading requirements and a selection of covers to suit the drive way finish, i.e. block paving are available on request.

It is important that a structural engineer is employed at an early stage prior to excavation, to ensure that sufficient strength is obtained from the cover slab and access cover. A ground condition survey is also strongly recommended to ensure the correct selection of backfill concrete.

The chamber itself will not be taking any load as it acts purely as a former; the concrete around the chamber takes the loading which is directed from the access cover and cover slab so correct structural preparation is essential.

Receipt Check

Prior to your receipt of the package pumping station, the equipment has been subject to an in-house pre-delivery inspection. This is to ensure that all of the components and parts are packed correctly and reach site safely.

On receipt of delivery, please ensure that the Polythene chamber is intact and has not been damaged in anyway. Please also check that the items you have received are in accordance with your order as any claims for missing or lost items must be made within 24 hours of receipt.

A major items check-list makes up part of the delivery note for the goods; this lists the key items so that they may be thoroughly checked on delivery. Please note that any items included within the delivery notes that are not signed for will be deemed delivered and correct.

Preparation

All internal pipe work and valves will be pre-fitted inside the chamber prior to delivery. On some occasions, owing to the nature of the delivery method that we use, items such as the submersible pumps and control gear may also be packed within the chamber. Please remove all such items prior to the installation commencing.


Handling

The pumping station chamber is moulded from polyethylene with a high strength and durability, however it is of vital importance that great care is taken to prevent accidental damage arising from blows from tools or concentrated pressure on the shell from levering etc.

Similarly, sharp corners or edges of bricks and stones must be kept clear of the shell at all times. Impact from a sharp object during the handling and installation of the product could fracture the shell. The chamber must only be lifted using certified lifting slings, and under no circumstances should the pipe connections or fittings be used whilst lifting. Structural damage to the station resulting from the above will render the warranty void.


Extension Turret Methodology

1. Ensure all parts have been checked against the parts list and are all present.
2. Build up lower clamp frame - Refer to Appendix 1 - TTPS/TURRCLAMPBOT




IMPORTANT:

Ensure turret seal is installed prior to clamping.
Ensure turret is installed vertically to level seal in tank opening.



Clamp Kit: Rod Lengths	
Turret Cut height	Rod Length
Full Height	1000mm
2/3 turret	700mm
1/3 turret	400mm

Nyloc nuts to top of threaded rod, to be max. 15mm from lip of turret to allow final cover of grout/screed. Tighten no more than 2Nm to avoid deformation of the GRP tank and turret lips.




IMPORTANT:

Once the above has been completed, the turret should stand rigid within the tank.


If at this point the tank is to be located in its final position DO NOT use the turret as a lifting point, fit lifting straps securely around the tank.

ITEM NO.	PART NUMBER	DESCRIPTION	QTY.
1	TTPS-EXTURR	EXTENSION TURRET TO SUIT MERCURY/VENUS	1
2	TTPS-TURSEAL	EXTENSION TURRET SEAL 2200mm	1
3	SOT0004414 REV 5	800mm DIA CLEAR OPENING ACCESS FRAME & COVER	1
4	TTPS-MIDCLAMP	MERCURY/VENUS EXT TURRET M10 CLAMP ROD	6
5	CONSUMABLE	M10 PEE WASHER	12
6	CONSUMABLE	M10 A2-70 STAINLESS STEEL NYLOC NUT	6
7	CONSUMABLE	M10 HEX NUT ST/ST	6


Rod tightening sequence



With the tank orientated to suit the location of the incoming pipework, mark the location of the cable duct on the turret. Please consider the location of the duct, in relation to the clamping rods.



To install a cable duct in the turret, use a $\varnothing 138\text{mm}$ hole saw, and cut into turret on the narrow section.



With hole cut and cleaned of any swarf or debris, push the supplied $\varnothing 110\text{mm}$ duct seal into the opening, then install cable duct.

IMPORTANT

If guiderails are supplied loose, ensure that the orientation of the turret complete with prefitted internal guiderail bracket is correct prior to fitment.

Installation

Please refer to the schematic installation diagram on page 6 of this manual for the installation process. We recommend that you engage the services of:-

- A competent civil engineer/ building contractor for the installation of your pump chamber in the ground and pipework connections.
- A competent electrical contractor is required for all electrical items and services including the provision of the power supply and the installation and connection of the pump and control cabling.

Excavation

Please refer to page 6 diagram.

Excavate sufficiently to permit easy placing and backfilling of the pump chamber and to allow for timbering and sheeting as required. Check the incoming drain invert depth and the depth of the excavation (as recommended on page 3 of this manual), allowing for a minimum of a 250mm thick concrete foundation to subsoil, and for the minimum depth required from lowest invert to sump base.

Check alignment of the required inlet socket with inlet pipework and cut out a hole behind the required socket. This can be done with a holesaw or similar.

Please do not attempt to use a hacksaw or similar to remove the back end of the selected inlet socket as this may damage the socket design resulting in leakages.

Positioning

Place a sufficient mound of concrete (250mm deep) to act as a cradle in the centre of the excavation base and lower the pumping station into position, "puddling" it into the concrete.

Check that the chamber is vertical and that the inlet and outlet pipes are in their correct position. After the concrete base has reached its initial set (24 hours minimum), fill the chamber with water whilst backfilling. We recommend that the water should reach no more than 50mm below the outlet connection. A maximum fill rate of concrete after the base has set of 500mm is required, allowing an initial set before the next pour. Always maintain the water level above the concrete fill level until 50mm below the outlet connection is reached, thus equalizing the pressure on the wall of the chamber to prevent flotation.

Connect the inlet pipe to the selected inlet socket(s) using a minimum of a 300mm length of pipe so that the remaining inlet pipe work assembly can be connected outside the concrete surround. Use shuttering around the concrete backfill to protect the pipe work socket connection external to the concrete.

The backfill of concrete of a minimum thickness of 200-250mm should be placed carefully and consolidated frequently, to ensure that voids are not left under and around the sides of the pump well and that there are no localised stress concentrations.


It is important to ensure that the excavation is kept dry throughout the installation and until the concrete surround has cured correctly, (normally seven days, please contact your concrete supplier for information).

Two cable duct sockets are also provided on the chamber wall at a higher level for the connection of the pump and float switch cable ducting. **The cable duct sockets are to suit 110mm pipe; this is the size of ducting that must be used owing to the amount and diameter of cables that will exit the system via this duct.**

If the positioning of the cable duct sockets is not suitable for your site, alternative ducts can be made by cutting a hole into the neck of the chamber by yourselves on site.

Alternative ducts must be sealed correctly on the connection to the chamber to avoid ingress and egress of liquid.

Civil Installation Diagram




4

3


2

1

CONNECT #110mm CABLE
DUCT THROUGH SOCKET.
DUCT TO PASS THROUGH
SHUTTERING.



① BACK FILL CONCRETE / AND FILL WATER TANK.
(SHOULD BE DONE IN 500mm STAGES AS SHOWN)



General Notes:

All dimensions are to be checked on site with allowances for variations due to normal construction tolerance.

All dimensions in mm unless otherwise stated.

Drawing errors or omissions are to be reported and checked with the Design Office.

This drawing is the property of T-T PUMPS LIMITED. No portion should be copied, loaned or information herein be transferred to a third party or reproduced without the consent of T-T PUMPS LIMITED.

© Copyright T-T PUMPS Ltd. 2019

WING IS SUITABLE FOR PEDESTRIAN LOADING AREAS ONLY.
SHOULD THE INSTALLATION FALL OUTSIDE THIS AREA.
WE ARE SUPPLIED PRE-FIXED TO THE TANK/TURRET.
2 FROM FRAME FOR TANK/TURRET INSTALLATION.
IG SCREWS ARE KEPT SAFE WITH COVER AT ALL TIMES.

Rev.	Created	App	Date	Details
A	SJH	JPW	19.06.19	FIRST ISSUE
B	SJH	JPW	24.09.19	UPDATED TO SHOW AMENDED CLAMPING KIT DESIGN

Drawing Status:

APPROVED

Design & Head Office, Onneley Works,
Newcastle Road, Woore, Cheshire, CW3 9RU
Tel: +44 (0) 1630 647200 Fax: +44 (0) 1630 642100

Client :

Scheme:

T-T STANDARD INSTALL DETAILS

Drawing Title :

MERCURY/VENUS TANK CIVIL INSTALLATION
DIAGRAM.

Drawn:

Approved By:

SJH

JPW



Date : 19.06.2019

Scale : 1:50 @ A3

Drawing No :

PP/0029

Revision:

B


Sheet:

1/1


Project No : NP5040

TT339-4

TER TANK.
AS SHOWN)



② IF USING TURRET, CUT OR FULL LENGTH, ENSURE CLAMP
KIT IS IN PLACE AND SECURE.
(FULL HEIGHT TURRET SHOWN)



Concrete Specification

Please refer to EN206-1 and BS8500. The two documents must be read in conjunction.

As mentioned previously within this manual, we strongly suggest that you employ the services of a ground condition surveyor to establish the quality of the ground that the system is to be installed into, and also to provide you with a recommendation as to the type of concrete pre-mix you should use. Below is a list of information that you may find beneficial:

RC25 pre-mixed concrete is the minimum specification of concrete with a slump class of S2 for type DC1 ground conditions. For ground conditions other than DC1, it is the responsibility of the site designer or appointed ground surveyor to recommend otherwise.

The concrete must be compacted thoroughly throughout the backfilling process to eliminate the chance of voids. **Please avoid prolonged contact between the chamber wall and the concrete pokers used to avoid poker burns and damage to the chamber.**

The site designer must also take into consideration the strength and condition of the ground for this type of installation, i.e. peaty ground etc. The base of the excavation may require strengthening, also bearing in the mind the loading requirement from the cover level.


It is of vital importance that the excavation is kept dry throughout the installation process. For high ground water conditions, the use of drainage pumps will be required to keep the excavation dry. This is imperative, as the strength of the concrete backfill can be affected, resulting in irreparable damage to the chamber.


T-T PUMPS Ltd will not accept any liability for a damaged chamber which is the direct result of a poor concrete selection or installation. No claims will be considered unless a concrete certificate is provided by a certified pre-mix supplier.

Fabricated steel access covers and frames - Fitting instructions

General

1. Covers and frames are manufactured as a unit – ensure that corresponding covers and frames match and fit correctly before commencing installation.
2. The frame of an access cover must be fully supported. Any load placed onto the access cover is transferred to the structural opening via the frame. If the frame is only partially supported, the unit will not carry the load it is designed for and will ultimately fail. Please see diagrams below.
3. Recessed covers (excluding paving infill) must be fully infilled with grade C25 concrete, by volume, 1 cement, 2 sand, 3 coarse aggregate (9.5 to 3mm), to achieve their stated loading capacity.





INSTALLATION IN TRAFFIC AREAS

Single Unit Covers

For other cover designs, refer to cover specific instructions.

Duct Run Systems

- 1) Before installation check all parts (lids and frames) against the layout diagrams where issued. Where possible, installation should start at a junction or a restricted end, thus reducing the effect of creep during installation. Locking units should be offered up to the duct with the lids locked in place. On non-locking units it is acceptable to fit the framing first using the required size lid as a spacer panel.
- 2) Place the frame (and cover on locking units) around the duct structural opening. Pack up the frame to the required level with suitable hard packing material, such as tile. Care must be taken to ensure the frame does not overhang the opening. The frame is provided with fixing pads; these must be used to bolt the frame to the sub-floor.
- 3) Check that the lids do not rock in the frame. Re-pack if necessary.
- 4) Fill the unsupported areas of the frame with suitable grouting material. The underside of the frame must be fully supported.
- 5) Allow grout to harden.

Notes

1. Full fitting instructions supplied with a particular product range will supersede these instructions.
2. Covers and frames are not designed to take traffic when not fully fitted.

Control System and Explanation

The pumping station is controlled via a control panel that will be supplied as standard with the system. The basic features of this system are to control the pumps and to alert the user(s) of the system in the event of a failure which will give an audible and visual alarm locally, or remotely via a telemetry system, dependent upon the system specification.

Float switches are the standard method of level control used in conjunction with the control panel (ultrasonic level control can also be used, again dependent upon the site specifications).

Float switch set up and adjustment

For single pump stations two float switches are supplied. The duty float switch will be marked with one band of white tape and the high level will be marked with two bands. For dual systems a similar labelling method is used but in this case with the addition of a standby float which is marked with two white bands; the high level float is then marked with three bands.

The float switch assembly inclusive of lifting chain and counter weight will be pre-set at our works to provide an estimated start, stop and high level setting to suit the site and the depth of the chamber involved. If required, the settings may be changed by altering the float cable securing positions on the lifting chain. If you are not sure, please contact our Internal Sales Department for further instruction.

It is our recommendation that the high level float switch is positioned just below the lowest inlet invert position of the incoming pipe on site. This will alert you of any problem with the system prior to any surcharging of the incoming pipe work.

It is also important that on dual stations, when the standby float switch is in a raised (start) position, it is above the duty float switch raised position. The standby float switch when it is in a lowered (stop) position, must also be lower than the lowered position of the duty float.

On some system designs, the type of float switch used may be different so please always refer to the control panel drawing supplied with the system.

Electrical Connections

Please employ the services of a competent electrical engineer / contractor.

Our T-T Engineers may attend site to complete this task for you if required. Please contact our Sales Department to discuss this if you have not already received our quotation.

Before attempting to make any electrical connections, please ensure that the pump(s) is lowered into the chamber and the cable from the pump(s) is not trapped and is free. The pump and the float switch cables need to be pulled through the cable ducting on site and you must refer to the electrical wiring diagram supplied with the control system for the electrical installation.

Part P Compliance

For domestic installations, we always request that the power to our control panel equipment is provided by others and connected to our control panel so that it is live but isolated. We only make the final connections of the pump and float switch to the control panel ourselves.

It is therefore the responsibility of the person making the alterations to the electrical circuit in order to provide power to our equipment, to certify that the installation complies with Part P (by being a competent person registered with an electrical self-certification scheme authorised by the Department for Communities and Local Government). Alternatively, notification of proposals to carry out the electrical installation must be given to a Building Control body before work begins.

Commissioning of your pumping station

Having satisfied yourself that all the connections are correct, a brief test run of the system is required as follows:

Raise the pump(s) to the surface and rest on the ground so that the impeller can be seen at the base of the pump unit(s).

To test the pump on a single pump station, lift the duty float into its start position and you should see the impeller turn and the pump operate. Carry out this procedure for a few seconds only and then return the float switch back to its stop position to turn the pump off.

For dual pumping stations this procedure should be carried out twice. The first time you should see one pump running, and the second time, the other pump should operate, proving that the stepping relay within the panel is operating correctly.

The standby float on a duty standby system is purely a backup in case the initial duty float fails. To test the standby float switch on a duty-assist pumping station, carry out the procedure as above but keep the duty float in its start position and then lift the standby float into the same position. You will see that the second pump unit will also operate at the same time. Once this has been completed, return both float switches to the stop position and the pumps will turn off.

To test the high level alarm float switch, simply lift this float into its start position and it will operate the alarm features of the control panel.

Impeller Rotation

On a three-phase submersible pump, it is important to test the rotation of the impellers to ensure that the pump is wired correctly to the control panel. Carry out the duty float switch test as above and then look at the pump through the pump base so that you can see the impeller. If wired correctly, the impeller should be spinning anti-clockwise. If the impeller runs clockwise, this means that two of the phases have been wired incorrectly and need to be corrected.

Please note that care and attention must be taken at all times when carrying out the about as electrical circuits will be live and the pumps contain rotational and sometimes very sharp parts to their design.

Never use the pump cables to lift the pump, as the cable gland may be damaged allowing water into the pumps motor, damaging the motor beyond repair. Always use the lifting chains and lifting equipment provided.

Operation, maintenance and Safety Procedures

Package pumping stations can be very hazardous, and appropriate working practices must be followed at all times. The instructions and information given in this manual are as explicit as reasonably practicable and both competence and expertise are necessary in the maintenance of the system.

To ensure reliable and trouble free operation of the system, we strongly recommend that the servicing of the system is only undertaken by experienced and authorised personnel. The operation and maintenance of this system must be carried out in compliance with all current health, safety and welfare legislation.

Sewage pumping stations are safe in operation, however because of the media being pumped, gases such as methane and hydrogen sulphide can build up. It is therefore important that sensible precautions are taken.

Package Stations have been designed to be maintained from the outside of the chamber as the pump(s) and float switches are all fully removable from the chamber.

The following check list should help:-

- Never work or maintain a sewage pumping station on your own.
- Isolate the electrical supply before working on a pumping station.
- Never enter the pump chamber under any circumstances unless fully qualified to do so, i.e. confined space trained, using appropriate safety equipment.
- Keep naked flames away from pumping stations.
- Never leave the pump chamber open or unattended.
- Always secure the access cover lid when leaving the pumping station.
- Never use a wander light in or around the pump chamber unless the light is intrinsically safe.
- The Plant/Equipment must not be used for work for which it is not design intended.

Fault Finding Guide

Symptom	Possible cause	Corrective action
Pump does not start	Power supply failure or low voltage at motor	Check and rectify power supply, including check for excessive cable length or incorrect cable size causing voltage drop
	Power not switched on at all points, or connections not secure	Check all switches and cable connections
	Fuse failed or circuit breaker operated	Check fuses / circuit breaker
	Control panel overload tripped	Check setting / condition of overload unit - reset / replace. If satisfactory, investigate cause; do not reset continuously
	Control panel fault	Investigate and rectify
	Motor fault	Investigate and rectify
	Cable damaged	Replace
	Pump impeller obstructed	Clear
	Level switches obstructed or at incorrect level	Check manual switching satisfactory (except on pumps with integral level switches). Ensure level switches are correctly set to operate.
Pump does not stop	Level switches obstructed	Ensure switches are free to operate
	Control panel fault	Investigate and rectify
Pump starts and stops repeatedly	Level switches obstructed or at incorrect level	Clear or reset
	Power supply fault	Investigate and rectify, including check for voltage drop on starting
	Pump impeller obstructed	Clear
	Non-return valve(s) obstructed or faulty, allowing back flow when pump stops	Clear or repair/replace
Pump starts but overload protection trips	Overload setting incorrect	Check setting / condition - reset / replace. If satisfactory, investigate cause - do not reset continually
	Power supply fault	Investigate and rectify, including check for availability of 3 phases (for 3-phase motor)
	Connections faulty	Investigate and rectify
	Pump impeller obstructed	Clear

Symptom	Possible cause	Corrective action
Pump runs but gives no output or reduced output	Discharge obstructed	Clear pipework
	Valve(s) partly or fully closed or obstructed	Open or clear valves
	Discharge leak in pumping chamber	Secure discharge connections
	Pump impeller obstructed	Clear
	Pump impeller worn	Replace
	Pump air locked	Release air
	Pump wrong rotation	Rectify electrical connections (3 phase motor only)
	Have site parameters changed from information provided at quotation stage	Contact T-T to check design (Tel: +44 (0) 1630 647200, Email: response@ttpumps.com)
	Pump impeller obstructed	Clear
Pump runs, but noisy or vibrates	Pump / impeller air locked	Release air
	Pump impeller worn or damaged, or pump shaft damaged	Investigate and replace as necessary

Hygiene

When working on a live sewage pumping station take sensible precautions with regard to hygiene. Always wear protective overalls, gloves and footwear. When work is completed remove soiled clothing for laundering or disposal and always wash thoroughly.

Much of the equipment installed on this plant is designed to operate automatically and may start without warning. Before working on any item of the plant or equipment, ensure it is correctly, electrically and mechanically isolated.

Removal / Installation of pumping equipment

For safe removal of pumping equipment we recommend the use of a lifting davit.

Lifting davits and sockets are optional extras and are designed for lifting equipment safely from pump stations. If using a davit the following procedure should be adhered to.

- Isolate electrically and hydraulically before commencing the removal of any pump.
- Install the lifting davit in the davit socket, then locate the lifting chain in one of the holes at the top of the davit using 'D' shackle provided.
- Remove the access cover over the pump that is to be removed (do not remove more covers than necessary). Lower the chain block hook and secure in the lowest accessible large ring of the pump lifting chain.
- Begin to lift the pump and this will break the seal between the pump delivery port and the duckfoot bend and enable the pump to slide up the guide rails.
- The pump is lifted until the staging chain safety hook can be secured into the large ring on the pump lifting chain. When this has been achieved, the chain block hook can then be removed and lowered to the lowest accessible ring on the pump lifting chain and the above process repeated until the pump reaches a point above ground level. The access cover should then be closed, to aid safe working around the pump.
- The pump can then be swung round to a desired position away from the access opening.

To re-install the pump in the wet well, reverse the above procedures.

Any defects in, or damage to, plant or equipment must be reported immediately.

General Maintenance

It is important that the pumping station is checked frequently, to ensure that it is in full working order and that there is not an excessive build up of fats and materials.

If there is a build up of fatty materials, pour a reasonable quantity of household detergent onto the affected area, leave for a little while and then hose down, repeat if necessary. This will ensure that the float switches and pumps operate freely without a build up of fatty matter. In areas where large amounts of grease are expected, the fitting of a grease trap prior to the pumping station is recommended.

Disposal and Recycling



This symbol displayed here and on the product is classed as an electrical or electronic equipment and should not be disposed of with other household or commercial waste at the end of its working life. Instead, it is your responsibility to dispose of your waste equipment by arranging to return it to a designated collection point for the recycling of waste electrical and electronic equipment.

Recycling



This symbol displayed here and on the product indicates that the tank is moulded using virgin High-density Polyethylene, meaning that it can be recycled.

After sales service

Your Package Pumping Station should have a long and reliable life if it is cared for and maintained correctly. We would strongly recommend that the pumping system is serviced thoroughly at least every six months. This should be undertaken by competent electrical/mechanical engineers.

T-T PUMPS offer a full After Sales Service, including our Service Agreement Scheme. This can give you peace of mind, allowing you to achieve maximum reliability and efficiency from your Package Pumping Station.


For full details of our Service Agreement Scheme please contact our Service Department who will be pleased to give you a quotation: call +44 (0) 1630 647200.



Notes

Notes

Notes




rising main to main sewer within No41
treatment plant

rainwater red

soil blue

Aco drain



Manholes: _____

Acc: 3.5 + 4.8

Deco: _____

Gulleys: _____

Steps: _____

Square Top Edges: _____

Others: 4.8 LOWERED KERBS

1.0 KERBS KEYS (3.5 ON 3.0)

Additional Works Required? ☐ Yes ☒ No

Area 1: Drive Size (m²): 45m²

Pattern: Old English Cobble

Colour: Sideroad Buff

Release: Monogray

Area 2: _____ Size (m²): _____

Pattern: _____

Colour: _____

Release: _____

Payment Schedule


Booking Fee: £	300-00
Preparation: £	2,809.20
Concrete: £	2,809.20
Completion: £	300-00
Total: £	6,218.40

Approx. fit date: ASAP



(We accept this survey and the conditions of the contract incorporated therein, and authorise the work to be carried out.)

[illegible]


CABLE DUCT ENTRIES



GUIDERAIL BEAM & DUCT ENTRIES




TYPICAL SECTION THROUGH EXTENSION TURRET



SECTIONAL ELEVATION ON OUTLET CENTRE LINE

PLAN VIEW

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
Project: MAS STANDARD PRODUCT															
T1238-2															



Area: 3.5 + 4.8

Decor: _____

Gullies: _____

Steps: _____

Square Top Edges: _____

Others: 4.8 LOWERED KERBS

1.0 RAISED KERBS (3.5 ON STR)

Additional Works Required? ☐ Yes ☐ No

Area 1: Drive Size (m²): 4.5m²

Pattern: Old English Cobble

Colour: Bideford Kopp

Release: Mahogany

Area 2: _____

Pattern: _____

Colour: _____

Release: _____

Payment Schedule

Booking Fee: £ 300.00

Preparation: £ 2,809.20


Concrete: £ 2,809.20

Completion: £ 300.00

Total: £ 6,218.40

Approx. fit date: ASAP

(We accept this survey and the conditions of the contract incorporated therein, and authorize you to



T-T Projects Engineer's Report

2022-11-30 K11618 Complete Property
Management / Complete Property Management
Commissioning / Planned / OTHER / TeamA

Complete

Score 100% Flagged items 0 Actions 0

Project Ref 2022-11-30 K11618 Complete
Property Management

Client Complete Property
Management

Site Contact [REDACTED]

Telephone [REDACTED]

Site Attended By OTHER

Please State TeamA

Visit Type Commissioning

Planned or Unexpected Return Visit? Planned

Location [REDACTED]

What3Words (app) Exact location Details [REDACTED]

Report

100%

Site Health and Safety

Induction Completed

N/A

Permits Recieved

N/A

Report Type

K Job Installation and
Commissioning

Project Details

Liquid

Foul Water

Temporary Lifting for Install Purposes

T-T Equipment

Style

Venus

Pump Connection

Duckfoot Autocoupling

Condition of Construction

No Issues

Is Site Ready in Accordance with Received Checklist?

Yes

Test Meters Used

100%

Test Meters Used 1

100%

Test Meter Description

T-257 INSULATION AND
CONTINUITY TESTER MEGGER
MIT320

T239

Visual Inspection

Harness

Pass

Tripod

Pass

PPE (Hard Hat / Steel Toe Cap Boots Etc)

Pass

Key Components

100%

1. Power Connected to the Panel

• Check correct voltage (230V / 400V)

Yes

2. Drilled Panel and Installed Glands

Yes

3. Guide Rail System Installed	Yes
4. Lifting Chains Put Onto Pumps	Yes
5. Pump Rotation Check	Pass
6. Lowered Pumps into Chamber	Yes
7. Float Switch Assembly Made <ul style="list-style-type: none"> • Chain Cut to Correct Length • Floats Installed in Chamber 	Yes
8. Junction Boxes Installed	N/A
9. Cables Pulled Through Duct into Junction Boxes/Control Panel	Yes
10. Terminated Cables in Junction Box(es)/Control Panel	Yes
11. Valve Opened	Yes
12. Pumps Run Check	Pass
13. Check Running Current With Both Pumps in Auto	Pass
14. Float Sequence Checked	Pass
15. Overloads Set Up	Yes
16. Stop Level Checked	Pass
17. Ducts Foamed	Yes

Photo



Photo 1

18. Check Telemetry for Signal and Function	N/A
19. Station Left	Switched On in Auto

Pumps / Motors / Other Equipment	100%
----------------------------------	------

Pumps / Motors	100%
----------------	------

No of Pumps / Motors Checked	2
------------------------------	---

Pump / Motor	100%
--------------	------

Pump / Motor	1
--------------	---

Starting Method	DOL
-----------------	-----

Serial No	003789015 / 003789018
-----------	-----------------------

Pump / Motor Type	DGO100/2/80
-------------------	-------------

Full Load Current (A)	6.5
-----------------------	-----

Winding Resistance (Ω)	3-7-10
---------------------------------	--------

Insulation Resistance (M Ω) Please Note: Insulation Resistance MUST be greater than 1 M Ω to meet electrical safety standards	1000
--	------

Capacitors (μ f)	25
-----------------------	----

Starting Amps (A)	N/A
-------------------	-----

Running Amps (A)	6.7
------------------	-----

Hours Run	N/A
-----------	-----

Impeller Rotation/Direction Physically checked	Yes
--	-----



Photo 2

Pump / Motor Removed?	No
-----------------------	----

Equipment Status

Equipment Present?	Yes
--------------------	-----

Supply Type	230V 1 Ph 50Hz
-------------	----------------

Pump Power Rating (kW)		0.88
Control Voltage	24V AC	
Other Relevant Equipment		100%
Ultrasonic Present and settings not changed from TT Test Parameters - these are as per US parameter sheet TT-214 issued by TTC Design	N/A	
Parameter Amended (please state parameter & value)		N/A
Parameter Amended (please state)		N/A
Parameter Amended (please state)		N/A
Parameter Amended (please state)		N/A
Other Relevant Equipment?	N/A	

End of Report

100%

Engineers Report and Details of Additional Work

100%

Engineer's Notes and Recommendations

Attended site to install and commission pump station.
All equipment located and brought round to chamber , mains power connected and tested all ok.
Pump chains fitted to pump and cables dressed in chamber before pulling through duct and terminated into control panel.
Floats fitted to chamber , cables dressed before pulling through duct and terminated into control panel.
16mm earth fitted to chamber and bonded to pump chain hooks , earth pulled through duct and terminated into control panel, Duct sealed with rise once finished.
Station turn on and pumps lifted to carry out directional check all ok.
Floats checked for correct operation and all ok
Earth bonding checked end to end all ok
Station proven to pump and stop level witnessed. Overloads set to correct current.

Station left switched on and in auto



Photo 3



Photo 4



Photo 5



Photo 6



Photo 7



Photo 8



Photo 9



Photo 10



Photo 11



Photo 12

Parts Required to Complete

None

Parts Missing from Parts List

None

Parts Left on Site

N/A

Kiosk Keys Handed to (State Name)

N/A

T-T Site Supervisor

100%

Name and Signature



[Redacted]

Accompanying Engineer

100%

Accompanying Engineer 1

100%

Name

Other

[Redacted]

Report Signed Off as

Commissioning Complete

Customer Present?

Yes

Customer Name and Signature

[Redacted]

Customer not available when leaving due to overnight travel and gone bed on site electrician signed report

Exiting Site - HouseKeeping

100%

All TT Packaging/Rubbish/Waste removed from site

N/A

**All surrounding area's left free of obstacles, clean & Tidy
(Unless Stated on previous issues within report)**



Customer needs to secure lid



Photo 13

**Product removed from site to be returned / disposed of at TT
works for appropriate repair/ disposed of in applicable waste
stream**

N/A

Site Attendance Record

Site Attendance Record

Day

Day 1

Date and Time On-Site	30.11.2022 08:46 GMT
------------------------------	----------------------

Date and Time Off-Site	30.11.2022 12:46 GMT
-------------------------------	----------------------

Gas Readings

Confined Space Entry Required?

No

Appendix



Photo 1



Photo 2



Photo 3



Photo 4



Photo 5



Photo 6



Photo 7




Photo 8



Photo 9



Photo 10



Photo 11



Photo 12



Photo 13





better together

Data sheet

DO 100/2/G50H A0CM5

Technical specification

1~ 50 Hz

[mm]
[inch]

Pump

Series	O series
Type	DO 100/2/G50H A0CM5
Version	T 05NN 230D NN NN
Standard	EN 809:2009

Operating limits (standard pumps)

Max. ambient temperature	40 °C
Max. density treated liquid	1100 kg/m ³
pH treated liquid	6 ÷ 14
Max. start per hour (equally distributed)	30
Wet/dry use	WET
Max. acoustic pressure level	70 dB
Operating mode	S1 - Continuous use

Motor data

Rated voltage	230 V
Frequency	50 Hz
Motor phases	1~
Number of poles	2
Rated power P2	0.88 kW
Incoming power P1	1.40 kW
Rated current	6.5 A
rpm	2900 1/min
cos φ	0.94
Rated torque	2.9 Nm
Start	
Degree of protection	IP 68
Insulation class	F

Construction materials

Case	Cast iron EN-GJL 250
Shaft	Stainless steel AISI 431
Hydraulic	Cast iron EN-GJL 250
Impeller	Cast iron - EN-GJL 250
Painting/Coating	Bi-epoxy 120 μm
Screws	Stainless steel - Class A2-70
Gaskets	NBR
Foot base (if present)	

Construction features

Main cable	4G1
Control cable	-
Cable length	5 mt
Mechanical seals	1 in silicon carbide (SiC) and 1 in alumina graphite (AL)
Additional drilling	-
Weight*	19.5 kg
Electrical variant	Thermal protection

* cable and fixing system excluded

Hydraulic

Type	DG (Set-back Vortex)
Free passage	50 mm
Impeller type	Set-back Vortex impeller
Max. hydraulic efficiency	
Suction	-
Discharge	DN 50 - G2" EN 1092-2
Curve tolerance	UNI EN ISO 9906:2012




better together

Data sheet
DGO 100/2/G50H A0CM5

Pump performance curves

1~ 50 Hz

Hydraulic type DG (Set-back Vortex)		Impeller type Set-back Vortex impeller	Free passage 50 mm	Discharge DN 50 - G2"	Suction -
DUTY POINT					
Flow 4.5 l/s	Head 7.6 m	Shaft power P2	Hydraulic efficiency	Density 998.3 kg/m ³	Viscosity 1.005 mm ² /s



All data shown are not binding. Zenit reserves the right to change data and dimensions without notice.

zenit.com

Created on 2022-08-19

Page 2 / 3



better together


Data sheet

DGO 100/2/G50H A0CM5

Dimensional drawing

1~ 50 Hz

Installation type Installation with bottom coupling device - Vertical outlet + GTP		
Wet/dry use WET	Drilling variant N	Flushing valve - drilling -
Discharge DN 50 - G2" EN 1092-2	Suction: -	Pressure rating (suction/discharge): PN 10
Accessory DAC 32-50/G50V-G65V 3/4" EN+GTP (P)		Accessory code 9028.002
Note: Accessory must be ordered separately		



L1: Minimum operating level for continuous use

L2: Minimum operating level for discontinuous use

All data shown are not binding. Zenit reserves the right to change data and dimensions without notice.

zenit.com

Created on 2022-08-19

Page 3 / 3