



REF: BOOTHS

CASE MATERIAL : GALV/POWDER COATED

FIN MATERIAL : Alup

TUBE MATERIAL : 5/16 0.9 COPPER TUBE

800mm DIAMETER EC FANS

INDIVIDUAL ISOLATORS FITTED TO FAN GUARD BRACKET

1 x 1 5/8" K65 INLETS

1 x 1 5/8" K65 OUTLETS

EC CONTROL PANEL FITTED AT HEADER END WITH RAIN SHEILD

HINGED TOPS SHOWING OPTION 1

PLEASE SEE DRG 1902-7525 FOR ALTERNATIVE OPTIONS

500mm LEG EXTENSIONS 1000mm UNDER UNIT

ADIABATIC SYSTEM FITTED

DRY WEIGHT = 1179 kg

TOLERANCES UNLESS OTHERWISE STATED		REVISION	E		
0-100	±1		D		
100-500	±2		C		
500-1000	±3		B		
1000-2000	±4		A		
2000-4000	±6			DATE	NAME

CUSTOMER **BLUE COOLING**

DESCRIPTION **AFR-ZAP-EC-146-ECMP-700-H**

DRG NO	2210-8849	
DRG SCALE	1:50	
DATE	27/10/22	
DRAWN & CHECKED BY	GC	