

Description

The IP65 driverless range of QuaZar™ floodlights incorporate the latest in high voltage LED technology. With their ultra slim profile and high performance, now you can light your external areas and gardens without sacrificing the appearance. Available in 10W, 20W, 30W and 50W versions including black and white housing finishes to suit external fascias.

**SLIM PROFILE
HIGH PERFORMANCE**

**up to 4500 Lumens
L70 25,000 Hours**

Features & Benefits

- IP65 rated LED floodlight with ultra slim design for minimal visual impact
- Mains voltage LED chips - no driver for improved reliability
- IK08 rated aluminium housing and tempered glass provides excellent protection
- Available in black and white finish housing
- Pre-wired with 600nm of cable
- 1.5KV surge protection
- 3 year warranty*



EN-FLHV10
10W Adjustable IP65
Driverless LED Floodlight



EN-FLHV20
20W Adjustable IP65
Driverless LED Floodlight



EN-FLHV30
30W Adjustable IP65
Driverless LED Floodlight



EN-FLHV50
50W Adjustable IP65
Driverless LED Floodlight

Cat. No.	Watts	Colour	Lumens	lm/W	L70 Life (hrs)	H x W x D (mm)	Halogen Subst.
EN-FLHV10*/30	10W	3000K	800lm	80	25,000	90 x 130 x 33mm	60W
EN-FLHV10*/40	10W	4000K	800lm	80	25,000	90 x 130 x 33mm	60W
EN-FLHV10*/65	10W	6500K	800lm	80	25,000	90 x 130 x 33mm	60W
EN-FLHV20*/30	20W	3000K	2000lm	100	25,000	125 x 181 x 34mm	100W
EN-FLHV20*/40	20W	4000K	2000lm	100	25,000	125 x 181 x 34mm	100W
EN-FLHV20*/65	20W	6500K	2000lm	100	25,000	125 x 181 x 34mm	100W
EN-FLHV30*/30	30W	3000K	3000lm	100	25,000	183 x 211 x 37mm	150W
EN-FLHV30*/40	30W	4000K	3000lm	100	25,000	183 x 211 x 37mm	150W
EN-FLHV30*/65	30W	6500K	3000lm	100	25,000	183 x 211 x 37mm	150W
EN-FLHV50*/30	50W	3000K	4500lm	90	25,000	190 x 274 x 42mm	200W
EN-FLHV50*/40	50W	4000K	4500lm	90	25,000	190 x 274 x 42mm	200W
EN-FLHV50*/65	50W	6500K	4500lm	90	25,000	190 x 274 x 42mm	200W

* Add suffix **W** or **BLK** for White or Black finish
* Warranty covers LED chip

Technical Information



Finish Options:

