

ELEVATION

SECTION

**Specification**

**General**

All components of the fencing are to be in accordance with the details and recommendations of B.S. 1722 Part 7 to which reference is made. The following is a brief synopsis of the content of the standard :-

**Posts**


Timber posts are to be 100mm diameter. Posts are to be set at 1800mm centers measured center to center of posts and are to be set in the ground to a depth of 600mm.

**Preservative Treatment**

Timber shall be treated in accordance with the requirements for fencing timber B.S. 5589 to give a category B (20 year) service life.

**Rails**

Rails should have a section of 38mm x 87mm Fixed to the Posts using 2No. 4mm x 100mm galvanised steel nails, at each post.



Drawing Title 1200 Post & 4 Rail Fence		Date 01/23	Scale 1/20@A3	Drawn / Checked by -
Drawing Status Planning Detail		Drawing Ref LSD.BT.F04.01	Rev -	

Revision		ad/mn/yy
Development		
Persimmon Homes Lancashire Standard Detail		