# PD Construction Consultants

7 Beech Street, Clitheroe, Lancs. BB7 2LL Paul Derbyshire Dip. Surv.

# ACOUSTIC INSULATION ASSESSMENT AND SPECIFICATION PROPOSED ALTERATIONS, 10 BRIDGE ROAD, CHATBURN, LANCS., BB7 4AW

#### 1. Introduction

This document provides an assessment of the acoustic insulation properties existing fabric of the building and the addresses the actions required to provide acoustic insulation to attain compliance with Building Regulations Approved Document, Part E1 & E2, 2015 – Resistance to Passage of Sound.

Any remedial specifications are designed to match or exceed the stipulated levels required by Building Regulations.

In preparing this assessment reference has been made to technical information contained within:

- "The British Gypsum White Book"
- "Robustdetails® Technical Handbook September 2023".
   The robustdetails® scheme is an alternative to pre-completion sound testing to satisfy Approved Document E of The Building Regulations

#### 2. The Existing Structure

# Party Wall:

The measured survey indicates that the ground floor width is 145mm narrower than at first floor level. The site survey inspection of an exposed section of party wall at ground floor level revealed random limestone in the party wall. At first floor level adjacent to no. 8 Bridge Road header courses were clearly visible indicating that the party wall is one brick thick. Basic interpolation of the survey photos and site measurements supports this with the ground floor party wall being 585mm width and the first floor party wall being 440mm. (plaster thickness has been discounted from these measurements).

The worst case scenario is that the party wall is 440mm thick clay brick and this is used for assessing the acoustic properties of the existing building.

#### First Floor:

The first floor comprises 25mm thick softwood timber board over  $175 \times 50$ mm softwood timber joists at 400mm centres. The ceiling finish to the underside is 12.5mm thick plasterboard with a plaster skim finish.

#### 3. Acoustic Assessment of the Existing Structure

## Party walls:

One brick thick walls with an unplastered can achieve a sound reduction index of 45dB. The nominal density of clay brick being 1690kg/m³

## First Floor:

Typically this type of timber floor construction would result in noise levels 78dB for Impact noise and 38dB for Airborne noise

## 4. Matters to address

The proposed alterations require that the works are to comply with Building Regulations Approved Document E.

Section 0: Performance, Table 0.1a details the minimum performance standards required for walls and floors to satisfy the requirements of Part E1 & E2.

Table 0.1a Dwelling-houses and flats - performance standards for separating walls,
separating floors, and stairs that have a separating function


	Airborne sound insulation sound insulation $D_{nT,w} + C_{tr} dB$ (Minimum values)	Impact sound insulation  L'n,w dB  (Maximum values)
Purpose built dwelling-houses and flats		
Walls	45	_
Floors and stairs	45	62
Dwelling-houses and flats formed by material change of use	-40	
Walls	43	1.50
Floors and stairs	43	64

Extract from Approved Document E

#### 5. Action Required to Comply with Approved Documents

# Party Wall:

Repair / replace plaster finishes to party walls. This will achieve an Airborne sound index of 50db > 43dB minimum requirement.




- minimum mass per unit area including plaster 375kg/m²;
- 13mm plaster on both room faces;
- · bricks to be laid frog up, coursed with headers.

#### Example of wall type 1.3

The required mass per unit area would be achieved by using

- 215mm brick
- brick density 1610kg/m³
- 75mm coursing
- 13mm lightweight plaster (minimum mass per unit area 10kg/m²) on both room faces

This is an example only. See Annex A for a simplified method of calculating mass per unit area. Alternatively use manufacturer's actual figures where these are available.




#### Extract from Approved Document E

## First Floor:

The Impact noise level needs reducing to at least 64dB, and the Airborne sound level needs increasing to a minimum of 43dB.

In addition to achieving compliance with Approved Document E, the first floor between the newly formed commercial ground floor and the domestic flat at first floor needs to comply with Building Regulations Approved Document B: Fire Safety. The floor structure needs to be 60 minutes fire resistant, so the existing structure will need to be upgraded.



Extract from British Gypsum White Book

Existing ceiling to be removed and replaced with 2no layers British Gypsum Soundblock fixed to RB1 resilient bars at 450mm centres. 100mm Isover General Purpose Roll between joist with minimum 22mm

timber board finish over. This provides Impact noise reduction to 60 dB < 64 dB and Airborne sound reduction increase to 54 dB > 43 dB

Signed:



Paul Derbyshire Dip. Surv.

Dated: 27<sup>th</sup> September 2023