

NOTES

PLAY AREA SCHEDULE

A DRAGONFLY PLAY SCULPTURE
Timber crocodile dragonfly by Handmade Places BX/HMP 350007.

B STEPPING LOGS
Timber stepping logs - 6 no. 300mm diam, 250mm high and 400mm apart. Tops to be chamfered.

C WOBBLE BRIDGE
Timber Wobble Bridge by Handmade Places BX/HMP3 100030.

D TRACTOR SPRINGY
Tractor springy by Broxap Ltd - BX/PD 300018.

E COW SPRINGY
Cow springy by Broxap Ltd - BX/PD 300005.

F SEATING
2 no. benches to be Woodscapes Excel Backrest Seat with ground fixing.

G BINS
To be furnitube Boston Litter Bin BOS 490T In-ground fixed litter bin
Steel-frame in black plastic coated finish, iroko slats in Sadolin stain Steel liner, capacity 80 litres, with facility to secure with padlock. To be set into 300 x 300 x 450 deep foundation. Furnitube Tel: 0208 3783200.




SURFACING
1. Main path through site to be bitmac with Marshalls charcoal keyblock edging 200x100x60mm running stretcher/running bond.
2. Area containing dragonfly play sculpture and stepping logs to be rubber crumb wetpour in blue.

FENCING
To be mild steel Anti Trap Bow Top fencing with a wider gap between each hoop above the top rail, to prevent children getting their heads, necks or limbs stuck between pales. To fully conform to play fence standards in BS EN 1176. To be Hot dip galvanised and powder coated to BS EN 13438 Colour: Black RAL 9005. 19mm pales with domed top caps, 2737mm wide panels, Posts 60.3 dia x1500mm. Posts to be set into concrete footings.

GATES
To be self closing gate options, with an in-ground operator with adjustable closing rate and soft close feature to ensure that the gate returns to the closed position after use preserving the integrity of the perimeter and prevents slamming and trapped fingers.

All fencing and gates to be Jackons Fencing Anti trap Bow Top fencing and Anti Trap Bow Top gate Tel: 01829 770 776

KEY

-  Proposed wetpour safety surface finished in blue (to manufacturer's recommended depths)
-  Proposed tarmac path
-  Proposed 1000mm high vertical metal railing powder coated colour: RAL 9005

Rev.A: Play space enlarged and additional equipment positioned (SF) June 2024

<div><div>Sue Farmer BA MALD MLI Landscape Architect</div><div>fdalandscape</div><div>Westleigh Hall Wakefield Road Denby Dale Huddersfield HD8 8QJ telephone 01484 861611 fax 01484 861616 isdn 01484 866900 email info@fdalandscape.co.uk www.fdalandscape.co.uk</div></div>				client Kier Living			
				project Residential Development PRESTON ROAD, LONGRIDGE			
				drawing title LAP DETAILS			
scale 1:100 @A2	date May 24	drwn by SF	drawing no R/2012/24A				